

## PROPOSED CONSTRUCTION OF PAVI KWALE CO-OPERATIVE UNION GINNERY AT KINONDO, KWALE COUNTY PHASE 1 (ONE)

#### **TENDER DOCUMENTS**

### MOC&MSME/SDC/SCM/002/2023-2024 WP ITEM NO. D116/CO/KWL/2001 - JOB NO. 10826A

#### **VOLUME 1 OF 3**

#### **CLIENT**

# STATE DEPARTMENT FOR CO-OPERATIVES P.O.BOX 30547-00800 NAIROBI

PROJECT MANAGER
WORKS SECRETARY
S.D.P.W
P.O.BOX 30743-00100
NAIROBI

QUANTITY SURVEYOR
CHIEF QUANTITY SURVEYOR
S.D.P.W
P.O.BOX 30743-00100
NAIROBI

ARCHITECT
CHIEF ARCHITECT
S.D.P.W
P.O.BOX 30743-00100
NAIROBI

ELECTRICAL ENGINEER
CHIEF ENGINEER (ELECTRICAL)
S.D.P.W
P.O.BOX 30743-00100
NAIROBI

CHIEF ENGINEER (STRUCTURAL) S.D.P.W	CHIEF ENGINEER (MECHANICAL-B.S) S.D.P.W
P.O.BOX 30743-00100	P.O.BOX 30743-00100
NAIROBI	NAIROBI
OCT	OBER, 2023

# PROPOSED CONSTRUCTION OF PAVI KWALE CO-OPERATIVE UNION GINNERY AT KINONDO, KWALE COUNTY PHASE I (ONE) WP ITEM NO. D116/CO/KWL/2001 - JOB NO. 10826A

#### **TENDER DOCUMENTS**

#### **Consisting**

A	Contents page			
В	Signature and	Special notes page		(ii)
C	Standard Tend	er Documents for Procurement of Works:		
	Section I:	Instructions to Tenderers		1
	Section II:	Tender Data Sheet (TDS)		18
	Section III:	Evaluation and Qualification Criteria		22
	Section IV:	Tendering Forms		28
	Section V:	Bills of Quantities		60
	Section VI:	Specifications		73
	Section VII:	Drawings		73
	Section VIII:	General Conditions of Contract (GCC)		74
	Section IX:	Special Conditions of Contract (SCC)		130
	Section X:	Contract Forms		132
D	Preliminaries		P/1	
E	Preambles and pricing notes PN/1			
F	Measured Works			BW/1
G	Provisional Sums			PS/1
Н	Grand Summary			

# PROPOSED CONSTRUCTION OF PAVI KWALE CO-OPERATIVE UNION GINNERY AT KINONDO, KWALE COUNTY PHASE I (ONE) WP ITEM NO. D116/CO/KWL/2001 - JOB NO. 10826A

Prepared by: -

Quantities and Contracts Department, State Department for Public Works, Ministry of Lands, Public Works, Housing & Urban Development P. O. Box 30743-00100, Nairobi.

Date :	_
THE CONTRACTOR	PRINCIPAL SECRETARY STATE DEPARTMENT FOR CO-OPERATIVES
contract.	ou thereto, shall be read and construct as part of the said
	OPMENT and public General Specification dated March, ed thereto) shall be read and construed as part of the said
•	r Documents and the MINISTRY OF LANDS PUBLIC
The confider for the above mentioned work	s entered into this day of

#### **SPECIAL NOTES**

The Contractor is required to check the numbers of the pages of these Bills of Quantities and should he find any missing or in duplicate or figures indistinct he must inform the Principal Secretary for State Department for Public Works, Head Office, Ngong Road, Nairobi at once and have the same rectified.

Should the Contractor be in doubt about the precise meaning of any item or figure for any reason whatsoever, he must inform the Principal Secretary, State Department for Public Works, Head Office in order that the correct meaning may be decided before the date for submission of tenders.

No liability will be admitted nor claim allowed in respect of errors in the Contractor's Tender due to mistakes in the specifications, which should have been rectified in the manner, described above.

#### SIGNATURE PAGE AND NOTES



### TABLE OF CONTENTS

	PREFACE				
APPI	ENDIX TOTHE PREFACE				
•••••	v GUIDELIN	ES FOR			
PREF	PARATION OF TENDER DOCUMENTS				
3. P.	ART 1 - TENDERING PROCEDURES ART 2 - PROCUREMENT ENTITY'S REQUIREMENTS ART 3 - CONDITIONS OF CONTRACT ANDCONTRACTFORMS	vi			
INVI viii	ITATION TOTENDER	•••••••••••••••••••••••••••••••••••••••			
PAR	T 1:TENDERING PROCEDURES	•••••			
	CTION I - INSTRUCTIONSTOTENDERERS				
	GENERALPROVISIONS				
1.0	Scope of tender				
2.0	Fraud and corruption				
3.0	Eligible tenderers				
4.0 5.0	Eligible goods, equipment, and services				
В. С	CONTENTS OFTENDER DOCUMENTS	•••••			
4					
6.0	Sections of Tender Document				
7.0	Clarification of Tender Document, Site Visit, Pre-tender Meeting	4			
8.0	Amendment of Tender Documents	5			
10.0	Language of Tender.	5			
11.0	Documents Comprising the Tender				
12.0	Form of Tenderand Schedules				
13.0	AlternativeTenders				
14.0	Tender Pricesand Discounts	6			
15.0	Currencies of Tenderand Payment				
16.0	Documents Comprising the Technical Proposal				
17.0	Documents Establishing the Eligibility and Qualifications of TheTenderer				
	Period of Validity of Tenders				
	Tender Security				
20.0	Format and Signing ofTender	9			
<b>D.</b> Si	UBMISSION AND OPENINGOFTENDERS1	•••••••••••••••••••••••••••••••••••••••			

	21.0	Sealing and Marking of Tenders	11
	22.0	Deadline for Submission of Tenders	11
	23.0	LateTenders	
l 1			
	24.0	Withdrawal, Substitution, and ModificationofTenders	
	25.0	Tender Opening	12
	15 15	VALUATION AND COMPARISONOFTENDERS	
			••••••
	12		
	26.0	Confidentiality	
		Clarification of Tenders	
		Determination of Responsiveness	
	30.0	Non-material Non-conformities	
	31.0	Arithmetical Errors	14
	33.0	Margin of PreferenceandReservations	14
	34.0	Nominated Subcontractors	14
	25.0	Frahratian aftandara	1.5
		Evaluation of Tenders	
	36.0	Comparison of tenders	
	37.0	Abnormally low tenders and abnormally high tenders	13
	Abno	rmally	LowTenders
			2011 10110011
		mally high tenders	
	38.0	Unbalanced and/or front-loaded tenders	
	39.0	Qualifications of the tenderer	
	40.0	Lowest evaluated tender	
	41.0	Procuring entity's right to accept any tender, and to reject any oralltenders	16
	E A	WARD OFCONTRACT	
	г. А	17	
	•••		
	42.0	Award criteria	17
	43.0	Notice of intention to enter into a contract	17
	44.0	Standstill Period	17
	44.0	Standstill Period	17
	45.0	Debriefing By TheProcuring Entity	17
	46.0		Letter of Award
	47.0	Signing of Contract	
	48.0	Performance Security	
	49.0	Publication of Procurement Contract	
	50.0	Procurement related Complaint and Administratrive Review	18
		ΓΙΟΝ II - TENDER DATASHEET(TDS)	
	•••••	18	
		FION III - EVALUATION AND QUALIFICATION CRITERIA	
		22	
	1.	0 01101 111 1110 1110 110 1110 110 110 110 1110 110 110 110 110 110 110 110 110 110 110 110 110 110 110 110	
	2.	Preliminary examination for Determination of Responsiveness	

3.	4.	Multiple	Contracts
5.	AlternativeTenders		
6.	•		
7.		t ward	
8.	QUALIFICATION FORM		25
		s	
1.		ULE	
3.			
5.	TENDERERS QUALIFICAT	IONWITHOUTPRE-QUALIFICATION	33
OTHE	ER FORMS		43
1.	FORM OF TENDER		43
	a) TENDERER'S ELIGIBILIT	TY- CONFIDENTIALBUSINESS QUESTION	NAIRE46
		b) CERTIFICATE OF INDEPENDENT	TENDERDETERMINATION50
	c) SEI	LF-DECLARATION FORM - SELF DECLAR	
			PPENDIX 1 - FRAUD AND
		CORRUPTION	54
2.	FORM OF TENDER SECURIT	Y – DEMAND BANKGUARANTEE	56
		Y (INSURANCE GUARANTEE)	
		G DECLARATION	
5.	APPENDIX TO TENDER		59

ii

SECTION V – BILLS OF QUANT					
1. PREAMBLES					
Bill No. 1 – Preliminary Items					
Bill No. 2: Work Items Bill No. 3: Schedule of Daywo					
Bill No. 3: Schedule of Daywo					
Bill No. 3: Schedule of Daywo					
Bill No. 3: Daywork Summary					
Bill No. 4: Provisional Sums					
9. GRAND SUMMARY			•••••		72
SECTION VI - SPECIFICATION 73	S	••••••		•••••	•••••
SECTION VII - DRAWINGS			72		
SECTION VIII - GENERAL CON					74
1. General Provisions		,			
The Procuring Entity					
3. The Engineer					
The Contractor					
5. Nominated Subcontractors					
6. Staff and Labor.					
7. Plant, Materials and Workmansh					
8. Commencement, Delays and Sus					
9. Tests on Completion					
10. Procuring Entity's Taking Over .					
11. Defects Liability					
12. Measurement and Evaluation					
13. Variations and Adjustments					
14. Contract Price and Payment					
15. Termination by Procuring Er					
16. Suspension and Termination by 0	Contractor				117
17. Risk and Responsibility					119
18. Insurance					
19. Force Majeure					
20. Settlement of Claims and Disput	es				126
Section IX - Special Conditions of 130	Contract	••••••	•••••••••••••••••••••••••••••••••••••••	•••••	***************************************
SECTION X – CONTRACT FOI	RMS			•••••	132
FORM No. 1 -	133				
FORM No. 2 –REQUEST FOR REV					
FORM No. 3 – LETTER OF AWAR					
FORM No. 4 – CONTRACT AGRI					
FORM No. 5 - PERFORMANCE SI	ECURITY [Option 1 - Uno	conditional	l DemandBank Guar	antee]	13′

FOR	RM No. 6- PERFORMANCE SECURITY [Option 2 – Performance Bond] 138 RM No. 7 – ADVANCE PAYMENT SECURITY 140 RM No. 8 – RETENTION MONEY SECURITY 141 RM No. 9 – BENEFICIAL OWNERSHIP DISCLOSURE FORM 142
	NDER DOCUMENTS FOR <u>PROCUREMENT OF WORKS (BUILDING AND ASSOCIATED</u> VIL ENGINEERING WORKS)
	1)NAME AND CONTACT ADDRESSES OF PROCURING ENTITY
	Name: STATE DEPARTMENT FOR CO-OPERATIVES Address: P.O. Box 30547- 00100, Nairobi
	Email address.
2)	Invitation to Tender (ITT) No: W.P. ITEM NO. D116 CO/KWL/2001 JOB NO. 10826A
3)	Tender Name: PROPOSED CONSTRUCTION OF PAVI KWALE CO-OPERATIVE UNION GINNERY AT KINONDO, KWALE COUNTY PHASE I (ONE)

#### **INVITATION TO TENDER**

**PROCURING ENTITY: STATE DEPARTMENT FOR CO-OPERATIVES** 

**CONTRACT NAME AND DESCRIPTION: : PROPOSED** 

CONSTRUCTION OF PAVI KWALE CO-OPERATIVE UNION

GINNERY AT KINONDO, KWALE COUNTY PHASE I (ONE)

- 1. The *Principal Secretary, State Department for Co-operatives* invites sealed tenders for the *Proposed Construction of PAVI Kwale Co-operative Union Ginnery at Kinondo, Kwale County Phase I (one)*
- **2.** Tendering will be conducted under National open competitive method using a standardized tender document. Tendering is open to all qualified and interested Tenderers.
- 3. Qualified and interested tenderers may obtain further information and inspect the Tender Documents during office hours 0800 to 1700 hours at NSSF Building Block B, 16<sup>th</sup> Floor.
- 4. A complete set of tender documents may be purchased or obtained by interested tenders upon payment of a non- refundable fees of Kshs. 1,000.00 in cash payable at Cash Office NSSF Building Block B 10<sup>th</sup> Floor or Banker's Cheque. Tender documents may be obtained electronically from the following links <a href="http://ushirika.go.ke">http://ushirika.go.ke</a> or the Public Procurement Information Portal at <a href="https://tenders.go.ke/">https://tenders.go.ke/</a>. Website and should register the same in our procurement office situated at NSSF Building, Block A Eastern Wing 16<sup>th</sup> Floor.
- 5. Tenders shall be quoted be in Kenya Shillings and shall include all taxes. Tenders shall remain valid for 126 days from the date of opening of tenders.
- **6.** All Tenders must be accompanied by a *tender Security* of *Kenya Shillings 1,300,000.00*
- 7. The Tenderer shall chronologically serialize all pages of the tender documents submitted.
- 8. Completed tenders must be delivered to the address below on or before 7<sup>th</sup> November 2023, 10.30 am Electronic Tenders will not be permitted.
- 9. Tenders will be opened immediately after the deadline date and time specified above. Tenders will be publicly opened in the presence of the Tenderers' designated representatives who choose to attend at the address below.
- 10. Late tenders will be rejected.
- 11. The addresses referred to above are:

#### A. Address for obtaining further information and for purchasing tender documents

- (1) Name of Procuring Entity: STATE DEPARTMENT FOR CO-OPERATIVES
- (2) Physical address for hand Courier Delivery to an office or Tender Box

State Department for Cooperatives.

Social Security Building, Nairobi.

Bishop Road

P.O Box 30547 – 00100

(1) Contact Person Name: Hillary Kemboi, Phone; 0725790243 email: procurement@ushirika.go.ke

	В.	<b>Address</b>	for	Subm	ission	of	<b>Tenders.</b>
--	----	----------------	-----	------	--------	----	-----------------

- (1) Name of Procuring Entity: STATE DEPARTMENT FOR CO-OPERATIVES
- (2) Postal Address: P.O. Box 30547-00100, Nairobi
- (3) Physical address for hand Courier Delivery to an office or Tender Box

State Department for Cooperatives.

Social Security Building, Nairobi. Bishop

#### Road

#### C. Address for Opening of Tenders.


- 1) Name of Procuring Entity: STATE DEPARTMENT FOR CO-OPERATIVES
- 2) Physical address for the location:

State Department for Cooperatives.

Social Security Building, Nairobi.

Bishop Road

Principal Secretary,	State Department for Co-operatives
Name	
(	(Official of the Procuring Entity issuing the invitation)
Designation	
Signature	





#### **SECTION I - INSTRUCTIONS TO TENDERERS**

#### A GENERAL PROVISIONS

#### 1.0 Scope of tender

- **1.1** The Procuring Entity as defined in the Appendix to Conditions of Contract invites tenders for Works Contract as described in the tender documents. The name, identification, and number of lots (contracts) of this Tender Document are specified in the TDS.
- **1.2** Throughout this tendering document:
  - a) The term "inwriting" means communicated in written form (e.g. by mail, e-mail, fax, including if specified in the TDS, distributed or received through the electronic-procurement system used by the Procuring Entity) with proof of receipt;
  - b) if the context so requires, "singular" means "plural" and vice versa;
  - c) "Day" means calendar day, unless otherwise specified as "Business Day". A Business Day is any day that is an official working day of the Procuring Entity. It excludes official public holidays.

#### 2.0 Fraud and corruption

- **2.1** The Procuring Entity requires compliance with the provisions of the Public Procurement and Asset Disposal Act, 2015, Section 62 "Declaration not to engage in corruption". The tender submitted by a person shall include a declaration that the person shall not engage in any corrupt or fraudulent practice and a declaration that the person or his or her sub-contractors are not debarred from participating in public procurement proceedings.
- **2.2** The Procuring Entity requires compliance with the provisions of the Competition Act 2010, regarding collusive practices in contracting. Any tenderer found to have engaged in collusive conduct shall be disqualified and criminal and/or civil sanctions may be imposed. To this effect, Tenders shall be required to complete and sign the "Certificate of Independent Tender Determination" annexed to the Form of Tender.
- **2.3** Tenderers shall permit and shall cause their agents (whether declared or not), subcontractors, sub-consultants, service providers, suppliers, and their personnel, to permit the Procuring Entity to inspect all accounts, records and other documents relating to any initial selection process, pre-qualification process, tender submission, proposal submission, and contract performance (in the case of award), and to have them audited by auditors appointed by the Procuring Entity.
- **2.4** Unfair Competitive Advantage Fairness and transparency in the tender process require that the firms or their Affiliates competing for a specific assignment do not derive a competitive advantage from having provided consulting services related to this tender. To that end, the Procuring Entity shall indicate in the **Data Sheet** and make available to all the firms together with this tender document all in formation that would in that respect give such firm any unfair competitive advantage over competing firms.

#### 3.0 Eligible tenderers

- **3.1** A Tenderer may be a firm that is a private entity, a state-owned enterprise or institution subject to ITT 3.8, or an individual or any combination of such entities in the form of a joint venture (JV) under an existing agree mentor with the intent to enter in to such an agreement supported by a letter of intent. In the case of a joint venture, all members shall be jointly and severally liable for the execution of the entire Contract in accordance with the Contract terms. The JV shall nominate a Representative who shall have the authority to conduct all business for and on behalf of any and all the members of the JV during the tendering process and, in the event the JV is awarded the Contract, during contract execution. Members of a joint venture may not also make an individual tender, be a subcontractor in a separate tender or be part of another joint venture for the purposes of the same Tender. The maximum number of JV members shall be specified in the **TDS**.
- **3.2** Public Officers of the Procuring Entity, their Spouses, Child, Parent, Brothers or Sister. Child, Parent, Brother or Sister of a Spouse, their business associates or agents and firms/organizations in which they have a substantial or controlling interest shall not be eligible to tender or be awarded a contract. Public Officers are also not allowed to participate in any procurement proceedings.

- **3.3** A Tenderer shall not have a conflict of interest. Any tenderer found to have a conflict of interest shall be disqualified. A tenderer may be considered to have a conflict of interest for the purpose of this tendering process, if the tenderer:
  - a) Directly or indirectly controls, is controlled by or is under common control with an other tenderer;
  - b) Receives or has received any director indirect subsidy from another tenderer;
  - c) Has the same legal representative as an other tenderer;
  - d) Has a relationship with an other tenderer, directly or through common third parties, that puts it in a position to influence the tender of an other tenderer, or influence the decisions of the Procuring Entity regarding this tendering process;
  - e) Any of its affiliates participated as a consultant in the preparation of the design or technical specifications of the goods or works that are the subject of the tender;
  - f) Any of its affiliates has been hired (or is proposed to be hired) by the Procuring Entity as a consultant for Contract implementation;
  - g) Would be providing goods, works, or non-consulting services resulting from or directly related to consulting services for the preparation or implementation of the contract specified in this Tender Document:
  - h) Has a close business or personal relationship with senior management or professional staff of the Procuring Entity who has the ability to influence the bidding process and:
  - i) Are directly or indirectly involved in the preparation of the Tender document or specifications of the Contract, and/or the Tender evaluation process of such contract; or
    - ii) May be involved in the implementation or supervision of such Contract unless the conflicts temming from such relationship has been resolved in a manner acceptable to the Procuring Entity throughout the tendering process and execution of the Contract.
- **3.4** A tenderer shall not be involved in corrupt, coercive, obstructive or fraudulent practice. A tenderer that is proven to have been involved in any of these practices shall be automatically disqualified
- **3.5** A Tenderer (either individually or as a JV member) shall not participate in more than one Tender, except for permitted alternative tenders. This includes participation as a subcontractor in other Tenders. Such participation shall result in the disqualification of all Tenders in which the firm is involved. Members of a joint venture may not also make an individual tender, be a sub-contractor in a separate tender or be part of another joint venture for the purposes of the same Tender. A firm that is not a tenderer or a JV member may participate as a subcontractor in more than one tender.
- 3.6 A Tenderer may have the nationality of any country, subject to the restrictions pursuant to ITT3.9. ATenderer shall be deemed to have the nationality of a country if the Tenderer is constituted, incorporated or registered in and operates in conformity with the provisions of the laws of that country, as evidenced by its articles of incorporation (or equivalent documents of constitution or association) and its registration documents, as the case may be. This criterion also shall apply to the determination of the nationality of proposed sub-contractors or sub-consultants for any part of the Contract including related Services.
- **3.7** A Tenderer that has been debarred from participating in public procurement shall be ineligible to tender or be awarded a contract. The list of debarred firms and individuals is available from the website of PPRA www.ppra.go.ke.
- **3.8** A Tenderer that is a state-owned enterprise or a public institution in Kenya may be eligible to tender and be awarded Contract(s) only if it is determined by the Procuring Entity to meet the following conditions, i.e. if it is:
  - i) A legal public entity of Government and/or public administration,
  - ii) financially autonomous and not receiving any significant subsidies or budget support from any public entity or Government, and;
  - (iii) operating under commercial law and vested with legal rights and liabilities similar to any commercial enterprise to enable it compete with firms in the private sector on an equal basis.
- **3.9** Firms and individuals shall be ineligible if their countries of origin are:
  - (a) As a matter of law or official regulations, Kenya prohibits commercial relations with that country;

(b) Byanactofcompliancewith a decision of the United Nations Security Council taken under Chapter VII of the Charterof the United Nations, Kenya prohibits any import of goods or contracting of works or services from that country, or any payments to any country, person, or entity in that country.

A tenderer shall provide such documentary evidence of eligibility satisfactory to the Procuring Entity, as the Procuring Entity shall reasonably request.

- **3.10** Foreign tenderers are required to source at least forty (40%) percent of their contract inputs (in supplies, local sub-contracts and labor) from citizen suppliers and contractors. To this end, a foreign tenderer shall provide in its tender documentary evidence that this requirement is met. Foreign tenderers not meeting this criterion will be automatically disqualified. Information required to enable the Procuring Entity determine if this condition is met shall be provided for this purpose in "SECTIONI II EVALUATION AND QUALIFICATION CRITERIA, Item 9".
- **3.11** Pursuant to the eligibility requirements of ITT 3.10, a tender is considered a foreign tenderer, If it is registered in Kenya and has less than 51 percent ownership by nationals of Kenya and if it does not subcontract to foreign firms or individuals more than 10 percent of the contract price, excluding provisional sums. JVs are considered as foreign tenderers if the individual member firms registered in Kenya have less 51 percent ownership by nationals of Kenya. The JV shall not subcontract to foreign firms more than 10 percent of the contract price, excluding provisional sums.
- **3.12** The National Construction Authority Act of Kenya requires that all local and foreign contractors be registered with the National Construction Authority and be issued with a Registration Certificate before they can undertake any construction works in Kenya. Registration shall not be a condition for tender, but it shall be a condition of contract award and signature. A selected tenderer shall be given opportunity to register before such award and signature of contract. Application for registration with National Construction Authority may be accessed from the website www.nca.go.ke.
- 3.13 The Competition Act of Kenya requires that firms wishing to tender as Joint Venture undertakings which may prevent, distort or lessen competition in provision of services are prohibited unless they are exempt in accordance with the provisions of Section 25 of the Competition Act, 2010. JVs will be required to seek for exemption from the Competition Authority. Exemption shall not be a condition for tender, but it shall be a condition of contract award and signature. A JV tenderer shall be given opportunity to seek such exemption as a condition of award and signature of contract. Application for exemption from the Competition Authority of Kenya may be accessed from the website <a href="https://www.cak.go.ke">www.cak.go.ke</a>.
- 4.14 A kenyan tenderer shall be eligible to tender if it provides evidence of having fulfilled his/her tax obligations by producing valid tax compliance certificate or tax exemption certificate issued by the Kenya Revenue Authority.

#### 4.0 Eligible goods, equipment, and services

- **4.1** Goods, equipment and services to be supplied under the Contract may have their origin in any country that is not ineligible under ITT 3.9. At the Procuring Entity's request, Tenderers may be required to provide evidence of the origin of Goods, equipment and services.
- **4.2** Any goods, works and production processes with characteristics that have been declared by the relevant national environmental protection agency or by other competent authority as harmful to human beings and to the environment shall not be eligible for procurement.

#### 5.0 Tenderer's responsibilities

- **5.1** The tenderer shall bear all costs associated with the preparation and submission of his/her tender, and the Procuring Entity will in no case be responsible or liable for those costs.
- **5.2** The tenderer, at the tenderer's own responsibility and risk, is encouraged to visit and examine and inspect the Site of the Works and its surroundings and obtain all information that may be necessary for preparing the tender and entering into a contract for construction of the Works. The costs of visiting the Site shall beat the tenderer's own expense.
- **5.3** The Tenderer and any of its personnel or agents will be granted permission by the Procuring Entity to enter upon its premises and lands for the purpose of such visit. The Tenderer shall indemnify the Procuring Entity again

- stall liability arising from death or personal injury, loss of or damage to property, and any other losses and expenses incurred as a result of the examination and inspection.
- **5.4** The tenderer shall provide in the Form of Tender and Qualification Information, a preliminary description of the proposed work method and schedule, including charts, as necessary or required.

#### B. <u>CONTENTS OF TENDER DOCUMENTS</u>

#### 6.0 Sections of Tender Document

**6.1** The tender document consists of Parts 1, 2, and 3, which includes all the sections specified below, and which should be read in conjunction with any Addenda issued in accordance with ITT 10.

#### **PART 1: Tendering Procedures**

Section I – Instructions to Tenderers Section II – Tender Data Sheet (TDS) Section III- Evaluation and Qualification Criteria Section IV – Tendering Forms

#### **PART 2: Works' Requirements**

Section V - Bills of Quantities Section VI - Specifications Section VII - Drawings

### PART 3: Conditions of Contract and Contract Forms

**Section VIII - General Conditions (GCC)** 

Section IX - Special Conditions of Contract

Section X- Contract Forms

- **6.2** The Invitation to Tender Notice issued by the Procuring Entity is not part of the Contract documents. Unless obtained directly from the Procuring Entity, the Procuring Entity is not responsible for the completeness of the Tender document, responses to requests for clarification, the minutes of a pre-arranged site visit and those of the pre-Tender meeting (if any), or Addenda to the Tender document in accordance with ITT 10. Incase of any contradiction, documents obtained directly from the Procuring Entity shall prevail.
- **6.3** The Tenderer is expected to examine all instructions, forms, terms, and specifications in the Tender Document and to furnish with its Tender all information and documentation as is required by the Tender document.

#### 7.0 Clarification of Tender Document, Site Visit, Pre-tender Meeting

- 7.1 A Tenderer requiring any clarification of the Tender Document shall contact the Procuring Entity in writing at the Procuring Entity's address specified in the **TDS** or raise its enquiries during the pre-Tender meeting if provided for in accordance with ITT 7.2. The Procuring Entity will respond in writing to any request for clarification, provided that such request is received no later than the period specified in the **TDS** prior to the deadline for submission of tenders. The Procuring Entity shall forward copies of its response to all tenderers who have acquired the Tender documents in accordance with ITT 7.4, including a description of the inquiry but without identifying its source. If so specified in the **TDS**, the Procuring Entity shall also promptly publish its response at the web page identified in the **TDS**. Should the clarification result in changes to the essential elements of the Tender Documents, the Procuring Entity shall amend the Tender Documents following the procedure under ITT 8 and ITT 22.2.
- **7.2** The Tenderer, at the Tenderer's own responsibility and risk, is encouraged to visit and examine and inspect the site(s) of the required contracts and obtain all information that may be necessary for preparing a tender. The costs of visiting the Site shall be at the Tenderer's own expense. The Procuring Entity shall specify in the **TDS** if a pre-arranged Site visit and or a pre-tender meeting will be held, when and where. The Tenderer's designated representative is invited to attend a pre-arranged site visit and a pre-tender meeting, as the case may be. The purpose of the site visit and the pre-tender meeting will be to clarify issues and to answer questions on any matter that may be raised at that stage.

- **7.3** The Tenderer is requested to submit any questions in writing, to reach the Procuring Entity not later than the period specified in the **TDS** before the meeting.
- **7.4** Minutes of a pre-arranged site visit and those of the pre-tender meeting, if applicable, including the text of the questions asked by Tenderers and the responses given, together with any responses prepared after the meeting,
  - will be transmitted promptly to all Tenderers who have acquired the Tender Documents. Minutes shall not identify the source of the questions asked.
- **7.5** The Procuring Entity shall al so promptly publish anonymized (*no names*) Minutes of the pre-arranged site visit and those of the pre-tender meeting at the web page identified in the **TDS**. Any modification to the Tender Documents that may become necessary as a result of the pre-arranged site visit and those of the pre-tender meeting shall be made by the Procuring Entity exclusively through the issue of an Addendum pursuant to ITT 8 and not through the minutes of the pre-Tender meeting. Non-attendance at the pre-arranged site visit and the pre-tender meeting will not be a cause for disqualification of a Tenderer.

#### 8.0 Amendment of Tender Documents

- **8.1** At any time prior to the deadline for submission of Tenders, the Procuring Entity may amend the Tender Documents by issuing addenda.
- **8.2** Any addendum issued shall be part of the Tender Documents and shall be communicated in writing to all who have obtained the Tender Documents from the Procuring Entity. The Procuring Entity shall also promptly publish the addendum on the Procuring Entity's website in accordance with ITT 7.5.
- **8.3** To give Tenderers reasonable time in which to take an addendum into account in preparing their Tenders, the Procuring Entity should extend the dead line for the submission of Tenders, pursuant to ITT 22.2.

#### C. PREPARATION OF TENDERS

#### 9. Cost of Tendering

The Tenderer shall bear all costs associated with the preparation and submission of its Tender, and the Procuring Entity shall not be responsible or liable for those costs, regardless of the conduct or outcome of the tendering process.

#### 10.0 Language of Tender

The Tender, as well as all correspondence and documents relating to the tender exchanged by the tenderer and the Procuring Entity, shall be written in the English Language. Supporting documents and printed literature that are part of the Tender may be in another language provided they are accompanied by an accurate and notarized translation of the relevant passages into the English Language, in which case, for purposes of interpretation of the Tender, such translation shall govern.

#### 11.0 Documents Comprising the Tender

- 11.1 The Tender shall comprise the following:
  - a) Form of Tender prepared in accordance with ITT 12;
  - b) Schedules including priced Bill of Quantities, completed in accordance with ITT 12 and ITT 14;
  - c) Tender Security or Tender-Securing Declaration, in accordance with ITT 19.1;
  - d) Alternative Tender, if permissible, in accordance with ITT 13;
  - e) *Authorization*: written confirmation authorizing the signatory of the Tender to commit the Tenderer, in accordancewithITT20.3;
  - f) *Qualifications:* documentary evidence in accordance with ITT 17 establishing the Tenderer's qualifications to per form the Contract if its Tender is accepted;

- g) Conformity: a technical proposal in accordance with ITT 16;
- h) Any other document required in the **TDS**.
- 11.2 In addition to the requirements under ITT 11.1, Tenders submitted by a JV shall include a copy of the Joint Venture Agreement entered into by all members. Alternatively, a letter of intent to execute a Joint Venture Agreement in the event of a successful Tender shall be signed by all members and submitted with the Tender, together with a copy of the proposed JV Agreement. Change of membership and conditions of the JV prior to contract signature will render the tenderliable for disqualification.

#### 12.0 Form of Tender and Schedules

- 12.1 The Form of Tender and Schedules, including the Bill of Quantities, shall be prepared using the relevant forms furnished in Section IV, Tendering Forms. The forms must be completed with out any alterations to the text, and no substitutes shall be accepted except as provided under ITT 20.3. All blank spaces shall be filled in with the information requested. The Tenderer shall chronologically serialize all pages of the tender documents submitted.
- 12.2 The Tenderer shall furnish in the Form of Tender information on commissions and gratuities, if any, paid or to be paid to agents or any other party relating to this Tender.

#### 13. Alternative Tenders

- 13.1 Unless otherwise specified in the TDS, alternative Tenders shall not be considered.
- 13.2 When alternative times for completion are explicitly invited, a statement to that effect will be included in the **TDS**, and the method of evaluating different alternative times for completion will be described in Section III, Evaluation and Qualification Criteria.
- 13.3 Except as provided under ITT 13.4 below, Tenderers wishing to offer technical alternatives to the requirements of the Tender Documents must first price the Procuring Entity's design as described in the Tender Documents and shall further provide all information necessary for a complete evaluation of the alternative by the Procuring Entity, including drawings, design calculations, technical specifications, breakdown of prices, and proposed construction methodology and other relevant details. Only the technical alternatives, if any, of the Tenderer with the Winning Tender conforming to the basic technical requirements shall be considered by the Procuring Entity.
- 13.4 When specified in the **TDS**, Tenderers are permitted to submit alternative technical solutions for specified parts of the Works, and such parts will be identified in the **TDS**, as will the method for their evaluating, and described in Section VII, Works' Requirements.

#### 14.0 Tender Prices and Discounts

- 14.1 The prices and discounts (including any price reduction) quoted by the Tenderer in the Form of Tender and in the Billof Quantities shall conform to the requirements specified below.
- 14.2 The Tenderer shall fill in rates and prices for all items of the Works described in the Bill of Quantities. Items against which no rate or price is entered by the Tenderer shall be deemed covered by the rates for other items in the Bill of Quantities and will not be paid for separately by the Procuring Entity. An item not listed in the priced Bill of Quantities shall be assumed to be not included in the Tender, and provided that the Tender is determined substantially responsive notwithstanding this omission, the average price of the item quoted by substantially responsive Tenderers will be added to the Tender price and the equivalent total cost of the Tender so determined will be used for price comparison.
- 14.3 The price to be quoted in the Form of Tender, in accordance with ITT 12.1, shall be the total price of the Tender, including any discounts offered.
- **14.4** The Tenderer shall quote any discounts and the methodology for their application in the Form of Tender, in accordance with ITT 12.1.

- 14.5 It will be specified in the **TDS** if the rates and prices quoted by the Tenderer are or are not subject to adjustment during the performance of the Contract in accordance with the provisions of the Conditions of Contract, except incases where the contract is subject to fluctuations and adjustments, not fixed price. In such a case, the Tenderer shall furnish the indices and weightings for the price adjustment formulae in the Schedule of Adjustment Data and the Procuring Entity may require the Tenderer to justify its proposed indices and weightings.
- 14.6 Where tenders are being invited for individual lots (contracts) or for any combination of lots (packages), tenderers wishing to offer discounts for the award of more than one Contract shall specify in their Tender the price reductions applicable to each package, or alternatively, to individual Contracts within the package. Discounts shall be submitted in accordance with ITT 14.4, provided the Tenders for all lots (contracts) are opened at the sametime.

14.7 All duties, taxes, and other levies payable by the Contractor under the Contract, or for any other cause, as of the date 30 days prior to the deadline for submission of Tenders, shall be included in the rates and prices and the total Tender Price submitted by the Tenderer.

#### 15.0 Currencies of Tender and Payment

- 15.1 The currency(ies) of the Tender and the currency(ies) of payments shall be the same.
- 15.2 Tenderers shall quote entirely in Kenya Shillings. The unit rates and the prices shall be quoted by the Tenderer in the Bill of Quantities, entirely in Kenya shillings.
  - a) A Tenderer expecting to incur expenditures in other currencies for inputs to the Works supplied from outside Kenya (referred to as "the foreign currency requirements") shall (if so allowed in the **TDS**) indicate in the Appendix to Tender the percentage(s) of the Tender Price (excluding Provisional Sums), needed by the Tenderer for the payment of such foreign currency requirements, limited to no more than two foreign currencies.
  - b) The rates of exchange to be used by the Tenderer in arriving at the local currency equivalent and the percentage(s) mentioned in (a) above shall be specified by the Tenderer in the Appendix to Tender and shall be based on the exchange rate provided by the Central Bank of Kenya on the date 30 days prior to the actual date of tender opening. Such exchange rate shall apply for all foreign payments under the Contract.
- 15.3 Tenderers may be required by the Procuring Entity to justify, to the Procuring Entity's satisfaction, their local and foreign currency requirements, and to substantiate that the amounts included in the unit rates and prices and shown in the Schedule of Adjustment Data in the Appendix to Tender are reasonable, in which case a detailed break down of the foreign currency requirements shall be provided by Tenderers.

#### 16.0 Documents Comprising the Technical Proposal

The Tenderer shall furnish a technical proposal including a statement of work methods, equipment, personnel, schedule and any other information as stipulated in Section IV, Tender Forms, insufficient detail to demonstrate the adequacy of the Tenderer's proposal to meet the work's requirements and the completion time.

#### 17.0 Documents Establishing the Eligibility and Qualifications of the Tenderer

- **17.1** Tenderers shall complete the Form of Tender, included in Section IV, Tender Forms, to establish Tenderer's eligibility in accordance with ITT 4.
- 17.2 In accordance with Section III, Evaluation and Qualification Criteria, to establish its qualifications to perform the Contract the Tenderer shall provide the information requested in the corresponding information sheets included in Section IV, Tender Forms.
- 17.3 If a marg in of preference applies as specified in accordance with ITT 33.1, nation al tenderers, individually or in joint ventures, applying for eligibility for national preference shall supply all information required to satisfy the criteria for eligibility specified in accordance with ITT 33.1.
- 17.4 Tenderers shall be asked to provide, as part of the data for qualification, such information, including details of ownership, as shall be required to determine whether, according to the classification established by the Procuring Entity, a particular contractor or group of contractors qualifies for a margin of preference. Further the information will enable the Procuring Entity identify any actual or potential conflict of interest in relation to the procurement and/or contract management processes, or a possibility of collusion between tenderers, and thereby help to prevent any corrupt influence in relation to the procurement process or contract management.

  17.5 The purpose of the information described in ITT 17.4 above overrides any claims to confidentiality which a tenderer may have. There can be no circumstances in which it would be justified for a tenderer to keep information relating to its ownership and control confidential where it is tendering to undertake public sector work and receive public sector funds. Thus, confidentiality will not be accepted by the Procuring Entity as a justification for a Tenderer's failure to disclose, or failure to provide required information on its ownership and control.
- 17.6 The Tenderer shall provide further documentary proof, information or authorizations that the Procuring Entity may request in relation to owner ship and control which in formation on any changes to the information which was provided by the tenderer under ITT 6.4. The obligations to require this information shall continue for the duration of the procurement process and contract performance and after completion of the contract, if any change to the information previously provided may reveal a conflict of interest in relation to the award or management of the contract.

- 17.7 All information provided by the tenderer pursuant to these requirements must be complete, current and accurate as at the date of provision to the Procuring Entity. In submitting the information required pursuant to these requirements, the Tenderer shall warrant that the information submitted is complete, current and accurate as at the date of submission to the Procuring Entity.
- 17.8 If a tenderer fails to submit the information required by these requirements, its tender will be rejected. Similarly, ifthe Procuring Entity is unable, after taking reasonable steps, to verify to a reasonable degree the information submitted by a tenderer pursuant to these requirements, then the tender will be rejected.
- 17.9 If information submitted by a tenderer pursuant to these requirements, or obtained by the Procuring Entity (whether through its own enquiries, through notification by the public or otherwise), shows any conflict of interest which could materially and improperly benefit the tenderer in relation to the procurement or contract management process, then:
  - i) If the procurement process is still ongoing, the tenderer will bed is qualified from the procurement process, ii) if the contract has been awarded to that tenderer, the contract award will be set as idepending the outcome of (iii),
  - iii) the tenderer will be referred to the relevant law enforcement authorities for investigation of whether the tenderer or any other person shave committed any criminal offence.
- 17.10 If a tenderer submits information pursuant to these requirements that is in complete, in accurate or out-of-date, or attempts to obstruct the verification process, then the consequences ITT 17.8 will ensue unless the tenderer can show to the reasonable satisfaction of the Procuring Entity that any such act was not material, or was due to genuine error which was not attributable to the intentional act, negligence or recklessness of the tender.

#### 18.0 Period of Validity of Tenders

- 18.1. Tenders shall remain valid for the Tender Validity period specified in the **TDS**. The Tender Validity period starts from the date fixed for the Tender submission deadline (as prescribed by the Procuring Entity in accordance with ITT 22). At ender valid for a shorter period shall be rejected by the Procuring Entity as non-responsive.
- 18.2 In exceptional circumstances, prior to the expiration of the Tender validity period, the Procuring Entity may requestTendererstoextendtheperiodofvalidityoftheirTenders. Therequestandtheresponsesshallbemadein writing. If a Tender Security is requested in accordance with ITT 19, it shall also be extended for thirty (30) days beyond the deadline of the extended validity period. A Tenderer may refuse the request without forfeiting its Tendersecurity. ATenderergrantingtherequests hall not be required or permitted to modify its Tender.

#### 19.0 Tender Security

- 19.1 The Tenderer shall furnish as part of its Tender, either a Tender-Securing Declaration or a Tender Security as specified in the **TDS**, in original form and, in the case of a Tender Security, in the amount and currency **specified** in the **TDS**. A Tender-Securing Declaration shall use the form included in Section IV, Tender Forms.
- **19.2** If a Tender Security is specified pursuant to ITT 19.1, the Tender Security shall be a demand guarantee in any of the following forms at the Tenderer's option:
  - I) cash; ii) a bank guarantee;
  - a guarantee by an insurance company registered and licensed by the Insurance Regulatory Authority listed by the Authority;
  - iv) a guarantee issued by a financial institution approved and licensed by the Central Bank of Kenya, from a reputable source, and an eligible country.
- 19.3 If an unconditional bank guarantee is issued by a bank located outside Kenya, the issuing bank shall have a correspondent bank located in Kenya to make it enforceable. The Tender Security shall be valid for thirty (30) days beyond the original validity period of the Tender, or beyond any period of extension if requested under ITT 18.2.
- 19.4 If a Tender Security or Tender-Securing Declaration is specified pursuant to ITT 19.1, any Tender not accompanied by a substantially responsive Tender Security or Tender-Securing Declaration shall be rejected by the Procuring Entity as non-responsive.

- 19.5 If a Tender Security is specified pursuant to ITT 19.1, the Tender Security of unsuccessful Tenderers shall be returned as promptly as possible upon the successful Tenderer's signing the Contract and furnishing the Performance Security and any other documents required in the TDS. The Procuring Entity shall also promptly
  - return the tender security to the tenderers where the procurement proceedings are terminated, all tenders were determined non-responsive or a bidder declines to extend tender validity period.
- 19.6 The Tender Security of the successful Tenderer shall be returned as promptly as possible once the successful Tenderer has signed the Contract and furnished the required Performance Security, and any other documents required in the TDS.
- 19.7 The Tender Security may be forfeited or the Tender-Securing Declaration executed:
- a) if a Tenderer withdraws its Tender during the period of Tender validity specified by the Tenderer on the Form of Tender, or any extension there to provided by the Tenderer; or
- b) if the successful Tenderer fails to:
  - i) signthe Contract in accordance with ITT47; or
  - ii) furnish a Performance Security and if required in the TDS, and any other documents required in the TDS.
  - 19.8 Where tender securing declaration is executed, the Procuring Entity shall recommend to the PPRA to debars the Tenderer from participating in public procurement as provided in the law.
- 19.9 The Tender Security or the Tender-Securing Declaration of a JV shall be in the name of the JV that submits the Tender. If the JV has not been legally constituted into a legally enforceable JV at the time of tendering, the Tender Security or the Tender-Securing Declaration shall be in the names of all future members as named in the letter of intent referred to in ITT 4.1 and ITT 11.2.
- 19.10 A tenderer shall not issue a tender security to guarantee itself.

#### 20.0 Format and Signing of Tender

- 20.1 The Tenderer shall prepare one original of the documents comprising the Tender as described in ITT 11 and clearly mark it "ORIGINAL." Alternative Tenders, if permitted in accordance with ITT 13, shall be clearly marked "ALTERNATIVE." In addition, the Tenderer shall submit copies of the Tender, in the number specified in the TDS and clearly mark them "COPY." In the event of any discrepancy between the origin a landthe copies, the original shall prevail.
- **20.2** Tenderers shall mark as "CONFIDENTIAL" all information in their Tenders which is confidential to their business. This may include proprietary information, trade secrets, or commercial or financially sensitive information.
- 20.3 The original and all copies of the Tender shall be typed or written in indelible ink and shall be signed by a person duly authorized to sign on behalf of the Tenderer. This authorization shall consist of a written confirmation as specified in the TDS and shall be attached to the Tender. The name and position held by each person signing the authorization must be typed or printed below the signature. All pages of the Tender where entries or amendments have been made shall be signed or initialed by the person signing the Tender.
- 20.4 Incase the Tenderer is a JV, the Tender shall be signed by an authorized representative of the JV on behalf of the JV, and so as to be legally binding on all the members as evidenced by a power of attorney signed by their legally authorized representatives.
- 20.5 Any inter-lineation, erasures, or overwriting shall be valid only if they are signed or initialed by the person signing the Tender.

#### D. SUBMISSION AND OPENING OF TENDERS

#### 21.0 Sealingand Marking of Tenders

- 21.1 The Tenderer shall deliver the Tender in a single sealed envelope, or in a single sealed package, or in a single sealed container bearing the name and Reference number of the Tender, addressed to the Procuring Entity and a warning not to open before the time and date for Tender opening date. Within the single envelope, package or container, the Tenderer shall place the following separate, sealed envelopes:
  - a) in an envelope or package or container marked "ORIGINAL", all documents comprising the Tender, as described in ITT 11; and
  - b) in a nenvelope or package or container marked "COPIES", all required copies of the Tender; and
  - c) if alternative Tenders are permitted in accordance with ITT 13, and if relevant:
    - i) in an envelope or package or container marked "ORIGINAL -ALTERNATIVE TENDER", the alternative Tender; and
    - ii) in the envelope or package or container marked "COPIES- ALTERNATIVE TENDER", all required copies of the alternative Tender.

The inner envelopes or packages or containers shall:

- a) bear the name and address of the Procuring Entity,
- b) bear the name and address of the Tenderer; and
- c) bear the name and Reference number of the Tender.
- **21.2** If an envelope or package or container is not sealed and marked as required, the *Procuring Entity* will assume no responsibility for the misplacement or premature opening of the Tender. Tenders misplaced or opened prematurely will not be accepted.

#### 22.0 Deadline for Submission of Tenders

- **22.1** Tenders must be received by the Procuring Entity at the address specified in the **TDS** and no later than the date and timeals ospecified in the **TDS**. When so specified in the **TDS**, tenderers shall have the option of submitting their Tenders electronically. Tenderers submitting Tenders electronically shall follow the electronic Tender submission procedures specified in the **TDS**.
- **22.2** The Procuring Entity may, at its discretion, extend the deadline for the submission of Tenders by amending the TenderDocumentsinaccordance with ITT 8, in which case all rights and obligations of the Procuring Entity and Tenderers previously subject to the deadline shall there after be subject to the deadline as extended.

#### 23.0 Late Tenders

The Procuring Entity shall not consider any Tender that arrives after the deadline for submission of tenders, in accordance with ITT 22. Any Tender received by the Procuring Entity after the deadline for submission of Tenders shall be declared late, rejected, and returned unopened to the Tenderer.

#### 24.0 Withdrawal, Substitution, and Modification of Tenders

- **24.1** A Tenderer may withdraw, substitute, or modify its Tenderafterith as been submitted by sending a written notice, duly signed by an authorized representative, and shall include a copy of the authorization in accordance with ITT 20.3, (except that withdrawal notices do not require copies). The corresponding substitution or modification of the Tender must accompany the respective written notice. All notices must be:
  - a) prepared and submitted in accordance with ITT 20 and ITT 21 (except that withdrawals notices do not require copies), and in addition, the respective envelopes shall be clearly marked "WITHDRAWAL," "SUBSTITUTION," "MODIFICATION;" and
  - b) received by the Procuring Entity prior to the deadline prescribed for submission of Tenders, in accordance with ITT 22.
- 24.2 Tenders requested to be withdrawn in accordance with ITT 24.1 shall be returned unopened to the Tenderers.
- **24.3** No Tender may be withdrawn, substituted, or modified in the interval between the deadline for submission of Tenders and the expiration of the period of Tender validity specified by the Tenderer on the Form of Tender or any extension thereof.

#### 25. Tender Opening

- 25.1 Except in the cases specified in ITT 23 and ITT 24.2, the Procuring Entity shall publicly open and read out all Tenders received by the deadline, at the date, time and place specified in the TDS, in the presence of Tenderers' designated representatives who chooses to attend. Any specific electronic Tender opening procedures required if electronic Tendering is permitted in accordance with ITT 22.1, shall be as specified in the TDS.
- **25.2** First, envelopes marked "WITHDRAWAL" shall be opened and read out and the envelopes with the corresponding Tender shall not be opened but returned to the Tenderer. No Tender withdrawal shall be permitted unless the corresponding withdrawal notice contains a valid authorization to request the withdrawal and is read out at Tender opening.
- 25.3 Next, envelopes marked "SUBSTITUTION" shall be opened and read out and exchanged with the corresponding Tender being substituted, and the substituted Tender shall not be opened, but returned to the Tenderer. No Tender substitution shall be permitted unless the corresponding substitution notice contains a valid authorization to request the substitution and is read out at Tender opening.
- 25.4 Next, envelopes marked "MODIFICATION" shall be opened and read out with the corresponding Tender. No Tender modification shall be permitted unless the corresponding modification notice contains a valid authorizationtorequestthemodification and is readout at Tenderopening.
- 25.5 Next, all remaining envelopes shall be opened one at a time, reading out: the name of the Tenderer and whether there is a modification; the total Tender Price, per lot (contract) if applicable, including any discounts and alternative Tenders; the presence or absence of a Tender Security or Tender-Securing Declaration, if required; and any other details as the Procuring Entity may consider appropriate.
- 25.6 Only Tenders, alternative Tenders and discounts that are opened and read out at Tender opening shall be considered further for evaluation. The Form of Tender and pages of the Bill of Quantities (to be decided on by the tender opening committee) are to be initialed by the members of the tender opening committee attending the opening.
- 25.7 At the Tender Opening, the Procuring Entitys hall neither discuss the merits of any Tender nor reject any Tender (except for late Tenders, in accordance with ITT 23.1).
- 25.8 The Procuring Entity shall prepare minutes of the Tender Opening that shall include, as a minimum:
  - a) the name of the Tenderer and whether there is a withdrawal, substitution, or modification;
  - b) the Tender Price, per lot (contract) if applicable, including any discounts;
  - c) any alternative Tenders;
  - d) the presence or absence of a Tender Security, if new as required;
  - e) number of pages of each tender document submitted.
- **25.9** The Tenderers' representatives who are present shall be requested to sign the minutes. The omission of a Tenderer's signature on the minutes shall not invalidate the contents and effect of the minutes. A copy of the tender opening register shall be distributed to all Tenderers.

#### E. EVALUATION AND COMPARISON OF TENDERS

#### 26. Confidentiality

- 26.1 Information relating to the evaluation of Tenders and recommendation of contract award shall not be disclosed to Tenderersorany other persons not officially concerned with the Tender process until information on Intention to Award the Contract is transmitted to all Tenderers in accordance with ITT 43.
- 26.2 Any effort by a Tenderer to influence the Procuring Entity in the evaluation of the Tenders or Contract award decisions may result in the rejection of its tender.
- 26.3 Not withstanding ITT 26.2, from the time of tender opening to the time of contract award, if a tenderer wishes to contact the Procuring Entity on any matter related to the tendering process, it shall do so in writing.

#### 27.0 Clarification of Tenders

- 27.1 To assist in the examination, evaluation, and comparison of the tenders, and qualification of the tenderers, the Procuring Entity may, at its discretion, ask any tenderer for a clarification of its tender, given a reasonable time for aresponse. Any clarification submitted by a tenderer that is not in response to a request by the Procuring Entity shallnot be considered. The Procuring Entity's request for clarification and the response shall be in writing. No change, including any voluntary increase or decrease, in the prices or substance of the tender shall be sought, offered, or permitted, except to confirm the correction of arithmetic errors discovered by the Procuring Entity in the evaluation of the tenders, in accordance with ITT 31.
- 27.2 If a tenderer does not provide clarifications of its tender by the date and time set in the Procuring Entity's request for clarification, its Tender may be rejected.

#### 28.0 Deviations, Reservations, and Omissions

- **28.1** During the evaluation of tenders, the following definitions apply:
  - a) "Deviation" is a departure from the requirements specified in the tender document;
  - b) "Reservation" is the setting of limiting conditions or withholding from complete acceptance of the requirements specified in the tender document; and
  - c) "Omission" is the failure to submit part or all of the information or documentation required in the Tender document.

#### 29.0 Determination of Responsiveness

- **29.1** The Procuring Entity's determination of a Tender's responsiveness is to be based on the contents of the tender itself, as defined in ITT 11.
- 29.2 A substantially responsive Tender is one that meets the requirements of the Tender document withoutmaterial deviation, reservation, or omission. A material deviation, reservation, or omission is one that, if accepted, would:
  - a) Affect in any substantial way the scope, quality, or performance of the Works specified in the Contract;
  - b) limit in any substantial way, inconsistent with the tender document, the Procuring Entity's rights or the tenderer's obligations under the proposed contract;
  - c) if rectified, would unfairly affect the competitive position of other tenderers presenting substantially responsivetenders.
- 29.3 The Procuring Entity shall examine the technical aspects of the tender submitted in accordance with ITT 16, to confirm that all requirements of Section VII, Works' Requirements have been met without any material deviation, reservation or omission.
- 29.4 If a tender is not substantially responsive to the requirements of the tender document, it shall be rejected by the Procuring Entity and may not subsequently be made responsive by correction of the material deviation, reservation, or omission.

#### 30.0 Non-material Non-conformities

- **30.1** Provided that a tender is substantially responsive, the Procuring Entity may waive any non-conformities in the tender.
- 30.2 Provided that a Tender is substantially responsive, the Procuring Entity may request that the tenderer submit the necessary information or documentation, within a reasonable period of time, to rectify non-material non-conformities in the tender related to documentation requirements. Requesting information or documentation on such non-conformities shall not be related to any aspect of the price of the tender. Failure of the tenderer to comply with the request may result in the rejection of its tender.
- 30.3 Provided that a tender is substantially responsive, the Procuring Entity shall rectify quantifiable non-material non-conformities related to the Tender Price. To this effect, the Tender Price shall be adjusted, for comparison purposes only, to reflect the price of a missing or non-conforming item or component in the manner specified in the TDS.

#### 31.0 Arithmetical Errors

- **31.1** The tender sum as submitted and read out during the tender opening shall be absolute and final and shall not be the subject of correction, adjustment or amendment in any way by any person or entity.
- 31.2 Provided that the Tender is substantially responsive, the Procuring Entity shall handle errors on the following basis:
  - a) Any error detected if considered a major deviation that affects the substance of the tender, shall lead to disqualification of the tender as non-responsive.
  - b) Any errors in the submitted tender arising from a miscalculation of unit price, quantity, subtotal and total bidpriceshallbe considered as a major deviation that affects the substance of the tender and shall lead to disqualification of the tender as non-responsive. and
  - c) if there is a discrepancy between words and figures, the amount in words shall prevail
- 31.3 Tenderers shall be notified of any error detected in their bid during the notification of award.

#### 32.0 Conversion to Single Currency

For evaluation and comparison purposes, the currency(ies) of the Tender shall be converted in to a single currency asspecified in the **TDS**.

#### 33.0 Margin of Preference and Reservations

- 33.1 A margin of preference may be allowed only when the contract is open to international competitive tendering where foreign contractors are expected to participate in the tendering process and where the contract exceeds the value/threshold specified in the Regulations.
- 33.2 A margin of preference shall not be allowed unless it is specified so in the TDS.
- 33.3 Contracts procured on basis of international competitive tendering shall not be subject to reservations exclusive to specific groups as provided in ITT 33.4.
- 33.4 Where it is intended to reserve a contract to as pecific group of businesses (these groups are Small and Medium Enterprises, Women Enterprises, Youth Enterprises and Enterprises of persons living with disability, as the case may be), and who are appropriately registered as such by the authority to be specified in the **TDS**, a procuring entity shall ensure that the invitation to tender specifically indicates that only businesses or firms belonging to the specified group are eligible to tender. No tender shall be reserved to more than one group. If not so stated in the Invitation to Tender and in the Tender documents, the invitation to tender will be open to all interested tenderers.

#### 34.0 Nominated Subcontractors

- 34.1 Unless otherwise stated in the **TDS**, the Procuring Entity does not intend to execute any specific elements of the Works by subcontractors selected/nominated by the Procuring Entity. Incase the ProcuringEntity nominates a subcontractor, the subcontract agreement shall be signed by the Subcontractor and the Procuring Entity. The main contract shall specify the working arrangements between the main contractor and the nominated subcontractor.
- **34.2** Tenderers may propose sub-contracting up to the percentage of total value of contracts or the volume of works as specified in the **TDS**. Subcontractors proposed by the Tenderer shall be fully qualified for their parts of the Works.
- 34.3 Domestic subcontractor's qualifications shall not be used by the Tenderer to qualify for the Works unless their specialized parts of the Works were previously designated so by the Procuring Entity in the TDS a scan be met by subcontractors referred to hereafter as 'Specialized Subcontractors', in which case, the qualifications of the Specialized Subcontractorsproposed by the Tenderer may be added to the qualifications of the Tenderer.

#### 35. Evaluation of Tenders

35.1 The Procuring Entity shall use the criteria and methodologies listed in this ITT and Section III, Evaluation and Qualification Criteria No other evaluation criteria or methodologies shall be permitted. By applying the criteria

and methodologies the Procuring Entity shall determine the Lowest Evaluated Tender in accordance with ITT 40

- 35.2 To evaluate a Tender, the Procuring Entity shall consider the following:
  - a) priceadjustment in accordance with ITT 31.1 (iii); excluding provisional sums and contingencies, if any, but including Daywork items, where priced competitively;
  - b) price adjustment due to discounts offered in accordance with ITT 14.4;
  - c) converting the amount resulting from applying (a) and (b) above, if relevant, to a single currency in accordance with ITT 32;
  - d) pricea djustment due to quantifiable non materialnon-conformities in accordance with ITT 30.3; and
  - e) any additional evaluation factors specified in the **TDS** and Section III, Evaluation and Qualification Criteria.
- 35.3 The estimated effect of the price adjustment provisions of the Conditions of Contract, applied over the period of execution of the Contract, shall not be considered in Tender evaluation.
- 35.4 Where the tender involves multiple lots or contracts, the tenderer will be allowed to tender for one or more lots (contracts). Each lot or contract will be evaluated in accordance with ITT 35.2. The methodology to determine the lowest evaluated tenderer or tenderers base done lot (contract) or based on a combination of lots (contracts), will be specified in Section III, Evaluation and Qualification Criteria. In the case of multiple lots or contracts, tenderer will be will be required to prepare the Eligibility and Qualification Criteria Form for each Lot.

#### **36.0** Comparison of tenders

The Procuring Entity shall compare the evaluated costs of all substantially responsive Tenders established in accordance with ITT 35.2 to determine the Tender that has the lowest evaluated cost.

#### 37.0 Abnormally low tenders and abnormally high tenders

#### **Abnormally LowTenders**

- 37.1 An Abnormally Low Tender is one where the Tender price, in combination with other elements of the Tender, appears so low that it raises material concerns as to the capability of the Tenderer in regards to the Tenderer's ability to perform the Contract for the offered Tender Price or that genuine competition between Tenderersis compromised.
- 37.2 In the event of identification of a potentially Abnormally Low Tender, the Procuring Entity shall seek written clarifications from the Tenderer, including detailed price analyses of its Tender price in relation to the subject matter of the contract, scope, proposed methodology, schedule, allocation of risks and responsibilities and any other requirements of the Tender document.
- **37.3** After evaluation of the price analyses, in the event that the Procuring Entity determines that the Tenderer has failed to demonstrate its capability to perform the Contract for the offered Tender Price, the Procuring Entity shall reject the Tender.

#### **Abnormally high tenders**

- 37.4 Anabnormally high tender price is one where the tender price, in combination with other constituent elements of the Tender, appears unreasonably too high to the extent that the Procuring Entity is concerned that it (the Procuring Entity) may not be getting value for money or it may be paying too high a price for the contract compared with market prices or that genuine competition between Tenderers is compromised.
- 37.5 Incase of a nab normally high price, the Procuring Entity shall make a survey of the market prices, check if the estimated cost of the contract is correct and review the Tender Documents to check if the specifications, scope of work and conditions of contract are contributory to the abnormally high tenders. The Procuring Entity may also seek written clarification from the tenderer on the reason for the high tender price. The Procuring Entity shall proceed as follows:
  - i) If the tender price is abnormally high based on wrong estimated cost of the contract, the Procuring Entity may accept or not a ccept the tender depending on the Procuring Entity's budget considerations.

- ii) If specifications, scope of work and/or conditions of contract are contributory to the abnormally high tender prices, the Procuring Entity shall reject all tenders and may retender for the contract based on revised estimates, specifications, scope of work and conditions of contract, as the case may be.
- **37.6** If the Procuring Entity determines that the Tender Price is abnormally too high because genuine competition between tenderers is compromised (*often due to collusion, corruption or other manipulations*), the Procuring Entity shall reject all Tenders and shall institute or cause competent Government Agencies to institute an investigation on the cause of the compromise, before retendering.

#### 38.0 Unbalanced and/ or front-loaded tenders

- **38.1** If in the Procuring Entity's opinion, the Tender that is evaluated as the lowest evaluated price is seriously unbalanced and/or frontloaded, the Procuring Entity may require the Tenderer to provide written clarifications. Clarifications may include detailed price analyses to demonstrate the consistency of the tender prices with the scope of works, proposed methodology, schedule and any other requirements of the Tender document.
- **38.2** After the evaluation of the information and detailed price analyses presented by the Tenderer, the Procuring Entity may as appropriate: a) accept the Tender;
  - b) require that the total amount of the Performance Security be increased at the expense of the Tenderer to a level not exceeding a 30% of the Contract Price;
  - c) agree on a payment mode that eliminates the inherent risk of the Procuring Entity paying too much for undelivered works;
  - d) reject the Tender,

#### 39.0 Qualifications of the tenderer

- **39.1** The Procuring Entity shall determine to its satisfaction whether the eligible Tenderer that is selected as having submitted the lowest evaluated cost and substantially responsive Tender, meets the qualifying criteria specified in Section III, Evaluation and Qualification Criteria.
- 39.2 The determination shall be based upon an examination of the documentary evidence of the Tenderer's qualifications submitted by the Tenderer, pursuant to ITT 17. The determination shall not take into consideration the qualifications of other firms such as the Tenderer's subsidiaries, parent entities, affiliates, subcontractors (other than Specialized Sub-contractors if permitted in the Tender document), or any other firm(s) different from the Tenderer.
- **39.3** An affirmative determination shall be a prerequisite for award of the Contract to the Tenderer. A negative determination shall result in disqualification of the Tender, in which event the ProcuringEntityshallproceedto the Tenderer who offers a substantially responsive Tender with the next lowest evaluated price to make a similar determination of that Tenderer's qualifications to perform satisfactorily.

#### 40.0 Lowest evaluated tender

Having compared the evaluated prices of Tenders, the Procuring Entity shall determine the Lowest Evaluated Tender. The Lowest Evaluated Tender is the Tender of the Tenderer that meets the Qualification Criteria and whose Tender has been determined to be:

- a) Mostresponsive to the Tender document; and
- b) the lowest evaluated price.

#### 41.0 Procuring entity's right to accept any tender, and to reject any or all tenders.

The Procuring Entity reserves the right to accept or reject any Tender and to annul the Tender process and reject all Tenders at any time prior to Contract Award, without there by incurring any liability to Tenderers. Incase of annulment, all Tenders submitted and specifically, Tender securities, shall be promptly returned to the Tenderers.

#### F. AWARD OF CONTRACT

#### 42.0 Award criteria

The Procuring Entity shall award the Contract to the successful tenderer whose tender has been determined to be the Lowest Evaluated Tender.

#### 43.0 Notice of Intention to Enter into a Contract/Notification of Award

Uponaward of the contract and Prior to the expiry of the Tender Validity Period the Procuring Entity shall issue a Notification of Intention to Enter into a Contract/Notification of award to all tenderers which shall contain, at a minimum, the following information:

- a) the name and address of the Tenderer submitting the successful tender;
- b) the Contract price of the successful tender;
- c) a statement of the reason(s) the tender of the unsuccessful tenderer to whom the letter is addressed was unsuccessful, unless the price information in (c) above already reveals the reason:
- d) the expiry date of the Standstill Period; and
- e) instruction son how to request a debriefing and/ or submit a complaint during the stand still period;

#### 44.0 Stand still Period

- 44.1 The Contract shall not be signed earlier than the expiry of a Standstill Period of 14 days to allow any dissatisfied tender to launch a complaint. Where only one Tender is submitted, the Standstill Period shall not apply.
- 44.2 Where a Standstill Period applies, it shall commence when the Procuring Entity has transmitted to each Tenderer the Notification of Intention to Enter into a Contract with the successful Tenderer.

#### 45.0 Debriefing by The Procuring Entity

- **45.1** On receipt of the Procuring Entity's Notification of Intention to Enter into a Contract referred to in ITT 43, an unsuccessful tenderer may make a written request to the Procuring Entity for a debriefing on specific issues or concerns regarding their tender. The Procuring Entity shall provide the debriefing within five days of receipt of the request.
- **45.2** Debriefings of unsuccessful Tenderers may be done in writing or verbally. The Tenderer shall bear its own costs of attending such a debriefing meeting.

#### 46.0 Letter of Award

Prior to the expiry of the Tender Validity Period and upon expiry of the Standstill Period specified in ITT 42.1, upon addressing a complaint that has been filed with in the Standstill Period, the Procuring Entity shall transmit the Letter of Award to the successful Tenderer. The letter of award shall request the successful tenderer to furnish the Performance Security within 21 days of the date of the letter.

#### 47.0 Signing of Contract

- **47.1** Upon the expiry of the fourteen days of the Notification of Intention to enter in to contract and upon the parties meeting their respective statutory requirements, the Procuring Entity shall send the successful Tenderer the Contract Agreement.
- **47.2** Within fourteen (14) days of receipt of the Contract Agreement, the successful Tenderer shall sign, date, and returnittotheProcuringEntity.
- 47.3 The written contract shall be entered into within the period specified in the notification of award and before expiry of the tender validity period.

#### 48.0 Performance Security

- 48.1 Within twenty-one (21) days of the receipt of the Letter of Award from the Procuring Entity, the successful Tenderer shall furnish the Performance Security and, any other documents required in the TDS, in accordance with the General Conditions of Contract, subject to ITT 38.2 (b), using the Performance Security and other Forms included in Section X, Contract Forms, or another form acceptable to the Procuring Entity. A foreign institution providing a bank guarantee shall have a correspondent financial institution located in Kenya, unless the Procuring Entity has agreed in writing that a correspondent bank is not required.
- **48.2** Failure of the successful Tenderer to submit the above-mentioned Performance Security and otherdocuments required in the **TDS** or sign the Contract shall constitute sufficient grounds for the annulment of the award and forfeiture of the Tender Security. In that event the Procuring Entity may award the Contract to the Tenderer offering the next Best Evaluated Tender.
- **48.3** Performance security shall not be required for contracts estimated to cost less than the amount specified in the Regulations.

#### 49.0 Publication of Procurement Contract

Within fourteen days after signing the contract, the Procuring Entity shall publish the awarded contract at its notice boards and websites; and on the Website of the Authority. At the minimum, the notice shall contain the following information:

- a) name and address of the Procuring Entity;
- b) name and reference number of the contract being awarded, a summary of its scope and the selection method used;
- c) the name of the successful Tenderer, the final total contract price, the contract duration;
- d) dates of signature, commencement and completion of contract;
- e) names of all Tenderers that submitted Tenders, and their Tender prices as readout at Tender opening.

#### 50.0 Procurement related Complaints and Administrative Review

- 50.1 The procedures for making Procurement-related Complaints are as specified in the TDS.
- **50.2** A request for administrative review shall be made in the form provided under contract forms.

# **Section II - Tender Data Sheet (TDS)**

The following specific data shall complement, supplement, or amend the provisions in the Instructions to Tenderers (ITT). Whenever there is a conflict, the provisions herein shall prevail over those in ITT.

Reference to PARTICULARS OF APPENDIX TO INSTRUCTIONS TO TENDERS
ITC Clause
A. General
The name of the contract isPROPOSED CONSTRUCTION OF PAVI KWALE COOPERATIVE UNION GINNERY AT KINONDO, KWALE COUNTY PHASE 1 (ONE).  The reference number of the Contract isW.P. ITEM NO. D116/CO/KWL/2001 JOB NO. 10826A  The number and identification of lots (contracts) comprising this Tender are [insert number and identification of lots (contracts)]  Lot 1- NameNA  Lot 2- NameNA  Lo NameNA  ETC.
The Information made available on competing firms is as follows: <i>None</i>
ITT 2.4  State Department for Public Works P. O. Box 30743-00100, Nairobi  The roles are defined as follows; Project Manager – Works Secretary Architect - Chief Architect Quantity Surveyor - Chief Quantity Surveyor Civil/Structural Engineer - Chief Structural Engineer Mechanical Engineer - Chief Mechanical Engineer Electrical Engineer – Chief Electrical Engineer
ITT 3.1 Maximum number of members in the Joint Venture (JV) shall be: <i>Not Applicable</i>
B. Contents of Tender Document

ITT 7.1	(i) The Tenderer will submit any request for clarifications in writing at the Address  State Department for Cooperatives.
	Social Security Building, Nairobi.
	Bishop Road
	P.O Box 30547 – 00100
	Nairobi
	to reach the Procuring Entity not later than3 days to the date of submission of tenders
	i) (ii) The Procuring Entity shall publish its response at the website <u>www.ushirika.go.ke</u> and <a href="https://tenders.go.ke">https://tenders.go.ke</a>
ITT 7.2	(A) A pre-arranged pretender site visit <i>SHALL</i> take place at the following date, time and place: 30 <sup>th</sup> October, 2023 at 11:00AM for those who are interested.
Reference to ITC Clause	PARTICULARS OF APPENDIX TO INSTRUCTIONS TO TENDERS
	Date:
	Time:
	Place:
	(B) Pre-Tender meeting <i>SHALL</i> take place at the following date, time and place:
	Date: as per tender advertisement
	Time: as per tender advertisement Place: as per tender advertisement
	1 lace us per tenuer unvertisement
ITT 7.3	The Tenderer will submit any questions in writing, to reach the Procuring Entity not later than

The Procuring Entity's website where Minutes of the pre-Tender meeting and the pre-arranged pretender will be published is <u>www.ushirika.go.ke</u>

ITT 7.5

ITT 9.1	For Clarification of Tender purposes, for obtaining further information and for purchasing tender documents, the Procuring Entity's address is:				
	(1) Name of Procuring Entity STATE DEPARTMENT FOR CO-OPERATIVES				
	(2) Physical address for hand Courier Delivery to an office or Tender Box (City, Street, Building, Floor Number and Room) <i>State Department for Cooperatives</i> ,				
	Social Security Building, Nairobi,				
	Bishop Road.				
	(3) Postal Address <i>P.O. Box 30547 - 00100, Nairobi</i>				
	(1) (4) Hillary Kemboi, Phone; 0725790243 email: <u>procurement@ushirika.go.ke</u>				
	Email Address: www.ushirika.go.ke/ict @ushirika.go.ke				
C. Preparation	of Ten ders				
ITT 11.1 (h)	The Tenderer shall submit the following additional documents in its Tender:  1. Evidence of Personnel Academic & Professional Qualifications				
	2. Evidence of completed projects of similar nature, complexity or magnitude				
	3. Evidence of completed projects of similar nature, complexity or magnitude				
	4. Proof / Evidence of Ownership for all the relevant equipment and transport				
	5. Audited Financial Reports for the last three (3) years (2022, 2021 & 2020) ce of Financial Resources (Cash in hand, lines of credit, overdraft etc) Eviden				
ITT 13.1	Alternative Tenders <i>SHALL NOT</i> be considered. [If alternatives shall be considered, the methodology shall be defined in Section III, Evaluation and Qualification Criteria.]				
ITT 13.2	Alternative times for completion SHALL NOT BE _permitted. [If alternative times for completion are permitted, the evaluation method will be as specified in Section III, Evaluation and Qualification Criteria.]				
ITT 13.4	Alternative technical solutions shall be permitted for the following parts of the Works: <i>NOT APPLICABLE</i>				
Reference to	PARTICULARS OF APPENDIX TO INSTRUCTIONS TO TENDERS				

Reference to ITC Clause	PARTICULARS OF APPENDIX TO INSTRUCTIONS TO TENDERS
ITT 14.5	The prices quoted by the Tenderer shall be: FIXED [insert "subject to adjustment" or "fixed"]
ITT 15.2 (a)	Foreign currency requirements not allowed.

ITT 18.1	The Tender validity period shall beONE HUNDRES AND TWENTY SIX (126) [insert a number of days that is a multiple of seven counting as of the deadline for Tender submission] days.				
ITT 18.3	(a) The Number of days beyond the expiry of the initial tender validity period will be				
	(b) The Tender price shall be adjusted by the following percentages of the tender price:				
	(i) ByNIL% of the local currency portion of the Contract price adjusted to reflect local inflation during the period of extension, and				
	(ii) ByNIL% the foreign currency portion of the Contract price adjusted to reflect the international inflation during the period of extension.				
ITT 19.1	Tender shall provide a Tender-Securing Declaration or a Tender Security (select one) The type of Tender security shall be Kenya shillings One Million, Three Hundred Thousand(Ksh 1,300,000.00)in the amount of Kenya shillings				
ITT 20.1	In addition to the original of the Tender, the number of copies is: ONE				
ITT 20.3	The written confirmation of authorization to sign on behalf of the Tenderer shall consist of: <u>Written</u> <u>power of Attorney</u>				
D. Submissi	on and Opening of Tenders				
ITT 22.1	(A) For <u>Tender submission purposes</u> only, the Procuring Entity's address is:				
	(1) Name of Procuring Entity STATE DEPARTMENT OF CO-OPERATIVES				
	(2) Postal Address (include name of Officer to be attentional) <i>P.O. Box 30547 - 00100, Nairobi</i>				
	(3)Physical address for hand Courier Delivery to an office or Tender Box				
	State Department for Cooperatives,				
	Social Security Building, Nairobi,				
	<b>Bishop Road</b> (4) Date and time for submission of Tenders 4 <sup>TH</sup> SEPTEMBER 2023				
	(5) Tandara shall SHALL NOT SHDMIT tandara shartara isallar				
ITT 25.1	<ul><li>(5) Tenders shall SHALL NOT SUBMIT tenders electronically.</li><li>The Tender opening shall take place at the time and the address for Opening of Tenders provided below:</li></ul>				
	(1) Name of Procuring Entity State Department for Co-operatives				
	(2) Physical address for the location (City, Street, Building, Floor Number and Room) <i>State Department for Cooperatives</i> ,				
	Social Security Building, Nairobi,				
	Bishop Road (3) State date and time of tender opening. 11.00AM ON 4 <sup>TH</sup> SEPTEMBER 2023				
ITT 25.1	If Tenderers are allowed to submit Tenders electronically, they shall follow the electronic tender				
1112011	submission procedures <b>specified below</b> <u>NOT APPLICABLE</u>				

Reference to ITC Clause	PARTICULARS OF APPENDIX TO INSTRUCTIONS TO TENDERS
E El4'	and Comment of Tandam
	and Comparison of Tenders
ITT 30.3	The adjustment shall be based on theAVERAGE price of the item or component as quoted in other substantially responsive Tenders. If the price of the item or component cannot be derived from the price of other substantially responsive Tenders, the Procuring Entity shall use its best estimate.
TT 32.1	The currency that shall be used for Tender evaluation and comparison purposes only to convert at the selling exchange rate all Tender prices expressed in various currencies into a single currency is: Kenya Shillings
	The source of exchange rate shall be: The Central bank of Kenya (mean rate)
	The date for the exchange rate shall be: the deadline date for Submission of the Tenders.
	For comparison of Tenders, the Tender Price, corrected pursuant to ITT 31, shall first be broken down into the respective amounts payable in various currencies by using the selling exchange rates specified by the Tenderer in accordance with ITT 15.1.
	In the second step, the Procuring Entity will convert the amounts in various currencies in which the Tender Price is payable (excluding Provisional Sums but including Daywork where priced competitively) to the single currency identified above at the selling rates established for similar transactions by the authority specified and, on the date, stipulated above.
ITT 33.2	A margin of preference SHALL NOTapply.
ITT 33.4	The invitation to tender is extended to the following group that qualify for ReservationsNOT APPLICABLE
ITT 34.1	At this time, the Procuring Entity DOES NOT INTEND to execute certain specific parts of the Works by subcontractors selected in advance.
ITT 34.2	Contractor's may propose subcontracting: Maximum percentage of subcontracting permitted is:

ITT 34.3	The parts of the Works for which the Procuring Entity permits Tenderers to propose Specialized Subcontractors are designated as follows: Electrical Installation Works Mechanical Installation Works  For the above-designated parts of the Works that may require Specialized Subcontractors, the relevant qualifications of the proposed Specialized Subcontractors will be added to the qualifications of the Tenderer for the purpose of evaluation(Subcontractor qualifications should be as per subcontract works evaluation criteria)
ITT 35.2 (e)	Additional requirements apply. These are detailed in the evaluation criteria in Section III, Evaluation and Qualification Criteria.

Reference to ITC Clause	PARTICULARS OF APPENDIX TO INSTRUCTIONS TO TENDERS
ITT 48.1	Other documents required in addition to the Performance Security are 1.  Program of Works / Progress Chart  2. The bidder before signing the contract should provide proof of registration with National Construction Authority (NCA) category 4 & above(Building works) and current annual contractors practicing license for the same
ITT 50.1	The procedures for making a Procurement-related Complaint are detailed in the "Notice of Intention to Award the Contract" herein and are also available from the PPRA Website <a href="https://www.ppra.go.ke">www.ppra.go.ke</a> or email <a href="mailto:complaints@ppra.go.ke">complaints@ppra.go.ke</a> .  If a Tenderer wishes to make a Procurement-related Complaint, the Tenderer should submit its complaint following these procedures, in writing (by the quickest means available, that is either by hand delivery or email to:  For the attention: [insert full name of person receiving complaints]  Title/position: [insert title/position]  Procuring Entity: [insert name of Procuring Entity]  Email address: [insert email address]  In summary, a Procurement-related Complaint may challenge any of the following (among others):  (i) the terms of the Tender Documents; and  (ii) the Procuring Entity's decision to award the contract.

## **SECTION III - EVALUATION AND QUALIFICATION CRITERIA**

#### 1.0 GENERAL PROVISIONS

- 1.1 This section contains the criteria that the Employer shall use to evaluate tender and qualify tenderers. No other factors, methods or criteria shall be used other than specified in this tender document. The Tenderer shall provide all the information requested in the forms included in Section IV, Tendering Forms. The Procuring Entity shall use the Standard Tender Evaluation Document for Goods and Works for evaluating Tenders.
- 1.2 Wherever a Tenderer is required to state a monetary amount, Tenderers should indicate the Kenya Shilling equivalent using the rate of exchange determined as follows:
  - a) For construction turnover or financial data required for each year Exchange rate prevailing on the last day of the respective calendar year (in which the amounts for that year is to be converted) was originally established.
  - b) Value of single contract Exchange rate prevailing on the date of the contract signature.
  - (c) Exchange rates shall be taken from the publicly available source identified in the ITT 14.3. Any error in determining the exchange rates in the Tender may be corrected by the Procuring Entity.

#### 1.3 EVALUATION AND CONTRACT AWARD CRITERIA

The Procuring Entity shall use the criteria and methodologies listed in this Section to evaluate tenders and arrive at the Lowest Evaluated Tender. The tender that(i) meets the qualification criteria, (ii) has been determined to be substantially responsive to the Tender Documents, and (iii) is determined to have the Lowest Evaluated Tender price shall be selected for award of contract.

#### 2.0 PRELIMINARY EXAMINATION FOR DETERMINATION OF

## **RESPONSIVENESS Preliminary examination for Determination of**

#### Responsiveness

The Procuring Entity will start by examining all tenders to ensure they meet in all respects the eligibility criteria and other mandatory requirements in the ITT, and that the tender is complete in all aspects in meeting the requirements provided for in the preliminary evaluation criteria outlined below. The Standard Tender Evaluation Report Document for Goods and Works for evaluating Tenders provides very clear guide on how to deal with review of these requirements. Tenders that do not pass the Preliminary Examination will be considered non-responsive and will not be considered further.

	PRELIMINARY EVALUATION CRITERIA / MANDATORY REQUIREMENTS FOR MAIN
S/No	CONTRACTOR
MR1	Dully filled and signed form of tender prepared in accordance with ITT 12
MR2	Provide proof of registration with the National Construction Authority (NCA) category 4 and above under builders works category with current annual contractors practicing license.
MR3	Must submit <b>one original and a copy</b> of the Tender Document. Submission of Original in the format required by the procuring entity and all the tender document to be <b>BOUND</b>
MR4	Properly tape bound, paginated or serialized tender document (all pages to be initialized and stamped in chronological order). For pagination, Arabic Numerals shall be used, i.e. 1,2,3,4,5,6,7,8,9,10n (n being the last numerical page of the tender document)-Spring or box files or spiral binding will not be allowed & will result in automatic disqualification

MR5	Tender Security in accordance with ITT 19.1; of Bank Guarantee from a bank approved by Public Procurement			
	Regulatory Authority (PPRA) in the amount of Kenya shillings One Million, Three Hundred Thousand			
	(1,300,000.00). The tender security shall be as per the form included in Section IV, Tender Forms.			
MR6	Provide proof of power of attorney (of tender signatory if not director of the company/ partner, signed and			
	stamped by Commissioner of Oaths)			
MR7	Valid Copy of Certificate of Incorporation/ Registration. (Certified by a Commissioner of Oaths)			
MR8	Valid Current Tax Compliance Certificate			
MR9	Dully filled, signed and stamped Confidential Business Questionnaire			
MR10	Valid Copy of Current Single Business permit (for the year 2023)			
MR11	Submission of valid CR12 form showing the list of directors /shareholding (issued within the last 12months) or			
	National Identity Card(s) for Sole Proprietorship/ Partnership			
MR12	Letter of authority to seek references from the Tenderer's bankers.			
MR13	Must fill and submit the Certificate of Independent Tender Determination in the format provided			
MR14	Must fill and submit the Self-declaration form that the person/tenderer is not debarred in the matter of the Public			
	Procurement and Asset Disposal Act 2015 in the format provided - Form SD1.			
MR15	Must fill and submit the Self-declaration that the person/tenderer will not engage in any corrupt or fraudulent			
	practice in the format provided - Form SD2			
MR16	Must fill and submit Declaration and Commitment to The Code of Ethics in the format provided			
MR17	Domestic Contractor's Agreement- A duly signed and stamped Agreement dated within the period of tender for			
	this works between the Main contractor and the			
	a) Electrical Installation works subcontractor			
	b) Mechanical Installation Works Subcontractor			
	Stating that if the main contractor is awarded the contract, he shall work with the firms as their domestic subcontractors			
	The agreement must be witnessed by an attorney/advocate			
	(Not necessary if the main contractor is registered for specialist work)			
	NB:			
	Bidders who do not satisfy any of the above requirements shall be considered non responsive and their			
	tenders will not be evaluated further.			
	• <i>Preliminary Evaluation</i> for the proposed specialist works listed under ITT 34.3 to be as <i>contained in</i>			
	this volume as per the section below.			
	Order of evaluation of works will be as follows:			
	a) Preliminary evaluation of Main Works			
	b) Preliminary Evaluation of Electrical Works (Includes evaluation of technical			
	specifications)			
	c) Preliminary Evaluation of Mechanical Works (Includes evaluation of technical			
	specifications)			
	d) Technical Evaluation of Main Works			
	• Technical evaluation(schedules & tables to be completed) for the proposed Electrical & Mechanical			
	Installation Works listed under ITT 34.3 to be as contained in the volumes/folio wing sections: -			
	Electrical Installation Works(Volume 2) & Mechanical Installation Works (Volume 3)			

#### PRELIMINARY EVALUATION FOR ELECTRICAL INSTALLATION WORKS

S/No	PRELIMINARY EVALUATION CRITERIA / MANDATORY REQUIREMENTS				
Electrica	Electrical Installation Works				
MR1	Company Certificate of incorporation/registration;				
MR2	Valid Tax Compliance Certificate;				
MR3	Current certificate of Registration with National Construction Authority (NCA 6 and above) in Electrical Installations;				
MR4	Valid Current Annual NCA contractor's Practicing license;				
MR5	Current Class of License with Energy and Petroleum Regulatory Authority (EPRA Class B and above)				
MR6	Compliance with Technical Specifications				

#### Note:

On compliance with Technical Specifications, bidders shall supply equipment/items which comply with the technical specifications set out in the bid document. In this regard, the bidders will be required to submit relevant technical brochures/catalogues with the tender document, highlighting (using a mark-pen or highlighter) the Catalogue Number/model of the proposed items. Such brochures/catalogues should indicate comprehensive relevant data of the proposed equipment/items which should include but not limited to the following:

- (i) Standards of manufacture;
- (ii) Performance ratings/characteristics;
- (iii) Material of manufacture;
- (iv) Electrical power ratings; and
- (v) All other requirements as indicated in the technical specifications of the bid.

The bids will then be analyzed, using the information in the technical brochures, to determine compliance with technical specifications for the works/items as indicated in the tender document. Bidders not complying with any of the technical specifications shall be adjudged technically non- responsive while those meeting all technical specifications shall be considered technically responsive.

The tenderer shall also fill in the Technical Schedule as specified in the tender document for Equipment and Items indicating the Country of Origin, Model/Make/Manufacturer and catalogue numbers of the Items/Equipment they propose to supply

The following table shall be used to determine the bidder's responsiveness to the technical specifications

# **Compliance to Technical Specifications (Electrical Works)**

	DESCRIPTION	Contractor Proposed (Attach Brochures and catalogue)			Compliant/
ITEM	(as described in particular specification)	TYPE/MAKE	MODEL NO.	COUNTRY OF ORIGIN	Compliant
1.0	Light Fittings i. High Bay LED				
	ii. Recessed Circular LED				
	iii. 600x600 LED Panel				
	iv. LED Flood Lightd				
	iv. Exit Signs				
	v.LED Batten fittings				
2.0	Distribution Boards				
3.0	Consumer Units				
4.0	MCB / MCCBs				
5.0	Power Cables				
6.0	Sockets				
7.0	Switches				
8.0	DP Switches				
9.0	SP Isolators				
10.0	TPN Isolators				
11.0	Industrial Sockets				
12.0	Smoke Detectors				
13.0	Fire Alarm Sounders				

14.	0	Fire Alarm Panels		

Bidders who do not satisfy any of the above requirements for the proposed specialist subcontractors shall be considered non responsive and their tenders will not be evaluated further.

## PRELIMINARY EVALUATION FOR MECHANICAL INSTALLATION WORKS

This stage of evaluation shall involve examination of the mandatory requirements as set out in the Tender Advertisement Notice or Letter of Invitation to Tender and any other conditions stated in the bid document.

These conditions shall include the following:

- i) Company Certificate of incorporation/registration
- ii) Current certificate of Registration with National Construction Authority (NCA 8 and above) in Fire Suppression Installation Works.
- iii) Current Annual NCA contractor's Practicing License(s) iv) Valid Tax Compliance Certificate:
- v) Compliance with Technical Specifications

#### ME/1

#### Note

On compliance with Technical Specifications, bidders shall supply equipment/items which comply with the technical specifications set out in the bid document. In this regard, the bidders will be required to submit relevant technical brochures/catalogues with the tender document, highlighting (using a mark-pen or highlighter) the Catalogue Number/model of the proposed items. Such brochures/catalogues should indicate comprehensive relevant data of the proposed equipment/items which should include but not limited to the following:

- (i) Standards of manufacture;
- (ii) Performance ratings/characteristics;
- (iii) Material of manufacture;
- (iv) Electrical power ratings; and
- (v) All other requirements as indicated in the technical specifications of the bid.

The bid will then be analyzed, using the information in the technical brochures, to determine compliance with <u>technical specifications</u> for the works/items as indicated in the tender document. Bidders not complying with **any** of the <u>technical specifications</u> shall be adjudged to be technically non-responsive while those meeting all the technical specifications shall be adjudged to be technically responsive.

The tenderer shall also fill in the Technical Schedule as specified in the tender document for Equipment and Items indicating the Country of Origin, Model/Make/Manufacturer and catalogue numbers of the Items/Equipment they propose to supply.

Bidders who do not satisfy any of the above mandatory requirements shall be considered NonResponsive and their tenders will not be evaluated further.

## 3.0 TENDER EVALUATION (ITT 35)

Price	e evaluation: in addition to the criteria listed in ITT 35.2 (a) $-$ (d) the following criteria shall apply:
(i)	Alternative Completion Times, if permitted under ITT13.2, will be evaluated as follows:
(ii)	Alternative Technical Solutions for specified parts of the Works, if permitted under ITT 13.4, will be evaluated as follows:
(iii)	Other Criteria; if permitted under ITT 35.2(j):

## 4.0 MULTIPLE CONTRACTS

**4.1** Multiple contracts will be permitted in accordance with ITT 35.4. Tenderers are evaluated on basis of Lots and a lowest evaluated tenderer identified for each Lot. The Procuring Entity will select one Option of the two Options listed below for award of Contracts.

## **OPTION 1**

(i) If a tenderer wins only one Lot, the tenderer will be awarded a contract for that Lot, provided the tenderer meets the Eligibility and Qualification Criteria for that Lot.

(ii) Ifatenderer wins more than one Lot, the tender will be awarded a contract for all won Lots, provided the tenderer meetstheaggregate Eligibility and Qualification Criteria for all the won Lots. The tenderer will be awarded only the combinations for which the tenderer qualifies and the others will be considered for award to second lowest the tenderers.

## **OPTION2**

The Procuring Entity will consider all possible combinations of won Lots [contract(s)] and determine the combination with the lowest evaluated price. Tenders will then be awarded to the Tenderer or Tenderers in the combination provided the tenderer meets the aggregate Eligibility and Qualification Criteria for all the won Lots.

## 5.0 ALTERNATIVE TENDERS (ITT 13.1)

## **Alternative Tenders (ITT 13.1)**

Analternative if permitted under ITT 3.1, will be evaluated as follows:

The Procuring Entity shall consider Tenders offered for alternatives as specified in Part 2 - Works requirements. Only the technical alternatives, if any, of the Tenderer with the Best Evaluated Tender conforming to the basic technical requirements shall be considered by the Procuring Entity.

#### 6.0 MARGIN OF PREFERENCE

- 6.1 If the TDS so specifies, the Procuring Entity will grant a margin of preference of fifteen percent (15%) to be loaded on evaluated prices of the foreign tenderers, where the percentage of share holding of Kenyan citizensis less than fifty- one percent (51%).
- 6.2 Contractors shall be asked to provide, as part of the data for qualification, such information, including details of ownership, as shall be required to determine whether, according to the classification established by the Procuring Entity, a particular contractor or group of contractors qualifies for a margin of preference.
- 6.3 After Tenders have been received and reviewed by the Procuring Entity, responsive Tenders shall be assessed to ascertain their percentage of shareholding of Kenyan citizens. Responsive tenders shall be classified into the following groups:
  - i) *Group A:* tenders offered by Kenyan Contractors and other Tenderers where Kenyan citizens hold shares of over fifty one percent (51%). ii) *Group B:* tenders offered by foreign Contractors and other Tenderers where Kenyan citizens hold shares of less than fifty one percent (51%).
- 6.4 All evaluated tenders in each group shall, as a first evaluation step, be compared to determine the lowest tender, and the lowest evaluated tender in each group shall be further compared with each other. If, as a result of this comparison, a tender from Group A is the lowest, it shall be selected for the award of contract. If a tender from Group B is the lowest, an amount equal to the percentage indicated in Item 6.1 of the respective tender price, including unconditional discounts and excluding provisional sums and the cost of day works, if any, shall be added to the evaluated price offered in each tender from Group B. All tenders shall then be compared using new prices with added prices to Group B and the lowest evaluated tender from Group A. If the tender from Group A is still the lowest tender, it shall be selected foraward. If not, the lowest evaluated tender from Group B based on the first evaluation price shall be selected.

#### 7. Post qualification and Contract ward (ITT 39), more specifically,

- a) In case the tender <u>was subject to post-qualification</u>, the contract shall be awarded to the lowest evaluated tenderer, subject to confirmation of pre-qualification data, if so required.
- b) Incase the tender was not subject to post-qualification, the tender that has been determined to be the lowest evaluated tenderer shall be considered for contract award, subject to meeting each of the following conditions.
  - i) The Tenderer shall demonstrate that it has access to, or has available, liquid assets, unencumbered real assets, lines of credit, and other financial means (independent of any contractual advance payment) sufficient to meet the construction cash flow of Kenya Shillings 28,000,000.00. (Attach

evidence in form of letter from bank, overdraft facility, current bank statements for the last 6months)

E/7

ii) Minimum <u>average</u> annual construction turnover of Kenya Shillings **200,000,000.00** \_\_\_\_[insert amount], equivalent calculated as total certified payments received for contracts in progress and/or completed within the last <u>three [3]</u> years.

(Attach evidence in form of audited accounts that are duly signed and stamped by a registered auditor/audit firm(ICPAK); all pages should be initialized)

Atleast *Three (3)* of contract(s) of a similar nature executed within Kenya, or the East African Community or a broad, that have been satisfactorily and substantially completed as a prime contractor, or joint venture member or sub-contractor each of minimum value Kenya shillings

67,000,000.0 equivalent. *Attach evidence of contracts;*Letter of award, contract agreement, acceptance letter and practical completion certificate)

- iv) Contractor's Representative and Key Personnel, which are specified as *listed in the Qualification Form.*
- v) Contractors key equipment listed on the table "Contractor's Equipment" below and more specifically

listed as [specify requirements for each lot as applicable]\_iv) Other conditions depending on their seriousness.

## a) History of non-performing contracts:

Tenderer and each member of JV in case the Tenderer is a JV, shall demonstrate that Non-performance of a contract did not occur because of the default of the Tenderer, or the member of a JV in the last *3 years*. The required information shall be furnished in the appropriate form.

## b) **Pending Litigation**

Financialpositionandprospectivelong-termprofit ability of the Single Tenderer, and in the case the Tenderer is a JV, of each member of the JV, shall remain sound according to criteria established with respect to Financial Capability under Paragraph (i) above if all pending litigation will be resolved against the Tenderer. Tenderer shall provide information on pending litigations in the appropriate form.

## c) LitigationHistory

There shall be no consistent history of court/arbitral award decisions against the Tenderer, in the last \_\_\_\_\_\_\_3 years. All parties to the contract shall furnish the information in the appropriate form about any litigation or arbitration resulting from contracts completed or on going unde rits execution over the years specified. A consistent history of awards against the Tenderer or any member of a JV may result in rejection of the tender.

**QUALIFICATION FORM\*** 

1	2	3	4	5
Item No.	Qualification Subject	Qualification Requirement	Document To be Completed by Tenderer	For Procuring Entity's Use (Qualification met or Not Met)
1	Nationality	Nationality in accordance with ITT 3.6	Forms ELI – 1.1 and 1.2, with attachments	
2	Tax Obligations for Kenyan Tenderers	Has produced a current tax clearance certificate or tax exemption certificate issued by Kenya Revenue Authority in accordance with ITT 3.14.	Attachment	
3	Conflict of Interest	No conflicts of interest in accordance with ITT 3.3	Form of Tender	
4	PPRA Eligibility	Not having been declared ineligible by the PPRA as described in ITT 3.7	Form of Tender	
5	State- owned Enterprise	Meets conditions of ITT 3.8	Forms ELI – 1.1 and 1.2, with attachments	
6	Goods, equipment and services to be supplied under the contract	To have their origin in any country that is not determined ineligible under ITT 4.1	Forms ELI – 1.1 and 1.2, with attachments	
7	History of Non- Performing Contracts	Non-performance of a contract did not occur as a result of contractor default since 1 <sup>st</sup> January [].	Form CON-2	
8	Suspension Based on Execution of Tender/Proposal Securing Declaration by the Procuring Entity	Not under suspension based on-execution of a Tender/Proposal Securing Declaration pursuant to ITT 19.9	Form of Tender	
9	Pending Litigation	Tender's financial position and prospective long-term profitability still sound according to criteria established in 3.1 and assuming that all pending litigation will NOT be resolved against the Tenderer.	Form CON – 2	
10	Litigation History	No consistent history of court/arbitral award decisions against the Tenderer since 1st January 2020.	Form CON – 2	
11	Financial Capabilities	(i) The Tenderer shall demonstrate that it has access to, or has available, liquid assets, unencumbered real assets, lines of credit, and other financial means (independent of any contractual advance payment) sufficient to meet the construction cash flow requirements estimated as Kenya Shillings [28,000,000.00] equivalent for the subject contract(s) net of the Tenderer's other commitments.  .(Attach letter from bank, overdraft facility, current bank statements for the last 6 months)	Form FIN – 3.1, with attachments	

1	2	3	4		5
				ed	For Procuring Entity's
Iten No.	n Qualification Subject	Qualification Requirement	Document To be Comple by Tenderer		Use (Qualification met or Not Met)
		(ii) The Tenderers shall also demonstrate, to the satisfaction of the Procuring Entity, that it has adequate sources of finance to meet the cash flow requirements on works currently in progress and for future contract commitments.			
		(iii) The audited balance sheets or, if not required by the laws of the Tenderer's country, other financial statements acceptable to the Procuring Entity, for the last <i>3</i> years shall be submitted and must demonstrate the current soundness of the Tenderer's financial position and indicate its prospective long-term profitability.			
12	Average Annual Construction Turnover	Minimum average annual construction turnover of Kenya Shillings 200,000,000.00 equivalent calculated as total certified payments received for contracts in progress and/or completed within the last 3 years, divided by 3 years.  Attach evedince of audited accounts that are duly signed and stamped by a registered auditor/audit firm(ICPAK); all pages should be initialized)	Form FIN – 3.2		
13	General Construction Experience	Experience under construction contracts in the role of prime contractor, JV member, sub-contractor, or management contractor for at least the last 5 years, starting 1st January [2017]. (Tenderer to attach atleast 3 contracts with evidence such as copies of letter of award, Signed contract and copies of interim payment certificates, completion certificates)	Form EXP – 4.1		

	Specific Construction &	A minimum number of [3] similar contracts specified below	Form EXP 4.2(a)	
14	Contract Management	that have been satisfactorily and substantially completed as a		
	Experience	prime contractor, joint venture member, management		
	-	contractor or sub-contractor between 1st January 2017 and		
		tender submission deadline i.e 3 contracts, each of		
		minimum value Kenya shillings67,000,000.00		
		equivalent.		
		Bidders shall attach copies of the following:		
		a) Letters of Award or,		
		b) Signed Contract and Completion Certificate for the		
		respective projects. or		
		If project is ongoing it must be at least 80% complete. Bidder		
		to attach copies of interim payment certificates		
		[In case the Works are to be tender as individual contracts		
		under multiple contract procedure, the minimum number of		

1	2	3	4	5
Item	Qualification Subject	Qualification Requirement	Document To be Completed by	For Procuring Entity's
No.			Tenderer	Use (Qualification met or Not Met)
		contracts required for purposes of evaluating qualification shall be selected from the options mentioned in ITT 35.4]		
		The similarity of the contracts shall be based on the following: [Based on Section VII, Scope of Works, specify the minimum key requirements in terms of physical size, complexity, construction method, technology and/or other characteristics including part of the requirements that may be met by specialized subcontractors, if permitted in accordance with ITT 34.3]		

Item No.	Qualification Subject	Qualification Requirement	Document To be Completed by Tenderer	For Procuring Entity's Use (Qualification met or Not Met
	1. Equipment			
5.1	Contractors key equipment	<ol> <li>Pick up (2 tonne) – Three(3)</li> <li>Tipper (10 Tonnes) – Five(5)</li> <li>Backhoe (1.2CM) – Two (2)</li> <li>Diesel Generator (200KvA) – One(1)</li> <li>Water Bowser (20,000L) – Two (2)</li> <li>Concrete Pump – One (1)</li> <li>If the equipment is owned, must provide CLEAR copies of logbook or proof of ownership.</li> <li>If equipment is hired or leased Provide a commitment letter from the lessor of the equipment addressed to the Principal Secretary—State Department for Co-operatives indicating that the lessor shall avail the equipment upon award of the tender and submit a copy of a written agreement to lease between lessee and lessor indicating list of equipment and their corresponding copies of log books or proof of ownership by lessor;</li> <li>The equipment listed shall be available on site when required</li> </ol>	Form EQU: Equipment	

Item No.	Qualification Subject	Qualification Requirement	Document To be Completed by Tenderer	For Procuring Entity's Use (Qualification met or Not Met)	
2. Key Personnel					

6.1	Contractor's Representative	a) Project Manager	Form PER -1 &	
0.1	and Key Personnel	Minimum qualifications and technical experience	Form PER -2	
	4114 120j 1 6188111161	Bachelor's degree in Architecture, Quantity Surveying,	FOIIII PER -2	
		Construction Management or Civil / Structural		
		Engineering.		
		2. Registered Professional with the respective registration		
		bodies Engineers Board of Kenya (EBK) or Board of		
		Registration of Architects and Quantity Surveyors (BORAQS) with a valid practicing license - Mandatory		
		3. General Experience –10 years.		
		4. Specific experience on Construction of building works –		
		10 years.		
		b) Site Agent		
		Minimum qualifications and technical experience		
		1. Higher Diploma in Building		
		Construction or equivalent.		
		2. Specific experience on Construction of building works –		
		7 years.		
		c) Foreman		
		Minimum qualifications and technical experience		
		1. Certificate- Building Construction, Electrical, Mechanical		
		2. Experience – 5 years		
		d) Artisans		
		Minimum qualifications and technical experience		
		1 Trade Test certificate in relevant field		
		2 Experience-5 years		
		e) Occupational Health and Safety Personnel		
		Qualifications and technical experience		
		1. Certificate- Occupational Safety and Health		
		2. Experience – 5 years		

	Note: Certified copies of certificates to be provided as	
	evidence.	

## **SECTION IV - TENDERING FORMS**

## **QUALIFICATION FORMS**

## 1. FOREIGN TENDERERS 40% RULE

Pursuant to ITT 3.9, a foreign tenderer must complete this form to demonstrate that the tender fulfils this condition.

ITEM	Description of Work Item	Describe location of Source	COST in K. shillings	Comments, if any
A	Local Labor			
1				
2				
3				
4				
5				
В	Sub contracts from Local source	es		
1				
2				
3				
4				
5				
С	Local materials			
1				
2				
3				
4				
5				
D	Use of Local Plant and Equipme	ent	1	,
1				
2				
3				
4				
5				
Е	Add any other items			
1				
2				
3				
4				
5				
6				
	TOTAL COST LOCAL CONTE	ENT	XXXXX	
	PERCENTAGE OF CONTRAC			

## 2. FORMEQU: EQUIPMENT

The Tenderer shall provide adequate information to demonstrate clearly that it has the capability to meet the requirements for the key equipment listed in Section III, Evaluation and Qualification Criteria. A separate Form shall be prepared for each item of equipment listed, or for ralternative equipment proposed by the Tenderer.

Item of equipm	ent			
Equipment information	Name of manufacturer	Model and power rating		
	Capacity	Year of manufacture		
Current status	S Current location			
	Details of current commitments			
Source	Indicate source of the equipment  ☐ Owned ☐ Rented ☐ Leased	☐ Specially manufactured		

Omit the following information for equipment owned by the Tenderer.

Owner	Name of owner		
	Address of owner		
	Telephone	Contact name and title	
	Fax	Telex	
Agreements	Details of rental / lease / manufacture agree	ements specific to the project	

## 3. **FORM PER -1**

## **Contractor's Representative and Key Personnel Schedule**

Tenderers should provide the names and details of the suitably qualified Contractor's Re presentative and Key Personnel to perform the Contract. The data on their experience should be supplied using the Form PER-2 below for each candidate.

## **Contractor' Representative and Key Personnel**

1.	Title of position: Contractor's Representative				
	Name of candidate:				
	<b>Duration of</b>	[insert the whole period (start and end dates) for which this position will be			
	appointment:	engaged]			
	Time commitment: for	[insert the number of days/week/months/ that has been scheduled for this			
	this position:	position]			
	<b>Expected time schedule</b>	[insert the expected time schedule for this position (e.g. attach high level			
	for this position:	Gantt chart]			
2.	Title of position: [	J			
	Name of candidate:				
	<b>Duration of</b>	[insert the whole period (start and end dates) for which this position will be			
	appointment:	engaged]			
	Time commitment: for	[insert the number of days/week/months/ that has been scheduled for this			
	this position:	position]			
	<b>Expected time schedule</b>	[insert the expected time schedule for this position (e.g. attach high level			
	for this position:	Gantt chart]			
3.	Title of position: [	Title of position: [			
	Name of candidate:				
	<b>Duration of</b>	[insert the whole period (start and end dates) for which this position will be			
	appointment:	engaged]			
	Time commitment: for	[insert the number of days/week/months/ that has been scheduled for this			
	this position:	position]			
	<b>Expected time schedule</b>	[insert the expected time schedule for this position (e.g. attach high level			
	for this position:	Gantt chart]			
4.	Title of position: [	Title of position: []			
	Name of candidate:				
	<b>Duration of</b>	[insert the whole period (start and end dates) for which this position will be			
	appointment:	engaged]			
	Time commitment: for	[insert the number of days/week/months/ that has been scheduled for this			
	this position:	position]			
	<b>Expected time schedule</b>	[insert the expected time schedule for this position (e.g. attach high level			
	for this position:	Gantt chart]			
<b>5.</b>	Title of position: [insert tit	le]			
	Name of candidate				
	<b>Duration of</b>	[insert the whole period (start and end dates) for which this position will be			
	appointment:	engaged]			
	Time commitment: for	[insert the number of days/week/months/ that has been scheduled for this			
	this position:	position]			

<b>Expected time schedule</b>	[insert the expected time schedule for this position (e.g. attach high level
for this position:	Gantt chart]

# 4. <u>FORM PER - 2:</u>

Resume and Declaration - Contractor's Representative and Key Personnel.

Name of Tenderer		

Position [#1]:	[title of position from Form PER-1]			
Personnel information	Name:	Date of birth:		
IIIIOIIIIatioii	A 11	T 1		
	Address:	E-mail:		
	Professional qualifications:			
	Academic qualifications:			
	Language proficiency: [language and levels of speaking, reading and writing skills]			
Details				
	Address of Procuring Entity:			
	Telephone:	Contact (manager / personnel officer):		
	Fax:			
	Job title:	Years with present Procuring Entity:		

Summarize professional experience in reverse chronological order. Indicate particular technical and managerial experience relevant to the project.

Project	Role	Duration of involvement	Relevant experience
[main project details]	[role and responsibilities on the project]	[time in role]	[describe the experience relevant to this position]

#### **Declaration**

I, the undersigned [insert either "Contractor's Representative" or "Key Personnel" as applicable], certify that to the best of my knowledge and belief, the information contained in this Form PER-2 correctly describes myself, my qualifications and my experience.

I confirm that I am available as certified in the following table and throughout the expected time schedule for this position as provided in the Tender:

Commitment	Details
Commitment to duration of contract:	[insert period (start and end dates) for which this
	Contractor's Representative or Key Personnel is available
	to work on this contract]
Time commitment:	[insert period (start and end dates) for which this
	Contractor's Representative or Key Personnel is available
	to work on this contract]

I understand that any misrepresentation or omission in this Form may:

(a) be taken into consideration during Tender evaluation; (b) result in my disqualification from participating in the Tender; (c) result in my dismissal from the contract.

Name of Contractor's Representative or Key Personnel: [insert name]
Signature:
Date: (day month year):
Countersignature of authorized representative of the Tenderer:
Signature:
Date: (day month year):

# 5. TENDERERS QUALIFICATION WITHOUT PREQUALIFICATION

To establish its qualifications to perform the contract in accordance with Section III, Evaluation and Qualification Criteria the Tenderer shall provide the information requested in the corresponding Information Sheets included hereunder.

# 5.1 FORM ELI -1.1

Tenderer InformationForm
Date:
ITT No. and title:
Tenderer's name
In case of Joint Venture (JV), name of each member:
Tenderer's actual or intended country of registration:
[indicate country of Constitution]
Tenderer's actual or intended year of incorporation:
Tenderer's legal address [in country of registration]:
Tenderer's authorized representative information
Name:
Address:
Telephone/Fax numbers:
E-mail address:
<ul> <li>1. Attached are copies of original documents of</li> <li>□ Articles of Incorporation (or equivalent documents of constitution or association), and/or documents of registration of the legal entity named above, in accordance with ITT 3.6</li> <li>□ In case of JV, letter of intent to form JV or JV agreement, in accordance with ITT 3.5</li> <li>□ In case of state-owned enterprise or institution, in accordance with ITT 3.8, documents establishing: □ Legal and financial autonomy</li> <li>□ Operation under commercial law</li> <li>1. Establishing that the Tenderer is not under the supervision of the Procuring Entity</li> </ul>
2. Included are the organizational chart and a list of Board of Directors
5.2 FORM ELI -1.2
Tenderer's JV Information Form (to be completed for each member of Tenderer's JV)  Date:
ITT No. andtitle:
Tenderer's JV name:
JV member's name:
JV member's country of registration:
JV member's year of constitution:
JV member's legal address in country of constitution:

JV mem	ber's authorized re	epresentative information	
Name: _			
Address	·		
Telephor	ne/Fax numbers: _		
E-mail a	ddress:		
registrat autonom the Proc	Articles of Incorportion documents of In case of a state-oxy, operation in accurring Entity, in accurrence accurren	original documents of constitution or associated the legal entity named above, in accordance with ITT 3.6 owned enterprise or institution, documents establishing legordance with commercial law, and that they are not undecordance with ITT 3.5.  Exational chart and a list of Board of Directors.	gal and financial
5.3 <u>FC</u>	ORM CON -2		
Historica	al Contract Non	-Performance, Pending Litigation and Litigation	History
	Name:		
Date:			
JV Membe	er's Name		
ITT No. aı	nd title:		
NI D C	10	1 '4 C ' III F 1 ' 10 1'C '	G.; ;
		a accordance with Section III, Evaluation and Qualification	
		mance did not occur since 1 <sup>st</sup> January <i>[insert year]</i> specin Criteria, Sub-Factor 2.1.	fied in Section III,
Lvaruation	i and Quanneacion	i Criteria, Suo-i actor 2.1.	
□ C	ontract(s) not perf	ormed since 1st January [insert year] specified in Section	III, Evaluation and
	ion Criteria, requi		,
	-		
□ C	ontract(s) withdra	wn since 1st January [insert year] specified in Section III	, Evaluation and
Qualificat			
	equirement 2.1		
Year	-	Contract Identification	Total Contract Amount
	portion of contract		(current value, currency, exchange rate and Kenya Shilling equivalent)
[insert	[insert amount	Contract Identification: [indicate complete contract	[insert amount]
year]	<u> </u>	name/ number, and any other identification]	<u> </u>
	1	Name of Procuring Entity: [insert full name]	
		Address of Procuring Entity: [insert street/city/country]	
		Reason(s) for nonperformance: [indicate main	
		reason(s)]	
		dance with Section III, Evaluation and Qualification Crit	
		on in accordance with Section III, Evaluation and Qualific	
	~ ~	accordance with Section III, Evaluation and Qualification	on Criteria, Sub-Factor 2.3
as indicate	ea below.		

Year of dispute	Amount in dispute (currency)	Contract Identification	Total Contract Amount (currency), Kenya Shilling Equivalent
			(exchange rate)
		Contract Identification:	
		Name of Procuring Entity:	
		Address of Procuring Entity:	
		Matter in dispute:	
		Party who initiated the dispute:	
		Status of dispute:	
		Contract Identification:	
		Name of Procuring Entity:	
		Address of Procuring Entity:	
		Matter in dispute:	
		Party who initiated the dispute:	
		Status of dispute:	
Litigation Hist	ory in accordance with	Section III, Evaluation and Qualification Crite	ria
2.4.	tion History in accorda	rdance with Section III, Evaluation and Qualifince with Section III, Evaluation and Qualification	•
Year of	Amount in dispute	Contract Identification	<b>Total Contract Amount</b>
dispute	(currency)		(currency), Kenya Shilling Equivalent (exchange rate)
[insert	[insert percentage]	Contract Identification: [indicate complete	[insert amount]
year]		contract name, number, and any other	
		identification]	
		Name of Procuring Entity: [insert full name]	
		Address of Procuring Entity: [insert	
		street/city/country]	
		Matter in dispute: [indicate main issues in dispute]	
		Party who initiated the dispute: [indicate	
		"Procuring Entity" or "Contractor"]	
		Reason(s) for Litigation and award decision	
		` /	
		[indicate main reason(s)]	

Include details relating to potential bid-rigging practices such as previous occasions where tenders were withdrawn, joint bids with competitors, subcontracting work to unsuccessful tenderers, etc.

# 5.4 **FORM FIN – 3.1:**

Tenderer's Name:

# **Financial Situation and Performance**

Date:

JV Me	ember's				
Name					
ITT No. and title:					
5.4.1. Financial Data					
Type of Financial information	Historic i	nformation f	or previous	vec	ırs
in	1115001101		or provious _		
(currency)	(amount	in currency, o	currency, excl	nange rate*,	USD
	equivalen	it)			
	Year 1	Year 2	Year 3	Year 4	Year 5
Statement of Financial Position (In	nformation fi	om Balance S	Sheet)		
Total Assets (TA)					
Total Liabilities (TL)					
Total Elabilities (TE)					
Tatal Equitar/Niat Wanth (NW)					
Total Equity/Net Worth (NW)					
Current Assets (CA)					
C (IIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIII					
Current Liabilities (CL)					
W. L. G. S. L. (WG)					
Working Capital (WC)					
Information from Income Stateme	nt				
Total Revenue (TR)					
Profits Before Taxes (PBT)					
Cash Flow Information					
Cash flow information					
Cash Flow from Operation	ng				
Activities					

<sup>\*</sup>Refer to ITT 15 for the exchange rate

#### **5.4.2** Sources of Finance

Specify sources of finance to meet the cash flow requirements on works currently in progress and for future contract commitments.

No.	Source of finance	Amount (Kenya Shilling equivalent)
1		
2		
3		

### 5.4.3 Financial documents

The Tenderer and its parties	shall provide copies of financial statements for	years pursuant Section III,
Evaluation and Qualifications	s Criteria, Sub-factor 3.1. The financial statements sha	all:

- (a) reflect the financial situation of the Tenderer or in case of JV member, and not an affiliated entity (such as parent company or group member).
- (b) be independently audited or certified in accordance with local legislation.
- (c) be complete, including all notes to the financial statements.
- (d) correspond to accounting periods already completed and audited.

☐ Attached are copies of financial statements¹	for the	years required	above; and	d complying	with the
requirements					

<sup>&</sup>lt;sup>1</sup> If the most recent set of financial statements is for a period earlier than 12 months from the date of Tender, the reason for this should be justified.

# 5.5 **FORM FIN – 3.2:**

# **Average Annual Construction Turnover**

Tenderer's Name:	
Date:	
JV Member's Name_	
ITT No. and title:	

	Annual turnove	r data (construction only)	
Year	Amount	<b>Exchange rate</b>	Kenya Shilling equivalent
	Currency		
[indicate year]	[insert amount and indicate		
	currency]		
Average			
Annual			
Construction			
Turnover *			

<sup>\*</sup> See Section III, Evaluation and Qualification Criteria, Sub-Factor 3.2.

## 5.6 **FORM FIN – 3.3:**

#### **Financial Resources**

Specify proposed sources of financing, such as liquid assets, unencumbered real assets, lines of credit, and other financial means, net of current commitments, available to meet the total construction cash flow demands of the subject contract or contracts as specified in Section III, Evaluation and Qualification Criteria

Fina	Financial Resources		
No.	Source of financing	Amount (Kenya Shilling equivalent)	
1			
2			
3			

## 5.7 FORM FIN - 3.4:

## **Current Contract Commitments / Works in Progress**

Tenderers and each member to a JV should provide information on their current commitments on all contracts that have been awarded, or for which a letter of intent or acceptance has been received, or for contracts approaching completion, but for which an unqualified, full completion certificate has yet to be issued.

Curren	t Contract Commitments	S			
No.	Name of Contract	Procuring Entity's Contact Address, Tel,	Value of Outstanding Work [Current Kenya Shilling /month Equivalent]	Estimated Completion Date	Average Monthly Invoicing Over Last Six Months [Kenya Shilling /month)]
1					
2					
3					
4					
5					

# 5.8 **FORM EXP - 4.1**

# **General Construction Experience**

Name		JV Member's	
TT No. an	nd title:	<del></del>	
Page		_ofpages	
Starting	Ending Year	Contract Identification	Role of Tenderer
Year			
		Contract name:	
		Brief Description of the Works performed by the	
		Tenderer:	
		Amount of contract:	
		Name of Procuring Entity:	
		Address:	
		Contract name:	
		Brief Description of the Works performed by the	
		Tenderer:	
		Amount of contract:	
		Name of Procuring Entity:	
		Address:	
		Contract name:	
		Brief Description of the Works performed by the	
		Tenderer:	
		Amount of contract:	
		Name of Procuring Entity:	
		Address:	

Tenderer's Name: \_\_\_\_\_\_
Date: \_\_\_\_\_
JV Member's Name\_\_\_\_\_

Similar Contract No.	Information			
Contract Identification				
Award date				
Completion date				
Role in Contract	Prime Contractor □	Member in JV □	Management Contractor  □	Sub- contractor
Total Contract Amount			Kenya Shilling	
If member in a JV or sub-contractor, specify participation in total Contract amount				
Procuring Entity's Name:			·	
Address: Telephone/fax number E-mail:				
Date: JV Member's Name ITT No. and title:				
Similar Contract No.	Information			
Contract Identification				
Award date				
Completion date				
Role in Contract	Prime Contractor □	Member in JV □	Management Contractor □	Sub- contractor
Total Contract Amount			Kenya Shilling	
If member in a JV or sub-contractor, specify participation in total Contract amount				
Procuring Entity's Name:				
Address: Telephone/fax number E-mail:				

# 5.9 **FORM EXP - 4.2 (a) (cont.)**

# **Specific Construction and Contract Management Experience (cont.)**

Simila	r Contract No.	Information		
	Description of the similarity in accordance			
with S	ub-Factor 4.2(a) of Section III:			
1.	Amount			
2.	Physical size of required works			
items				
3.	Complexity			
4.	Methods/Technology			
5.	Construction rate for key activities			
6.	Other Characteristics			

# 5.10 **FORM EXP - 4.2(b)**

# **Construction Experience in Key Activities**

Tenderer's Name:					
Date:					
Tenderer's JV Member Name:					
Sub-contractor's Name <sup>2</sup> (as per ITT 34):					
ITT No. and title:	_				
All Sub-contractors for key activities m			nformation	n in this form a	s per ITT 34
Evaluation and Qualification Criteria, S	Sub-Factor 4.2	2.			
1. Key Activity No One: _					
	Information				
Contract Identification					
Award date					
Completion date					
Role in Contract	Prime	Mei	mber in	Management	Sub-
	Contractor	JV		Contractor	contractor
Total Contract Amount				Kenya Shillin	g
Quantity (Volume, number or rate of	Total quantity		Percentag	ge	Actual
production, as applicable) performed under	the contract (i)	)	participat	ion	Quantity
the contract per year or part of the year			(ii)		Performed
X7 4					(i) x (ii)
Year 1					
Year 2					
Year 3					
Year 4					
Procuring Entity's Name:					
Address:					
Telephone/fax number E-					
mail:					

<sup>&</sup>lt;sup>2</sup> If applicable

	Information
Description of the key activities in accordance with Sub-Factor 4.2(b) of Section III:	

3. .....

## **OTHER FORMS**

## 6. FORM OF TENDER

# (Amended and issued pursuant to PPRA CIRCULAR No. 02/2022)

#### INSTRUCTIONS TO TENDERERS

- i) All italicized text is to help the Tenderer in preparing this form.
- ii) The Tenderer must prepare this Form of Tender on stationery with its letterhead clearly showing the Tenderer's complete name and business address. Tenderers are reminded that this is a mandatory requirement.

Date of this Tender submission:.............[insert date (as day, month and year) of Tender submission] Tender

iii) Tenderer must complete and sign CERTIFICATE OF INDEPENDENT TENDER DETERMINATION and the SELF DECLARATION FORMS OF THE TENDERER as listed under (xxii) below.

Nam	e and	Identification:[insert	identification] Alternative
No.:.		[insert identification No if this is a Ten	der for an alternative]
То:	[I	Insert complete name of Procuring Entity]	
for	Tender No.: [insert id	ssion: [insert date (as day, month and year) of entification] Name and description of Tender this is a Tender for an alternative]	
To:	[insert complete name	of Procuring Entity]	
Dea	ar Sirs,		
1.	of the above named V defects therein for the	Conditions of Contract, Specifications, Drawin Works, we, the undersigned offer to construct sum <sup>3</sup> of Kenya Shillings [[Amount in figures]_	and complete the Works and remedy any Kenya Shillings
		eludes foreign currency <sup>4</sup> amount (s) of [state fig	gure or a percentage and currency]

<sup>&</sup>lt;sup>3</sup> This sum should be carried forward from the Summary of the Bills of Quantities.

<sup>&</sup>lt;sup>4</sup> The percentage quoted above should not include provisional sums, and not more than two foreign currencies are allowed.

\_\_\_\_\_\_\_

2. We undertake, if our tender is accepted, to commence the Works as soon as is reasonably possible after the receipt of the Architect notice to commence, and to complete the whole of the Works comprised in the Contract within the time stated in the Special Conditions of Contract.

- 3. We agree to adhereby this tender until\_\_\_\_\_[Insert date], and it shall remain binding upon us and may be accepted at any time before that date.
- 4. We understand that you are not bound to accept the lowest or any tender you may receive.
- 5. We, the under signed, further declare that:
  - i) <u>No reservations</u>: We have examined and have no reservations to the tender document, including Addenda issuedinaccordance with ITT 28;
  - ii) <u>Eligibility:</u> We meet the eligibility requirements and have no conflict of interest in accordance with ITT 3 and 4:
  - iii) <u>Tender Securing Declaration</u>: We have not been suspended nor declared ineligible by the Procuring Entity based on execution of a Tender-Securing or Proposal-Securing Declaration in the Procuring Entity's Country in accordance with ITT 19.8;
  - iv) <u>Conformity</u>: We offer to execute in conformity with the tendering documents and in accordance with the implementation and completion specified in the construction schedule, the following Works: [insert a brief description of the Works];
  - v) <u>Tender Price:</u> The total price of our Tender, excluding any discounts offered in item 1 above is: [Insert one of the options below as appropriate]
  - vi) Option 1, incase of one lot: Total priceis: [insert the total price of the Tender in words and figures, indicating the various amounts and the respective currencies]; or

#### Option2, in case of multiple lots:

- (a) Total price of each lot [insert the total price of each lot in words and figures, indicating the various amounts and the respective currencies]; and
- (b) <u>Total price of all lots</u> (sum of all lots) [insert the total price of all lots in words and figures, indicating the various amounts and the respective currencies];
- vii) Discounts: The discounts offered and the methodology for their application are:
- viii) The discounts offered are: [Specify in detail each discount offered.]
- ix) The exact method of calculations to determine the net price after application of discounts is shown below: [Specify in detail the method that shall be used to apply the discounts];
- x) <u>Tender Validity Period</u>: Our Tender shall be valid for the period specified in TDS 18.1 (as amended, if applicable) from the date fixed for the Tender submission deadline specified in TDS 22.1 (as amended, if applicable), and it shall remain binding upon us and may be accepted at any time before the expiration of that period;
- xi) <u>Performance Security:</u> If our Tender is accepted, we commit to obtain Performance Security in accordance with the Tendering document;

- xii) One Tender Per Tender: Weare not submitting any other Tender(s) as an individual Tender, and we are not participating in any other Tender(s) as a Joint Venture member or as a sub-contractor, and meet the requirements of ITT 3.4, other than alternative Tenders submitted in accordance with ITT 13.3;
- xiii) <u>Suspension and Debarment</u>: We, along with any of our subcontractors, suppliers, Engineer, manufacturers, or service providers for any part of the contract, are not subject to, and not controlled by any entity or individual that is subject to, a temporary suspension or a debarment imposed by the Public Procurement Regulatory Authority or any other entity of the Government of Kenya, or any international organization.
- xiv) <u>State-owned enterprise or institution:</u> [select the appropriate option and delete the other] [We are not a state-owned enterprise or institution]/[We are a state-owned enterprise or institution but meet the requirements of ITT3.8];
- xv) <u>Commissions, gratuities, fees</u>: We have paid, or will pay the following commissions, gratuities, or fees with respect to the tender process or execution of the Contract: [insert complete name of each Recipient, its full address, the reason for which each commission or gratuity was paid and the amount and currency of each such commission or gratuity].

Name of Recipient	Address	Reason	Amount

(If none has been paid or is to be paid, indicate "none.")

- xvi) <u>Binding Contract:</u> We understand that this Tender, together with your written acceptance there of included in your Letter of Acceptance, shall constitute a binding contract between us, until a formal contract is prepared and executed;
- xvii) Not Bound to Accept: We understand that you are not bound to accept the lowest evaluated cost Tender, the Most Advantageous Tender or any other Tender that you may receive;
- xviii) <u>Fraud and Corruption:</u> We here by certify that we have taken steps to ensure that no personacting for us or on our behalf engages in any type of Fraud and Corruption; and
- xix) <u>Collusive practices:</u> We hereby certify and confirm that the tender is genuine, non-collusive and made with the intention of accepting the contract if awarded. To this effect we have signed the "Certificate of Independent Tender Determination" attached below.
- xx) We undertake to adhere by the Code of Ethics for Persons Participating in Public Procurement and Asset Disposal, copy available from *(specify website)* during the procurement process and the execution of any resulting contract.
- xxi) **Beneficial Ownership Information:** We commit to provide to the procuring entity the Beneficial Ownership Information in conformity with the Beneficial Ownership Disclosure Form upon receipt of notification of intention to enter into a contract in the event we are the successful tenderer in this subject procurement proceeding.
- xxii) We, the Tenderer, have duly completed, signed and stamped the following Forms as part of our Tender:
  - (a) Tenderer's Eligibility; Confidential Business Questionnaire to establish we are no tin any conflict to interest.
  - (b) Certificate of Independent Tender Determination to declare that we completed the tender without colluding with other tenderers.

- (a) Self-Declaration of the Tenderer to declare that we will, if awarded a contract, not engage in any form of fraud and corruption.
- (d) Declaration and commitment to the Code of Ethics for Persons Participating in Public Procurement and Asset Disposal.

Further, we confirm that we have read and understood the full content and scope of fraud and corruption as informed in "Appendix 1 - Fraud and Corruption" attached to the Form of Tender.

Name of the Tenderer: \*[insert complete name of person signing the Tender]

Name of the person duly authorized to sign the Tender on behalf of the Tenderer: \*\*[insert complete name of person duly authorized to sign the Tender]

**Title of the person signing the Tender**: [insert complete title of the person signing the Tender]

**Signature of the person named above**: [insert signature of person whose name and capacity are shown above]

Datesioned	davof	

#### Notes

## (a) TENDERER'S ELIGIBILITY-CONFIDENTIAL BUSINESS QUESTIONNAIRE

**Date signed** [insert date of signing] day of [insert month], [insert year]

### **Instruction to Tenderer**

Tender is in structed to complete the particulars required in this Form, *one form for each entity if Tender is a JV.* Tenderer is further reminded that it is an offence to give false information on this Form.

#### (a) Tenderer's details

	ITEM	DESCRIPTION
1	Name of the Procuring Entity	
2	Reference Number of the Tender	
3	Date and Time of Tender Opening	
4	Name of the Tenderer	
5	Full Address and Contact Details of the Tenderer.	<ol> <li>City</li> <li>Location</li> <li>Building</li> <li>Floor</li> </ol>
		<ul><li>6. Postal Address</li><li>7. Name and email of contact person.</li></ul>
6	Current Trade License Registration	
	Number and Expiring date	

<sup>\*</sup> In the case of the Tender submitted by joint venture specify the name of the Joint Venture as Tenderer.

<sup>\*\*</sup>Person signing the Tender shall have the power of attorney given by the Tenderer to be attached with the Tender.

7	Name, country and full address (postal and physical addresses,						
	and telephone number) of Regis	stering					
0	Body/Agency						
8	Description of Nature of Busines  Maximum value of business wh						
9	Tenderer handles.	iicii tile					
10	State if Tenders Company is list	ted in					
	stock exchange, give name and						
	address (postal and physical						
	addresses, email, and telephone	?					
	number) of						
	state which stock exchange						
(b) Nar Nat	Name in full Age  Nationality Country of Origin  Citizenship						
(0)	Partnership, provide the follow						
	Names of Partners	Nationality	Citizenship	% Shares owned			
1	Names of Partners	Nationality	Citizenship	% Shares owned			
1 2	Names of Partners	Nationality	Citizenship	% Shares owned			
+	Names of Partners	Nationality	Citizenship	% Shares owned			
2	Registered Company, provide  I) Private or public Compa  ii) State the nominal and iss  Nominal Kenya Shillings (Equivalent)  iii) Give details of Directors	the following d ny sued capital of thirding the control of t	etails.				
2 3 (d)	Registered Company, provide  I) Private or public Compa  ii) State the nominal and iss  Nominal Kenya Shillings (Equivalent)	the following d ny sued capital of thirding the control of t	etails.				
2 3 (d)	Registered Company, provide  I) Private or public Compa  ii) State the nominal and iss  Nominal Kenya Shillings (Equivalent)  iii) Give details of Directors	the following d ny sued capital of the ivalent)	etails.	Issued			
2 3 (d)	Registered Company, provide  I) Private or public Compa  ii) State the nominal and iss  Nominal Kenya Shillings (Equivalent)  iii) Give details of Directors	the following d ny sued capital of the ivalent)	etails.	Issued			

	Names of Person	Designation in the	Interest or Relationship with
		Procuring Entity	Tenderer
1			
2			
3			

# (iii) Conflict of interest disclosure

	Type of Conflict	Disclosure YES OR NO	If YES provide details of the relationship with Tenderer
1	Tenderer is directly or indirectly		
	controls, is controlled by or is under		
	common control with another		
	tenderer.		
2	Tenderer receives or has received any		
	direct or indirect subsidy from		
	another tenderer.		
3	Tenderer has the same legal		
	representative as another tenderer		
4	Tender has a relationship with		
	another tenderer, directly or through		
	common third parties, that puts it in a		
	position to influence the tender of		
	another tenderer, or influence the		
	decisions of the Procuring Entity		
	regarding this tendering process.		
5	Any of the Tenderer's affiliates		
	participated as a consultant in the		
	preparation of the design or technical		
	specifications of the works that are		
	the subject of the tender.		
6	Tenderer would be providing goods,		
	works, non-consulting services or		
	consulting services during		
	implementation of the contract		
	specified in this Tender Document.		
7	Tenderer has a close business or		
	family relationship with a		
	professional staff of the Procuring		
	Entity who are directly or indirectly		
	involved in the preparation of the	<b>D.</b> .	TAXIFC III III III III III III III III III
	Type of Conflict	Disclosure YES OR NO	If YES provide details of the relationship with Tenderer
	Tender document or specifications		
	of the Contract, and/or the Tender		
	evaluation process of such contract.		
8	Tenderer has a close business or		
	family relationship with a		
	professional staff of the Procuring		
	Entity who would be involved in		
	the implementation or supervision of		
	the such Contract.		

9 Has the conflict stemming from such relationship stated in item 7 and 8 above been resolved in a manner acceptable to the Procuring Entity throughout the tendering process and execution of the Contract.
Certification
On behalf of the Tenderer, I certify that the information given above is complete, current and accurate as at the date of submission.
Full Name
Titleor Designation
(Signature) (Date)
b) <u>CERTIFICATE OF INDEPENDENT TENDER DETERMINATION</u>
I, the undersigned, in submitting the accompanying Letter of Tender to the
Icertify, on behalf of[NameofTenderer]that:
1. I have read and I understand the contents of this Certificate;
2. I understand that the Tender will be disqualified if this Certificate is found not to be true and complete in every respect;
3. Iamthe authorized representative of the Tenderer with authority to sign this Certificate, and to submit the Tender on behalf of the Tenderer;
4. For the purposes of this Certificate and the Tender, I understand that the word "competitor" shall include any individual or organization, other than the Tenderer, whether or not affiliated with the Tenderer, who:

a) Has been requested to submit a Tender in response to this request for tenders;

- b) could potentially submit a tender in response to this request for tenders, based on their qualifications, abilities or experience;
- 5. The Tenderer discloses that [check one of the following, as applicable]:
  - a) The Tenderer has arrived at the Tender independently from, and without consultation, communication, agreement or arrangement with, any competitor;
  - b) the Tenderer has entered into consultations, communications, agreements or arrangements with one or more competitors regarding this request for tenders, and the Tenderer discloses, in the attached document(s), complete details thereof, including the names of the competitors and the nature of, and reasons for, such consultations, communications, agreements or arrangements;
- 6. Inparticular, without limiting the generality of paragraphs (5)(a) or(5)(b) above, there has been no consultation, communication, agreement or arrangement with any competitor regarding: a) prices;
  - b) methods, factors or formulas used to calculate prices;
  - c) the intention or decision to submit, or not to submit, a tender; or
  - d) the submission of a tender which does not meet the specifications of the request for Tenders; except as specifically disclosed pursuan tto paragraph (5)(b) above;
- 7. In addition, there has been no consultation, communication, agreement or arrangement with any competitor regarding the quality, quantity, specifications or delivery particulars of the works or services to which this request for tenders relates, except as specifically authorized by the procuring authority or as specifically disclosed pursuant toparagraph(5)(b) above;
- 8. The terms of the Tender have not been, and will not be, knowingly disclosed by the Tenderer, directly or indirectly, to any competitor, prior to the date and time of the official tender opening, or of the awarding of the Contract, whichevercomes first, unless otherwise required by aw or as specifically disclosed pursuant to paragraph (5)(b) above.

Name	
Title	
Date _	

[Name, title and signature of authorized agent of Tenderer and Date]

### (c) SELF- DECLARATION FORMS

#### FORM SD1

SELF DECLARATION THAT THE PERSON/TENDERER IS NOT DEBARRED IN THE MATTER OF THE PUBLIC PROCUREMENT AND ASSET DISPOSAL ACT 2015.

	, of Post Office Box being a resident
	in the Republic of do hereby make a statement as
follo	ws: -
	THAT I am the Company Secretary/ Chief Executive/Managing Director/Principal Officer/Direct or of
	for (insert tender title/description) for (insert name of
	the Procuring entity) and duly authorized and competent to make this statement.

<ol> <li>THAT the aforesaid Bidder, its Directors and subcontractors have not been debarred from participating procurement proceeding under Part IV of the Act.</li> <li>THAT what is deponded to here in above is true to the best of my knowledge, information and belief.</li> </ol>				
	(Title) (Signature) (Date)			
	Bidder Official Stamp			
	FORM SD2			
	ELF DECLARATION THAT THE PERSON/TENDERER WILL NOT ENGAGE IN ANY CORRUPT OR RAUDULENT PRACTICE.			
1.	THAT I am the Chief Executive/Managing Director/Principal Officer/Director of			
	THAT therafore said Bidder, its servants and/oragents/subcontractorswillnotengageinanycorruptorfraudulent practice and has not been requested to pay any inducement to any member of the Board, Management, Staff and/or employees and/or agents of			
4.	THAT the aforesaid Bidder will not engage /has not engaged in any corrosive practice with other bidders participating in the subject tender			
5.	THAT what is deponed to here in above is true to the best of my knowledge information and belief.			
	(Title) (Signature) (Date)			
	Bidder's Official Stamp			
D	ECLARATION AND COMMITMENT TO THE CODE OF ETHICS			
Ι.	(person) on behalf of (Name of the Business/ Company/Firm)			
 Pu	declare that I have read and fully understood the contents of the ablic Procurement & Asset Disposal Act, 2015, Regulations and the Code of Ethics for persons participating in ablic Procurementand Asset Disposal and my responsibilities under the Code.			

Date.....

I do here by commit to abide by the provisions of the Code of Ethics for persons participating in Public Procurement

#### (d) APPENDIX 1 - FRAUD AND CORRUPTION

(Appendix 1 shall not be modified)

### 1. Purpose

and Asset Disposal.

1.1 The Government of Kenya's Anti-Corruption and Economic Crime laws and their sanction's policies and procedures, Public Procurement and Asset Disposal Act (no. 33 of 2015) and its Regulation, and any other Kenya's Acts or Regulations related to Fraud and Corruption, and similar offences, shall apply with respect to Public Procurement Processes and Contracts that are governed by the laws of Kenya.

#### 2. Requirements

- 2.1 The Government of Kenya requires that all parties including Procuring Entities, Tenderers, (applicants/proposers), Consultants, Contractors and Suppliers; any Sub-contractors, Sub-consultants, Service providers or Suppliers; any Agents (whether declared or not); and any of their Personnel, involved and engaged in procurement under Kenya's Laws and Regulation, observe the highest standard of ethics during the procurement process, selection and contract execution of all contracts, and refrain from Fraud and Corruption and fully comply with Kenya's laws and Regulations as per paragraphs 1.1 above.
- 2.2 Kenya's public procurement and asset disposal act (no. 33 of 2015) under Section 66 describes rules to be followed and actions to be taken in dealing with Corrupt, Coercive, Obstructive, Collusive or Fraudulent practices, and Conflicts of Interest in procurement including consequences for offences committed. A few of the provisions noted below highlight Kenya's policy of no tolerance for such practices and behavior:
  - 1) A person to whom this Act applies shall not be involved in any corrupt, coercive, obstructive, collusive or fraudulent practice; or conflicts of interest in any procurement or as set disposal proceeding;

- 2) A person referred to under subsection (1) who contravenes the provisions of that sub-section commits an offence;
- 3) Without limiting the generality of the subsection (1) and (2), the person shall be:
  - a) disqualified from entering into a contract for a procurement or asset disposal proceeding; or
  - b) if a contract has already been entered into with the person, the contract shall be voidable;
- 4) The voiding of a contract by the procuring entity under subsection (7) does not limit any legal remedy the procuring entity may have;
- 5) An employee or agent of the procuring entity or a member of the Board or committee of the procuring entity whohas a conflict of interest with respect to a procurement:
  - a) Shall not take part in the procurement proceedings;
  - b) shall not, after a procurement contract has been entered in to, take part in any decision relating to the procurement or contract; and
  - c) shall not be a subcontract or for the tender to whom was awarded contract, or a member of the group of tenderers to whom the contract was awarded, but the subcontractor appointed shall meet all the requirements of this Act.
- 6) An employee, agent or member described in subsection (1) who refrains from doing anything prohibited under that subsection, but for that subsection, would have been within his or her duties shall disclose the conflictofinteresttotheprocuringentity;
- 7) If a person contravenes subsection (1) with respect to a conflict of interest described in subsection (5)(a) and the contract is awarded to the person or his relative or to another person in whom one of them had a direct or indirect pecuniary interest, the contract shall be terminated and all costs incurred by the public entity shall be made good by the awarding officer. Etc.
- 3. In compliance with Kenya's laws, regulations and policies mentioned above, the Procuring Entity:
  - a) Defines broadly, for the purposes of the above provisions, the terms setf orth below as follows:
    - i) "corrupt practice" is the offering, giving, receiving, or soliciting, directly or indirectly, of anything of value to influence improperly the actions of another party;
    - ii) "fraudulent practice" is any act or omission, including is representation, that knowingly or recklessly misleads, or attempts to mislead, a party to obtain financial or other benefit or to avoid an obligation;
    - iii) "collusive practice" is an arrangement between two or more parties designed to achieve an improper purpose, including to influence improperly the actions of another party; "coercive practice" is impairing or harming, or threatening to impair or harm, directly or indirectly, any party or the property of the party to influence improperly the actions of a party;
    - iv) "obstructive practice" is:
      - Deliberately destroying, falsifying, altering, or concealing of evidence material to the investigation or making false statements to investigators in order to materially impede investigation by Public Procurement Regulatory Authority (PPRA) or any other appropriate authority appointed by Government of Kenya into allegations of a corrupt, fraudulent, coercive, or collusive practice; and/or threatening, harassing, or intimidating any party to prevent it from disclosing its knowledge of matters relevant to the investigation or from pursuing the investigation; or
      - acts intended to materially impede the exercise of the PPRA's or the appointed authority's inspection and audit rights provided for under paragraph 2.3 e. below.

- b) Defines more specifically, in accordance with the above procurement Act provisions set forth for fraudulent and collusive practices as follows:
  - "fraudulent practice" includes a misrepresentation of fact in order to influence a procurement or disposal processorthe exercise of a contract to the detriment of the procuring entity or the tenderer or the contractor, and includes collusive practices amongst tenderers prior to or after tender submission designed to establish tender prices at artificial non-competitive levels and to deprive the procuring entity of the benefits of free and open competition.
- c) Rejects a proposal for award<sup>5</sup> of a contract if PPRA determines that the firm or individual recommended for award, any of its personnel, or its agents, or its sub-consultants, sub-contractors, service providers, suppliers and/ or their employees, has, directly or indirectly, engaged in corrupt, fraudulent, collusive, coercive, or obstructive practices in competing for the contract in question;
- d) Pursuant to the Kenya's above stated Acts and Regulations, may recommend to appropriate authority(ies) for sanctioning and debarment of a firm or individual, as applicable under the Acts and Regulations;
- e) Requires that a clause be included in Tender documents and Request for Proposal documents requiring(i) Tenderers (applicants/proposers), Consultants, Contractors, and Suppliers, and their Sub-contractors, Subconsultants, Service providers, Suppliers, Agents personnel, permit the PPRA or any other appropriate authority appointed by Government of Kenya to inspect<sup>6</sup> all accounts, records and other documents relating to the procurement process, selection and/or contract execution, and to have them audited by auditors appointed by the PPRA or any other appropriate authority appointed by Government of Kenya; and
- f) Pursuant to Section 62 of the above Act, requires Applicants/Tenderers to submit along with their Applications/Tenders/Proposals a "Self-Declaration Form" as included in the procurement document declaring that they and all parties involved in the procurement process and contract execution have not engaged/will not engage in any corrupt or fraudulent practices.

## FORM OF TENDER SECURITY-[Option 1-Demand Bank Guarantee]

	neficiary:quest forTenders No:	
_ Da	te:	-
	ENDER GUARANTEE No.:	
Gı	arantor:	_
1.	We have been informed that(here inafter called "the Applicant Beneficiary its Tender (here inafter called" the Tender") for the executio("the ITT").	
2.	Furthermore, we understand that, according to the Beneficiary's condition	ons, Tenders must be supported by a

Tender guarantee.

<sup>&</sup>lt;sup>5</sup> For the avoidance of doubt, a party's in eligibility to be awarded a contract shall includee, without limitation, (i) applying for pre-qualification, expressing interest in a consultancy, and tendering, either directly or as a nominated sub-contractor, nominated consultant, nominated manufacturer or supplier, or nominated service provider, in respect of such contract, and (ii) entering into an addendum or amendment introducing a material modification to any existing contract.

<sup>&</sup>lt;sup>6</sup> Inspections in this context usually are investigative (i.e., forensic) in nature. They involve fact-finding activities undertaken by the Investigating Authority or persons appointed by the Procuring Entity to address specific matters related to investigations/audits, suc has evaluating the veracity of an allegation of possible Fraud and Corruption, through the appropriate mechanisms. Such activity includes but is not limited to: accessing and examining a firm's or individual's financial records and information, and making copies thereof as relevant; accessing and examining any other documents, data and information (whether in hard copyor electronic format) deemed relevant for th einvestigation/audit, and making copies there of as relevant; interviewing staff and other relevant individuals; performing physical inspections and site visits; and obtaining third party verification of information.

3.	At the request of the Applicant, we, as Guarantor, hereby irrevocably undertake to pay the Beneficiary any sum or sums not exceeding in total an amount of() upon receipt by us of the Beneficiary's complying demand, supported by the Beneficiary's statement, whether in the demand itself or a separate signed document accompanying or identifying the demand, stating that either the Applicant:
(a)	has withdrawn its Tender during the period of Tender validity set forth in the Applicant's Letter of Tender ("the Tender Validity Period"), or any extension thereto provided by the Applicant; or
b)	having been notified of the acceptance of its Tender by the Beneficiary during the Tender Validity Period or any extension there to provided by the Applicant, (i) has failed to execute the contract agreement, or (ii) has failed to furnish the Performance.
4.	This guarantee will expire: (a) if the Applicant is the successful Tenderer, upon our receipt of copies of the contract agreement signed by the Applicant and the Performance Security and, or (b) if the Applicant is not the successful Tenderer, upon the earlier of (i) our receipt of a copy of the Beneficiary's notification to the Applicant of the results of the Tendering process; or (ii) thirty days after the end of the Tender Validity Period.
5.	Consequently, any demand for payment under this guarantee must be received by us at the office indicated above onor before that date.
	[signature(s)]
	Note: All italicized text is for use in preparing this form and shall be deleted from the final product.
FOR	MAT OF TENDER SECURITY [Option 2–Insurance Guarantee]
TEN	DER GUARANTEE No.:
1.	Whereas [Name of the tenderer] (hereinafter called "the tenderer") has submitted its tender dated
2.	"the Tender") for the execution of under Request for Tenders No. ("the ITT").
	KNOW ALL PEOPLE by these presents that WE
	KNOW ALL PEOPLE by these presents that WE
3.	KNOW ALL PEOPLE by these presents that WE

Tender ("the Tender Validity Period"), or any extension thereto provided by the Principal; or

b) having been notified of the acceptance of its Tender by the Procuring Entity during the Tender Validity Period or any extension thereto provided by the Principal; (i) failed to execute the Contract agreement; or (ii) has failed to furnish the Performance Security, in accordance with the Instructions to tenderers ("ITT") of the Procuring Entity's Tendering document.

then the guarantee undertakes to immediately pay to the Procuring Entity up to the above amount upon receipt of the Procuring Entity's first written demand, without the Procuring Entity having to substantiate its demand, provided that in its demand the Procuring Entity shall state that the demand arises from the occurrence of any of the above events, specifying which event(s) has occurred.

- 4. This guarantee will expire: (a) if the Applicant is the successful Tenderer, upon our receipt of copies of the contract agreement signed by the Applicant and the Performance Security and, or (b) if the Applicant is not the successful Tenderer, upon the earlier of (i) our receipt of a copy of the Beneficiary's notification to the Applicant of the results of the Tendering process; or (ii)twenty-eight days after the end of the Tender Validity Period.
- 5. Consequently, any demand for payment under this guarantee must be received by us at the office indicated above on or before that date.


[Date]	[Signature of the Guarantor]
[Witness]	[Seal]

Note: All italicized text is for use in preparing this form and shall be deleted from the final product.

#### FORM OF TENDER - SECURING DECLARATION

- 1. I/We understand that, according to your conditions, bids must be supported by a Tender-Securing Declaration.
- 2. I/We accept that I/we will automatically be suspended from being eligible for tendering in any contract with the Purchaser for the period of time of [insert number of months or years] starting on [insert date], if we are in breach of ourobligation(s) under the bid conditions, because we—(a) have withdrawn our tender during the period of tender validity specified by us in the Tendering Data Sheet; or (b) having been notified of the acceptance of our Bid by the Purchaser during the period of bid validity, (i) fail or refuse to execute the Contract, if required, or (ii) fail or refuse to furnish the Performance Security, in accordance with the instructions to tenders.
- 3. I/We understand that this Tender Securing Declaration shall expire if we are not the successful Tenderer(s), upon the earlier of:
  - a) Our receipt of a copy of your notification of the name of the successful Tenderer; or
  - b) thirty days after the expiration of our Tender.
- 4. I/We understand that if Iam /we are/ in a Joint Venture, the Tender Securing Declaration must be in the name of the Joint Venture that submits the bid, and the Joint Venture has not been legally constituted at the time of bidding, the Tender Securing Declaration shall be in the names of all future partners as named in the letter of intent.

Signed:		ner or
sole proprietor, etc.)		
Name:		sign the bid
for and on behalf of: [insert complete name of Tend	lerer]	
Dated on day of,	[Insert date of signing] Seal orstamp	
Appendix to Tender		
<b>Schedule of Currency requirements</b>		
Summary of currencies of the Tender for	[insert name of Section of	the Works]
Name of currency	Amounts payable	
Local currency:		
Foreign currency #1:		
Foreign currency #2:		
Foreign currency #3:		
Provisional sums expressed in local currency	[To be entered by the Procuring Entity]	



#### **SECTION V - BILLS OF QUANTITIES**

### A. Notes and Sample Items for Preparing a Bill of Quantities

- 1. These Notes for Preparing a Bill of Quantities are intended only as information for the Procuring Entity or the person drafting the Tender Documents. Priced Bills of Quantities shall be part and parcel of the Contract Documents.
- 2. The objectives and purpose of the Bills of Quantities are to provide sufficient information on the specifications, descriptions and quantities of Works to be performed to enable tenders to be prepared efficiently and accurately and when a contract has been entered into, to provide a priced Bill of Quantities for use in the periodic valuation of Works executed. Inorder to attain these objectives, Works should be itemized in the Bill of Quantities insufficient detail to distinguish between the different classes of Works, or between Works of the same nature carried outin different locations or in other circumstances which may give rise to different considerations of cost. Consistent with these requirements, the layout and content of the Bill of Quantities should be as simple and clear as possible.
- 3. The Bills of Quantities should be divided generally into the following sections: a) Preambles
  - b) Preliminary items
  - c) Work Items
  - c) Daywork Schedule; and
  - d) Provisionalitems
  - e) Summary.

#### 4. NOTES TO PREPARING PREAMBLES

- 4.1 The Preambles should include only those items that constitute the cost of the works but would not be priced separately as they are expected to be included in the unit prices. Care should be taken to ensure that these items are not are petition of the conditions of contract. The Preambles should indicate the inclusiveness of the unit prices and should state the methods of measurement that have been adopted in the preparation of the Bill of Quantities, that are to be used for the measurement of any part of the Works. The units of measurement and abbreviations should be defined and any mandatory national units defined and described. The methods of and procedure for re- measurement should be described in the Preambles.
- 4.2 Units of Measurement The following units of measurement and abbreviations shall be used, unless other national units are mandatory in Kenya.

Unit	Abbreviation	Unit	Abbreviation
cubic meter hectare hour kilogram lump sum meter metric ton	m³ or cu m ha h kg ls m t	millimetre month number square meter square millimeter week	mm mon nr m² or sq m mm² or sq mm wk

- 4.3 The Bills of Quantities shall be read in conjunction with the Instructions to Tenders, General and Special Conditions of Contract, Technical Specifications, and Drawings.
- 4.4 The quantities given in the Bills of Quantities are estimated and partly provisional and are given to provide a common basis for tendering. The basis of payment will be the actual quantities of work ordered and carried

out, as measured by the Contractor and verified by the Architect and valued at the rates and prices tender in the priced

Bills of Quantities, where applicable, and otherwise at such rates and prices as the Architect may fix within the terms of the Contract.

- 4.5 The rates and prices tender in the priced Bills of Quantities shall, except in so far as it is otherwise provided under the Contract, include all Constructional Plant, labour, supervision, materials, erection, maintenance, insurance, profit, taxes, and duties, together with all general risks, liabilities, and obligations set out or implied in the Contract.
- 4.6 Arateorprice shall be entered against each item in the priced Bill of Quantities, whether quantities are stated or not. The cost of Items against which the Contractor has failed to enter a rate or price shall be deemed to be covered by other rates and prices entered in the Bill of Quantities.
- 4.7 The whole cost of complying with the provisions of the Contract shall be included in the Items provided in the priced Bills of Quantities, and where no Items are provided, the cost shall be deemed to be distributed among the ratesand prices entered for the related Items of Work.
- 4.8 General directions and descriptions of work and materials are not necessarily repeated nor summarized in the Bills of Quantities. References to the relevant sections of the Contract documents shall be made before entering prices against each item in the priced Bills of Quantities.
- 4.9 Provisional Sums and contingency sums included and so designated in the Bills of Quantities shall be expended in whole or in part at the direction and discretion of the Architect in accordance with Sub-Clause 13.5 and Clause 13.6 of the General Conditions of contract.
- 4.10 In preparing the Bills of Quantities, notes should be removed as they are intended to guide the person preparing the Tender Documents. The Contractor must allow in his rates for any costs associated with and complying with the requirements in the Preambles.
- 4.11 Should a tenderer/contractor not price any item in any section of the Bills of Quantities including Preliminary items, it will be assumed that he/she has spread its cost in other areas that he/she will have priced. Therefore, the itemor items will be executed without any additional costs or without being treated like variations.

### 5. NOTES ON PREPARING BILLS OF QUANTITIES

- 5.1 The <u>Preliminary Items</u> should be limited to tangible items that should be priced by the tenderer, are identifiable and can be priced separately and included in the interim valuations precisely. Such items may include such items as site office, notice boards, and other temporary works, otherwise items such as security for the Works which are primarily part of the Contractor's obligations should be included in the Contractor's rates.
- 5.2 The work items in the Bills of Quantities should be grouped into sections to distinguish between those parts of the Works which by nature, location, access, timing, or any other special characteristics may give rise to different methods of construction, or phasing of the Works, or considerations of cost. Such groups could be ground excavations, structures, external works, services, etc. General items common to all parts of the Works may be grouped as a separate section in the Bill of Quantities.
- 5.3 Quantities should be computed net from the Drawings, unless directed otherwise in the Contract, and no allowance should be made for bulking, shrinkage or waste. Quantities should be rounded upwhere appropriate.
- 5.4 Where the measured items a redeemed not to be exact because of the likelihood that the scope can change during the execution of the works, such items could be subject to re-measurement, the word "provisional" should be used to identify such cases. Where whole sections of the work items fall in this class, for example foundations, they should be labelled "Provisional Quantities" or "Provisional Items" so that the Tenderer/Contractor is advised up front that such items are subject to re-measurement to done before such work is cover-up.
- 5.5 All items that have not been measured and therefore not subject tot enders pricing should be listed in the Bills of Quantities as **Provisional Sums** for particular item or class of Work, which may be subject to a nominated subcontract or separate measurements at a later date during the execution of the works. For example, if it is deemed not possible to measure electrical works before going to tender because detail designs are not ready, a

provisional sum can be allowed in the Bills of Quantities for "Installation of Electrical Works" to be executed later when actual design details are completed. To the extent not covered above, there should be in the Bills of Quantities a general provision for physical and financial contingencies made as a "Provisional Sum for Contingencies" and "Provisional Sum for Fluctuations". The inclusion of such provisional sums often facilitates budgetary approval by avoiding the need to request periodic supplementary approvals as the future need arises.

- 5.6 Provisional sums to cover specialized works normally carried out by Nominated Sub Contractors should be avoided and instead Bills of Quantities of the specialized Works should be included as a section of the main Bills of Quantities to be priced by the Main Contractor. The Main Contractor should be required to indicate the name(s) of the specialized firms he proposes to engage to carry out the specialized Works as his approved domestic sub-contractors. Only provisional sums to cover specialized Works by statutory authorities should be included in the Bills of Quantities.
- 5.7 A Daywork Schedule should be included if the probability of unforeseen work, outside the items included in the Bill of Quantities, is relatively high. To facilitate checking by the Procuring Entity of the realism of rates quoted by the tenderers, the Daywork Schedule should normally comprise:
  - i) A list of the various classes of labor, and materials for which basic.
  - ii) Daywork rates and prices for various categories of labor are to be inserted by the tenderer, together with a statement of the conditions under which the Contractor will be paid for Work executed on a Daywork basis.
  - iii) A percent a get o be entered by the tenderer agains teach basic Day work item.
  - iv) Subtotal amount for labor, materials and plant representing the Contractor's profit, overheads, supervision and other charges.
- 5.8 The Summary should contain a tabulation of the separate parts of the Bills of Quantities carried forward, with provisional sums for Daywork, Provisional sums and Contingencies, and provision for Total Costing. The last line should allow for tenderer to indicate any discounts before arriving at a total cost carried forward to the Form of Tender.

## **BILLS OF QUANTITIES**

#### (a) <u>Preambles</u>

1. The method of measurement of completed work for payment shall be in accordance with [insert the name of a standard reference guide, or full details of the methods to be used].

2.	The Site is situated in (provide full description where the site is situated, coordinates from the nearest known		
	landmark like a town and its size)	It is approximately	Kilometers from
	Nairobi. Access to the site shall be through		,

Which is an existing public road. Any damage caused to the surfaces of this road shall be made good at the Contractor's expense. The Contractor shall visit the site and acquaint itself with its nature and position, the nature of the ground, substrata and other local conditions, positions of existing power, water and other services, access roads or any other limitations that might affect his cost or progress. No claim for extras shall be considered on account of lack of knowledge in this respect.

- 3. The Contractor shall obtain the Architect's approval on the siting of all temporary buildings, spoil heaps, temporary access path, and storage of materials. The Contractor shall also obtain the Architect approval and direction regarding the use of any materials found on the Site.
- 4. The drawings used in the preparation of these Bills of Quantities can be inspected at the offices of the Procuring Entityor Procuring Entity's Representative during normal working hours. Two sets of the Working Drawings shall be provided to the contractor but additional copies shall be provided at a cost to be determined by the Engineer.
- 5. The Contractor shall allow for the payment of all bank charges in connection with the procurement of Bank Guarantees and stamp charges in connection with this contract Agreement.
- 6. The Contractor shall carry out the various sections of the Works in such an order as the Architect May direct. The Procuring Entity reserves the right to occupy the Works by sections on completion provided that such occupation is considered to be both practical and reasonable and will not interfere with the Works. The Contractor shall allow any costs associated with such occupation.
- 7. The main Contractor will be fully responsible for paying his Sub-Contractor but the Procuring Entity reserves the right in very exceptional circumstances to make such payments direct in the interests of the project where the completion thereof might be jeopardized by any dispute or vicariousness between the Contractor and the Sub-Contractor involve.
- 8. The Contractor shall complete and deliver the Works in the period inserted in the Form of Tender as his time for completion of the Works from the date for Possession, to be agreed with the Engineer. The Contract Period is presumed to have been calculated making due allowance for seasonal inclement weather conditions. Noclaimfor extension of time due to the normal in clement weather for this area shall be entertained.
- 9. The Contractor shall, upon receiving instructions to proceed with the Works, draw up a Programme and Progress Chart setting out the order in which the Works are to be carried out, with the appropriate dates there of. This Chart shall be agreed with the Architect and no deviation from the order set out in it will be permitted without the written consent of the Engineer. The Contractor will be responsible for arranging the above programme with all his sub-Contractors and Specialties. The Contractor shall allow in his rates for carrying out this exercise, and for updating it as required.
- 10. The Contractor shall submit to the Architect on the first day of each week or such longer period as the Architect from time to time direct, a Progress Report and any information for the proceeding period, showing the progress during the period and the up-to-date cumulative progresson all important items of each section or portion of the Works.
- 11. The Contractor shall arrange for photographs of the Site to be taken by a professional photographer approved by the Engineer. The Photographs shall provide a record of the Site and adjacent are as prior to the commencement of the Works and shall cover such portion of the works in progress and completion as the Architect shall direct. All prints shall be full plate size, unmounted, and marked on the reverse side with the date of exposure, identification reference and brief description. The copyright of all photographs shall be vested in

- the Procuring Entity. The negatives and four prints from each negative shall be delivered to the Architect within two weeks of exposure.
- 12. Figured dimensions are to be followed in preference to dimensions scaled from the Drawings, but whenever possible dimensions are to be taken on the Site or from the buildings. Before any work is commenced by Sub-Contractors or Specialist Firms, dimensions must be checked on the site comparable dimensions shown on the drawings. The Contractor shall be responsible for the accuracy of such dimensions.
- 13. Prior to commencement of any work the Contractor is to ascertain from the relevant Authorities the exact position, depth and level of all existing electric cables, waterpipes or other services in the are and he shall make whatever provisions may be required by the Authorities concerned for the support and protection of such services. Any damage or disturbance caused to any services shall be reported immediately to the Architect and the relevant Authority and shall be made good to their satisfaction at the Contractor's expense. Where appropriate the Contractor shall open up the ground in advance of the main work by hand digging if necessary, to locate precisely the position and details of the services which are likely to affect his operations.
- 14. The Contractor shall include in his prices for the transport of materials, workmen, etc./, to and from the site of the proposed works, at such hours and by such route as are permitted by the Authorities.
- 15. The Contractor will be required to make good, at his own expense and damage he may cause to the present road surface and pavements within or beyond the boundary of the Site, during the period of the works. All existing paths, storm water channels, etc., that may be destroyed or damaged during the progress of the Works shall be reinstated by the Contractor to the satisfaction of the Engineer.
- 16. The Contractor is to allow for complying with all instructions and regulations of the Police Authorities.
- 17. All water shall be fresh, clean and pure, free from earthly, vegetable or organic matter, acid or alkaline substance in solution. The Contractor shall provide at his own risk and cost all water for use in connection with the Works, (including works of sub—contractors). If need be, he shall make arrangements with the Local Water Authority for the installation of a separate meter for all water used by him throughout the Contract and pay all cost and fees in connection therewith. He shall also provide temporary storage tanks and tubing, etc., as may be necessary, and clear away at completion. 18. The Contractor shall provide all artificial lighting and power for his own use on the Works, (including Sub Contractor's) including all temporary connections, wiring, fittings, etc., and clearing away on completion. The Contractor shall pay all fees and obtain all permits in connection there with.
- 19. The Contractor shall constantly keep on the Works a Literate English-speaking Agent or Representative, competent and experienced in the kind of work involved, who shall given is whole time to the superintendence of the works. (Including works of sub contractors). Such Agent or Representative shall receive on behalf of the Contractordirections and instruction from the Engineer, and such directions and instructions shall be deemed to be given to the contractor in accordance with the Conditions of Contract. The Agent shall not be replaced without the specific approval of the Engineer.
- 20. The Contractor shall ensure that the safety of his work people and all authorized visitors to the site are protected at all times. In particular, there shall be the proper provision of guard—rails to scaffolding, protection against falling materials, tools on site, dust, nail and other sharp objects. The site shall be kept tidy and clear of dangerous rubbish. The Architect shall be empowered to suspend work on site should it be considered this condition is not being observed and no claim arising from such suspension will be allowed.
- 21. The are as available to the Contractor for workyards, offices and other facilities shall be directed by the Architect and any existing features to remain shall be protected from damage throughout the Contract Period and handed back in good condition when they are vacated at the end of the Contract. If additional areas are required, the contractorshallsourcethenatowncost.
- 22. The Contractor shall give the Architect reasonable notice of the intention to set out or take levels for any part of the Works so that arrangements may be made for checking the work. The accuracy of setting out and leveling shall be within the tolerances specified in the Specifications or on the Drawings. The checking of setting out or leveling by the Architect shall not relieve the Contractor of his duties or responsibilities under the Contract.
- 23. The Contractor must take steps necessary to safe guard and shall beheld fully responsible for any damage caused to existing and adjacent property, including buildings that are not a subject of demolition. He shall make good at

- his own cost damage to persons and property caused there on, and he shall indemnify the Procuring Entity against any loss or claim that may arise.
- 24. The Contractor shall take such steps and exercise such care and diligence as to minimize nuisance arising from dust, noise or any other cause to the occupiers of the existing and adjacent property. He must provide such temporary and special screens and tarpaulins or gummy bags, hoarding, barriers, warning signs etc. as he considers necessary and sufficient for the protection of the existing and adjacent property and or prevention of nuisance etc. as directed by Engineer.
- 25. The Contractors attention is drawn to the standards levy order which was amended on 15<sup>th</sup>October 1998.Legal notice No.154 of 1998. The Contractor is required to pay a monthly level of 0.2% of his factory price of construction works with effect from January 1999. Tenderer shall allow for this in the build-upo f his rates.
- 26. The Contractor shall provide temporary sheds, offices meshrooms, sanitary, accommodation and other temporary buildings for the use of the contractor and sub-contractors, including lighting furniture equipment and attendance.
- 27. Contractor shall provide/build labor camp sat areas to be agreed with the Engineer. Labor camps shall be complete with sanitary accommodation and fencing gates.
- 28. The Contractor must provide the necessary toilet facilities to the requirement and satisfaction of the Health Authorities and maintain the same in a thoroughly clean and sanitary condition and pay all conservancy fees during the period of the Works and remove when no longer required.
- 29. The Contractor shall provide at his own risk and cost all watching and lighting as necessary to safeguard the Works, Plant and materials against damage and theft.
- 30. The Contractor shall provide all necessary hoists, tackle, plant, equipment, vehicles, tools and appliances of every description for the due and satisfactory completion of the Works and shall remove the same on completion. All such plant, tools and equipment shall comply with all regulations in force throughout the period of the Contract and shall be altered or adopted during the Contract period as may be necessary to comply with any amendments in or additions to such regulations.
- 31. Provide, erect and maintain all necessary scaffolding, sufficiently strong and efficient for the due performance of the works, including Sub-Contract Works, provide special scaffolding as required by Sub-Contractors, alter and adopt all scaffolding as and when required during the Works, and remove on completion. No scaffolding is measured here in after and the Contractor must allow in his rates for this.
- 32. The Contractor shall take all necessary precautions such as temporaryf encing, hoarding fans, planked footways, guard–rails gantries screen, etc., for the safe custody of the Works, materials and public protection and adjacent properties.
- 33. Cover up all and protect from damage, including damage from in clement weather, all finished work and unfixed materials, including that of Sub-Contractors, etc., to the satisfaction of the Architect until the completion of the Contract.
- 34. The Contractor shall, after completion of the works, at his own expense, remove and clear away all surplus excavated demolition materials, plant, rubbish and unused materials and shall leave the whole of the Site and Works in a clean and tidy state to the satisfaction of the Engineer, sheds, camps, etc. Particular care shall be taken toleavecleanallfloors and windows and tore move all paint and cement all rubbis hand dirt as it accumulates. The Contractor is to find his own dump and shall pay all charges in connection there with.
- 35. Concrete test cubes shall be prepared in a set of three, as described including testing fees, labor and materials, making molds, transport, handling, etc. Allow in your rates for making at least four cubes on each occasion, from different batches; the concrete being taken from the point of deposit.
- 36. The Contractors hall furnish at the earliest possible opportunity before work commences, and at his own cost, any samples of materials and workmanship that may be called for by the Architect for the approval or rejection, and any further samples in the case of rejection, until such samples are approved by the Engineer. Such samples, when approved, shall be the minimum standard for the work to which they apply. The procedure or submitting

- samples of materials for testing or approval and the method of marking for identification shall be as laid down by the Engineer. The Contractor shall allow in his Tender for such samples and tests, including those in connection with his Sub-Contractors work.
- 37. The Contractors attention is drawn to the Finance Bill of the year 2000/2001 on withholding tax on contractual payment section 35(7)(i)(ii) which became effective on 1st July 2000. A 3% withholding tax will be applicable
  - to all in terim payments exceeding Kshs...... for work done in respect of building or civil works. The contractor shall allow for any costs arising resulting there from in the build-up of rates.
- 38. Blasting will only be allowed with the express permission of the Architect in writing. All blasting operations shall be carried out at the Contractor's sole risk and cost, in accordance with any Government regulations in force for the time being, and any special regulations laid down by the Architect governing the use and storage of explosives.
- 39. The National Construction Authority is a state corporation established under the national construction authority Act No.14 of 2011. The broad Mandate of the Authority is to over see the construction industry and coordinate its development. The National Construction Authority Regulations 2014 with an effective date of 6<sup>th</sup>June 2014, regulation 25, Allow 0.5% of the tender sum/contract sum for construction levy.
- 40. The Contractor attention is drawn to Finance Bill of 1993 where VAT was introduced in all contracts for construction services. The tenderer is also drawn to VAT Act Cap 476 clause 19(9). The tenderer must allow for VAT 1.19 as instructed else where.
- 41. The contractor shall allow and pay for all insurance to cover risks and indemnities required Items 17 and 18 of the Conditions of contract and also specified in the Special Conditions of Contract.

# **BILL NO. 1 - PRELIMINARY ITEMS**

	DESCRIPTION	AMOUNT
ITEM		
No.		
1.	The Contractor shall provide, or erect and maintain an approved lock-up office for the sole use of the Architect and his own site staff. The office, which will have a total floor area of not less thansquare metres, will be divided into two separate interconnected offices. Services to be provided shall include a telephone, water sanitary and electrical supply and drainage. The offices shall be supplied with furniture and equipment that shall include:  4 No. desks with chairs; 1 No. large table with sufficient number of chairs; drawing table along the full length of one side with plan drawers and drawing stools: 4 No. waste paper baskets: sufficient number of pin boards: and any additional furniture and fittings as may reasonably be required during the Contract period. The Contractor shall provide the Architect and site staff with computer sets or laptops, printers and telephones all that are necessary for project use.  The office furniture and equipment shall all be to the approval of the Engineer. The Contractor shall also provide all labor, equipment and consumable stores equipment throughout the currency of the contract.	
2	[OPTIONAL] Contractor shall provide a house for Engineers site agent, which shall be one bedroomed temporary house with a sitting room, toilet, bathroom and a kitchen complete with electrical and sanitary installations and provide maintenance and paying of bills of water and electricity up to and including end of the contract period.	
3	Provide a signboard not less than square meters in size of a design type, and with lettering and coloring and in a position approved by the Engineer. The signboard shall be for the display of the Main Contractor's name and the names of all his Sub-Contractors, with the Procuring Entity's name painted thereon. All Consultants names be printed in letters not exceeding 50 mm high. No other signboard or advertising shall be allowed. The signboard shall be fully maintained during the Contract Period and shall be pulled down and removed at the end of the contract.	
4	Add others (if any)	
5		
6		
	TOTAL CARRIED TO GRAND SUMMARY	

# **BILL NO. 2: WORK ITEMS**

(organized appropriately into work sections, such as foundations, walls/structure, finishes, doors and windows, mechanical installations. etc.

Bill No 2 - (Name of Section e.g. Foundations).

Item no.	Description	Unit	Quantity	Rate	Amount

Total for Bill No. 2 (carried forward to Summary, p. )					

Bill No. 3: Schedule of Daywork Rates Labor

Item no.	Description	Unit	Nominal quantity	Rate	Amount
	Subtotal  Allow percentage of Subtotal for Contractor's overhead, profit, etc., in accordance with paragraph 3 (b) above.				
	Total for Daywork (carried forward to Daywork Summary, p)				

a. To be entered by the Tenderer.

**Bill No. 4: Schedule of Daywork Rates Materials** 

Item no.	Description	Unit	Nominal quantity	Rate	Extended amount

Subtotal

Allow \_ percent a. of Subtotal for Contractor's overhead, profit, etc., in accordance with paragraph 4 (b) above.

Total for Daywork: Materials (carried forward to Daywork Summary, p.

a. To be entered by the Tenderer.

Bill No. 5: Schedule of Daywork Rates Contractor's Equipment

Item no.	Description	Nominal quantity (hours)	Basic hourly rental rate	Extended amount
	Allow _ percent a of Subtotal for			
	Contractor's overhead, profit, etc., in			
	accordance with paragraph 5 above.			
Total for l	Daywork: Contractor's Equipment (carried for	orward to Daywork S	ummary, p )	

a. To be entered by the Tenderer.

# Bill No. 6: Daywork Summary

	Amount <sup>a</sup>	%	Currency
		Foreign	
1. Total for Daywork: Labor			
2. Total for Daywork: Materials			
3. Total for Daywork: Contractor's Equipment			
Total for Daywork (Provisional Sum) (carried forward to			
Summary of Bills of Quantities, p)			

# **Bill No. 7: Provisional Sums**

Bill no.	Item no.	Description	Amount
1			
2			
3			
4			
etc.			
Total for Specified Provisional Sums (carried forward to Grand Summary			

# **GRAND SUMMARY**

SUMMARY ITEMS	Page	Amount
Bill No. 1: Preliminary Items		
Bill No. 2: Work Items		
Bill No 3: Daywork Summary		

Bill No 4: Provisional Sums

Subtotal of Bills No 1-4

Allow for any Discounts i

TOTAL TENDER PRICE Carried forward to Form of Tender

(i) If a percentage used, it should be indicated on which Bill No. items but on Bill No.4 – Provisional Sums.

#### **SECTION VI - SPECIFICATIONS**

Notes for preparing Specifications

- 1. Specifications must be drafted to present a clear and precise statement of the required standards of materials, and workmanshipfor tenderers to respond realistically and competitively to the requirements of the Procuring Entity and ensure responsiveness of tenders. The Specifications should require that all materials, plant, and other supplies to be permanently incorporated in the Works be new, unused, of the most recent or current models, and incorporating all recent improvements in design and materials unless provided otherwise in the Contract. Where the Contractor is responsible for the design of any part of the permanent Works, the extent of his obligations must be stated.
- 2. Specifications from previous similar projects are useful and may not be necessary to re-write specifications for every Works Contract.
- 3. There are considerable advantages in standardizing **General Specifications** for repetitive Works in recognized public sectors, such as high ways, urban housing, irrigation and water supply. The General Specifications should cover all classes of workmanship, materials and equipment commonly involved in constructions, although not necessarily to be used in a particular works contract. Deletions or addenda should then adapt the General Specifications to the particular Works.
- 4. Caremust be taken in drafting Specifications to ensure they are not restrictive. In the Specifications of standards for materials, plant and workmanship, existing Kenya Standards should be used as much as possible, otherwise recognized international standards may also be used.
- 5. The Procuring Entity should decide whether technical solutions to specified parts of the Works are to be permitted. Alternatives are appropriate in cases where obvious (and potentially less costly) alternatives are possible to the technical solutions indicated in tender documents for certain elements of the Works, taking into consideration the comparative specialized advantage of potential tenderers.
- 6. The Procuring Entity should provide a description of the selected parts of the Works with appropriate reference to Drawings, Specifications, Bills of Quantities, and Design or Performance criteria, stating that the alternative solutions shall be at least structurally and functionally equivalent to the basic design parameters and Specifications.
- 7. Such alternative solutions shall be accompanied by all information necessary for a complete evaluation by the Procuring Entity, including drawings, design calculations, technical specifications, breakdown of prices, proposed construction methodology, and other relevant details. Technical alternatives permitted in this manner shall be considered by the Procuring Entity each on its own merits and independently of whether the tenderer has priced the item as described in the Procuring Entity's design included with the tender documents.

#### **SECTION VII - DRAWINGS**

<u>Note</u> A list of drawings should be inserted here. The actual drawings including Site plans should be annexed in a separate booklet.



### SECTION VIII - GENERAL CONDITIONS OF CONTRACT (GCC)

[Name of Procuring Entity]

[Name of Contract]

[Architect Name and Address]

#### **General Conditions of Contract**

\_\_\_\_\_\_

#### 1. GENERALPROVISIONS

#### 1.1 Definitions

In this Contract, except where context otherwise requires, the following terms shall be interpreted as indicated below. Words indicating persons or parties include corporations and other legal entities, except where the context requires otherwise.

- "Accepted Contract Amount" means the amount accepted in the Letter of Acceptance for the execution and completion of the Works and the remedying of any defects.
- "Base Date" means a date 30 day prior to the submission of tenders.
- "Bill of Quantities" means the priced and completed Bill of Quantities forming part of the tender.
- "Completion Date" meansthedateofcompletionofthe Worksascertified by the Engineer.
- "Contract Price" means the price defined in the contract and there after as adjusted in accordance with the provisions of the Contract.
- "Contract" means the agreement entered into between the Procuring Entity and the Contractor as recorded in the Agreement Form and signed by the parties including all attachments and appendices thereto and all documents incorporated by reference therein to execute, complete, and maintain the Works.
- "Contractor's Documents" means the calculations, computer programs and other software, progress reports, drawings, manuals, models and other documents of a technical nature (if any) supplied by the Contractor under the Contract.
- "Contractor's Equipment" means all apparatus, machinery, vehicles and other things required for the execution and completion of the Works and the remedying of any defects. However, Contractor's Equipment excludes Temporary Works, Procuring Entity's Equipment (if any), Plant, Materials and any other things intended to form or forming part of the Permanent Works.
- "Contractor's Personnel" means the Contractor's Representative and all personnel whom the Contractor utilizes on Site, who may include the staff, labor and other employees of the Contractor and of each Subcontractor; and any other personnel assisting the Contractor in the execution of the Works.
- "Contractor's Representative" means the person named by the Contractor in the Contractor appointed from time to timeby the Contractor who acts on behalf of the Contractor.
- "Contractor" means the person(s) named as contractor in the Form of Tender accepted by the Procuring Entity.
- "Cost" means expenditure reasonably incurred (or to be incurred) by the Contractor, whether on or off the Site, including overhead and similar charges, but does not include profit.
- "Day" means a calendar day and "year" means 365 days.

"Dayworks" means Work inputs	s subject to payment on a t	ime basis for labour and the	e associated materials and plant.

- "Defect" means any part of the Works not completed in accordance with the Contract.
- "Defects Liability Certificate" means the certificate issued by Architect upon correction of defects by the Contractor.
- "Defects Liability Period" means the period named in the Special Conditions of Contract and calculated from the Completion Date, within which the contractor is liable for any defects that may develop in the handed over works.
- **"Defects Notification Period"** means the period for notifying defects in the Works oraSection(asthecasemaybe) under Sub-Clause 11.1 [Completion of Outstanding Work and Remedying Defects], whichextendsoverthedaysstated intheSpecialConditionsofContract.
- "Drawings" means the drawings of the Works, as included in the Contract, and any additional and modified drawings issued by (or on behalf of) the Procuring Entity in accordance with the Contract.
- **"Final Payment Certificate"** means the payment certificate issued under Sub-Clause 14.13 [Issue of Final Payment Certificate].
- "Final Statement" means the statement defined in Sub-Clause 14.11 [ApplicationforFinalPaymentCertificate].
- "Force Majeure" is defined in Clause19 [Force Majeure].
- **"Foreign Currency"** means a currency of another country (not Kenya) in which part (or all) of the Contract Price is payable, but not the Local Currency.
- "Goods" means Contractor's Equipment, Materials, Plant and Temporary Works, or any of them as appropriate.
- "Interim Payment Certificate" means a payment certificate issued under Clause 14 [Contract Price and Payment], other than the Final Payment Certificate.
- "Laws" means all national legislation, statutes, ordinances, and regulations and by-laws of any legally constituted public authority.
- "Letter of Acceptance" means the letter of formal acceptance of a tender, signed by Procuring Entity, including any annexed memoranda comprising agreements between and signed by both Parties.
- "Local Currency" means the currency of Kenya.
- "Materials" means things of all kinds (other than Plant) intended to form or forming part of the Permanent Works, including the supply-only materials (if any) to be supplied by the Contractor under the Contract.
- "Notice of Dissatisfaction" means the notice given by either Party to the other under Sub-Clause 20.3 indicating its dissatisfaction and intention to commence arbitration.
- "Special Conditions of Contract" means the pages completed by the Procuring Entity entitled Special Conditions of Contract which constitute Part A of the Special Conditions.
- "Party" means the Procuring Entity or the Contractor, as the context requires.
- "Payment Certificate" means a payment certificate issued under Clause 14 [Contract Price and Payment].
- "Performance Certificate" means the certificate issued under Sub-Clause 11.9 [Performance Certificate].
- "Performance Security" means the security (or securities, if any) under Sub-Clause 4.2 [Performance Security].
- "Permanent Works" means the permanent works to be executed by the Contractor under the Contract.

- "Plant" means the apparatus, machinery and other equipment intended to form or forming part of the Permanent Works, including vehicles purchased for the Procuring Entity and relating to the construction or operation of the Works.
- "Procuring Entity's Equipment" means the apparatus, machinery and vehicles (if any) made available by the Procuring Entity for the use of the Contract or in the execution of the Works, as stated in the Specification; but does not include Plant which has not been taken over by the Procuring Entity.
- "Procuring Entity's Personnel" means the Engineer, the Engineer, the assistants and all other staff, labor and other employees of the Architect and of the Procuring Entity; and any other personnel notified to the Contractor, by the Procuring Entity or the Engineer, as Procuring Entity's Personnel.
- "Procuring Entity" means the Entity named in the Special Conditions of Contract.
- **"Engineer"** is the person named in the Appendix to Conditions of Contract (or any other competent person appointed by the Procuring Entity and notified to the Contractor, to act in replacement of the Engineer) who is responsible for supervising the execution of the Works and administering the Contract and shall be an "Architect" or a "Quantity Surveyor" registered under the Architects and Quantity Surveyors Act Cap 525 or an "Engineer" registered under Engineers Registration Act Cap 530.
- **"Engineer"** means the person appointed by the Procuring Entity to act as the Architect for the purposes of the Contract and named in the Special Conditions of Contract, or other person appointed from time to time by the Procuring Entity and notified to the Contractor
- **"Provisional Sum"** means a sum (if any) which is specified in the Contract as a provisional sum, for the execution of any part of the Works or for the supply of Plant, Materials or services under Sub-Clause 13.5 [Provisional Sums].
- "Retention Money" means the accumulated retention moneys which the Procuring Entity retains under Sub-Clause 14.3 [Application for Interim Payment Certificates] and pays under Sub-Clause 14.9 [Payment of Retention Money].
- "Schedules" means the document(s) entitled schedules, completed by the Contractor and submitted with the Form of Tender, as included in the Contract.
- "Section" means a part of the Works specified in the Special Conditions of Contract as a Section (if any)
- "Site Investigation Reports" are those reports that may be included in the tendering documents which a ref actual and interpretative about the surface and sub-surface condition sat the Site.
- "Site" means the places where the Permanent Works are to be executed, including storage and working areas, and to which Plant and Materials are to be delivered, and any other places as may be specified in the Contract as forming part of the Site.
- "Specification" means the document entitled specification, as included in the Contract, and any additions and modifications to the specification in accordance with the Contract. Such document specifies the Works.
- "Start Date" or "Commencement Date" is the latest date when the Contractor shall commence execution of the Works. It does not necessarily coincide with the Site possession date(s).
- "Statement" means a statement submitted by the Contractor as part of an application, under Clause 14 [Contract Price and Payment], for a payment certificate.
- "Subcontractor" means any person named in the Contract as a subcontractor, or any person appointed as a subcontractor, for a part of the Works.
- "Taking-Over Certificate" means a certificate issued under Clause 10 [Procuring Entity's Taking Over].
- "Temporary Works" means all temporary works of every kind (other than Contractor's Equipment) required on Site for the execution and completion of the Permanent Works and the remedying of any defects.

- "Temporary works" means works designed, constructed, installed, and removed by the Contractor which are needed for construction or installation of the Works.
- "Tender" means the Form of Tender and all other documents which the Contractor submitted with the Form of Tender, as included in the Contract.
- "Tests after Completion" means the tests (if any) which are specified in the Contract and which are carried out in accordance with the Specification after the Works or a Section (as the case may be) are taken over by the Procuring Entity.
- "Testson Completion" means the tests which are specified in the Contractor agreed by both Parties or instructed as a Variation, and which are carried out under Clause 9 [Tests on Completion] before the Works or a Section (as the case may be) are taken over by the Procuring Entity.
- "Time for Completion" means the time for completing the Works or a Section (as the case may be) as stated in the Special Conditions of Contract (with any extension calculated from the Commencement Date.
- "Unforeseeable" means not reasonably foreseeable by an experienced contractor by the Base Date.
- "Variation" means any change to the Works, which is instructed or approved as a variation under Clause 13 [Variations and Adjustments].
- "Works" means the items the Procuring Entity requires the Contractor to undertake as defined in the Appendix to Conditions of Contract. "Works" may also mean the Permanent Works and the Temporary Works, or either of them as appropriate.

### 1.2 Interpretation

In the Contract, except where the context requires otherwise: a)

Words indicating one gender include all genders;

- b) words indicating the singular also include the plural and words indicating the plural also include the singular;
- c) provisions including the word "agree", "agreed" or "agreement" require the agreement to be recorded in writing;
- d) "written" or "in writing" means hand-written, type-written, printed or electronically made, and resulting in a permanent record; and

The marginal words and other headings shall not be taken into consideration in the interpretation of these Conditions.

#### 1.3 Communications

- 1.3.1 Wherever these Conditions provide for the giving or issuing of approvals, certificates, consents, determinations, notices, requests and discharges, these communications shall be:
  - a) In writing and delivered by hand (against receipt), sent by mail or courier, or transmitted using any of the agreed systems of electronic transmission as stated in the Special Conditions of Contract; and
  - b) delivered, sentor transmitted to the addressf or the recipient's communications as stated in the Special Conditions of Contract. However:
    - i) if the recipient gives notice of another address, communications shall thereafter be delivered accordingly; and
    - ii) if the recipient has not stated otherwise when requesting an approval or consent, it may be sent to the addressfromwhichtherequestwasissued.
- 1.3.2 Approvals, certificates, consents and determinations shall not be unreasonably withheld or delayed. When a certificate is issued to a Party, the certifier shall send a copy to the other Party. When a notice is issued to a Party, by the other Party or the Engineer, a copy shall be sent to the Architect or the other Party, as the case may be.

### 1.4 Law and Language

- **1.4.1** The Contract shall be governed by the laws of **Kenya**.
- 1.4.2 The ruling language of the Contract shall be English.

### 1.5 Priority of Documents

The documents forming the Contract are to be taken as mutually explanatory of one another. For the purposes of interpretation, the priority of the documents shall be in accordance with the following sequence:

- a) The Contract Agreement,
- b) The Letter of Acceptance,
- c) The Special Conditions Part A,
- d) the Special Conditions Part B
- e) the General Conditions of Contract
- f) the Form of Tender,
- g) the Specifications and Bills of Quantities
- h) the Drawings, and
- i) the Schedules and any other documents forming part of the Contract.

If an ambiguity or discrepancy is found in the documents, the Architect shall issue any necessary clarification or instruction.

### 1.6 Contract Agreement

The Parties shall enter into a Contract Agreement within 14 days after the Contractor receives the Contract Agreement, unless the Special Conditions establish otherwise. The Contract Agreement shall be based upon the formannexed to the Special Conditions. The costs of stamp duties and similar charges (if any) imposed by law in connection with entry into the Contract Agreement shall be borne by the Procuring Entity.

#### 1.7 Assignment

The Contractor shall not assign the whole or any part of the Contract or any benefit or interest in or under the Contract. However, the contractor:

- a) May as sign the whole or any part with the prior consent of the Procuring Entity, and
- b) may, as security in favor of a bank or financial institution, assign its right to moneys due, or to become due, under the Contract.

### 1.8 Care and Supply of Documents

- 1.8.1 The Specifications and Drawings shall be in the custody and care of the Procuring Entity. Unless otherwise stated in the Contract, two copies of the Contract and of each subsequent Drawings and Bills of Quantities shall be supplied to the Contractor, who may make or request further copies at the cost of the Contractor.
- 1.8.2 Each of the Contractor's Documents shall be in the custody and care of the Contractor, unless and until taken over bythe Procuring Entity. Unless otherwise stated in the Contract, the Contractor shall supply to the Architect two copies of each of the Contractor's Documents.
- 1.8.3 The Contractor shall keep, on the Site, a copy of the Contract, publications named in the Specification, the Contractor's Documents (if any), the Drawings and Variations and other communications given under the Contract. The Procuring Entity's Personnel shall have the right of access to all these documents at all reasonable times.
- 1.8.4 If a Party becomes aware of an error or defect in a document which was prepared for use in executing the Works, the Party shall promptly give notice to the other Party of such error or defect.

### 1.9 Timely provision of Drawings or Instructions

- 1.9.1 The Contractor shall give notice to the Architect whenever the Works are likely to be delayed or disrupted if any necessary drawing or instruction is not issued to the Contractor within a particular time, which shall be reasonable. The notice shall include details of the necessary drawing or instruction, details of why and by when it should be issued, and the nature and amount of the delay or disruption likely to be suffered if it is late.
- 1.9.2 If the Contractor suffers delay and/or incurs Cost as a result of a failure of the Architect to issue the notified drawing or instruction within a time which is reasonable and is specified in the notice with supporting details, the Contractor shall give a further notice to the Architect and shall be entitled subject to Sub-Clause 20.1 [Contractor's Claims] to:
  - a) an extension of time for any such delay, if completion is or will be delayed, under Sub-Clause 8.4 [Extension of Time for Completion], and
  - b) payment of any other associated costs accrued, which shall be included in the Contract Price.
- 1.9.3 After receiving this further notice, the Architect shall proceed in accordance with Sub-Clause 3.5 [Determinations] to agree or determine these matters.
- 1.9.4 However, if and to the extent that the Architect failure was caused by any error or delay by the Contractor, including an error in, or delay in the submission of, any of the Contractor's Documents, the Contractor shall not be entitled to such extension of time, or costs accrued.

### 1.10 Procuring Entity's Use of Contractor's Documents

- 1.10.1 Asagreed between the Parties, the Contractor shall retain the copyright and other intellectual property rights in the Contractor's Documents and other design documents made by (or on behalf of) the Contractor.
- 1.10.2 The Contractor shall be deemed (by signing the Contract) to give to the Procuring Entity a non-terminable transferable non-exclusive royalty-free license to copy, use and communicate the Contractor's Documents, including making and using modifications of them. This license shall:
  - a) apply throughout the actual or intended working life (whichever is longer) of the relevant parts of the Works,
  - b) entitle any person in proper possession of the relevant part of the Works to copy, use and communicate the Contractor's Documents for the purposes of completing, operating, maintaining, altering, adjusting, repairing and demolishing the Works, and
  - c) in the case of Contractor's Documents which are in the form of computer programs and other software, permit their use on any computer on the Site and other places as envisaged by the Contract, including replacements of any computers supplied by the Contractor.
- 1.10.3 The Contractor's Documents and other design documents made by (or on behalf of) the Contractor shall not, without the Contractor's consent, be used, copied or communicated to a third party by (or on behalf of) the Procuring Entityf or purposes other than those permitted under Sub-Clause 1.10.2.

### 1.11 Contractor's Use of Procuring Entity's Documents

As agreed between the Parties, the Procuring Entity shall retain the copyright and other intellectual property rights in the Specification, the Drawings and other documents made by (or on behalf of) the Procuring Entity. The Contractor may, at his cost, copy, use, and obtain communication of these documents for the purposes of the Contract. They shall not, without the Procuring Entity's consent, be copied, used or communicated to a third party by the Contractor, except as necessary for the purposes of the Contract.

#### 1.12 Confidential Details

1.12.1 The Contractor's and the Procuring Entity's Personnel shall ensure confidentiality at all times. The confidentiality shall survive termination or completion of the contract. They shall disclose all such confidential and other information as may be reasonably required in order to verify compliance with the Contract and allow its proper implementation.

1.12.2 The Contractor's and the Procuring Entity's Personnel shall also treat the details of the Contract as private and confidential, except to the extent necessary to carry out their respective obligations under the Contract or to comply with applicable Laws. Each of them shall not publish or disclose any particulars of the Works prepared by the other Party without the previous agreement of the other Party. However, the Contractor shall be permitted to disclose any publicly available information, or information otherwise required to establish his qualifications to compete for other projects.

### 1.13 Compliance with Laws

The Contractor shall, in performing the Contract, comply with applicable Laws. Unless otherwise stated in the Special Conditions of Contract:

- a) The Procuring Entity shall have obtained (or shall obtain) the planning, zoning, building permitor similar permission for the Permanent Works, and any other permissions described in the Specifications as having been (or to be) obtained by the Procuring Entity; and the Procuring Entity shall indemnify and hold the Contractor harmless against and from the consequences of any failure to do so; and
- b) the Contractor shall give all notices, pay all taxes, duties and fees, and obtain all permits, licenses and approvals, as required by the Laws in relation to the execution and completion of the Works and the remedying of any defects; and the Contractor shall indemnify and hold the Procuring Entity harmless against and from the consequences of any failure to do so, unless the Contractor is impeded to accomplish these actions and shows evidence of its diligence.

### 1.14 Joint and Several Liability

If the Contractor constitutes (under applicable Laws) a joint venture, consortium or other unincorporated grouping of two or more persons:

- a) These persons shall be deemed to be jointly and severally liable to the Procuring Entity for the performance of the Contract;
- b) these persons shall notify the Procuring Entity of their leader who shall have authority to bind the Contractor and each of these persons; and
- c) the Contractor shall not alter its composition or legal status without the prior consent of the Procuring Entity.

### 1.15 Inspections and Audit by the Procuring Entity

Pursuant to paragraph 2.2(e). of Appendix B to the General Conditions, the Contractor shall permit and shall cause its subcontractors and sub-consultants to permit, the Public Procurement Regulatory Authority, Procuring Entity and/or persons appointed or designated by the Government of Kenya to inspect the Site and/or the accounts and records relating to the procurement process, selection and/or contract execution, and to have such accounts and records audited by auditors appointed by the Procuring Entity if requested by the Procuring Entity. The Contractor's and its Subcontractors' and sub-consultants' attention is drawn to SubClause 15.6 (Fraud and Corruption) which provides, inter alia, that acts intended to materially impede the exercise ofthe Procuring Entity's inspection and audit rights constitute a prohibited practice subject to contract termination (as well as to a determination of in eligibility pursuant to the Procuring Entity's prevailing sanctions procedures).

#### 2. THE PROCURING ENTITY

### 2.1 Right of Access to the Site

2.1.1 The Procuring Entity shall give the Contractor right of access to, and possession of, all parts of the Site within thetime (or times) stated in the **Special Conditions of Contract.** The right and possession may not be exclusive to the Contractor. If, under the Contract, the Procuring Entity is required to give (to the Contractor) possession of any foundation, structure, plant or means of access, the Procuring Entity shall do so in the time and manner stated in the Specification. However, the Procuring Entity may withhold any such right or possession until the Performance Security has been received.

- 2.1.2 If no such time is stated in the Special Conditions of Contract, the Procuring Entity shall give the Contractor right of access to, and possession of, the Site within such times as required to enable the Contractor to proceed without disruption in accordance with the programme submitted under Sub-Clause 8.3 [Programme].
- 2.1.3 If the Contractor suffers delay and/or incurs Cost as a result of a failure by the Procuring Entity to give any such right or possession within such time, the Contractor shall give notice to the Architect and shall be entitled subject to Sub-Clause 20.1 [Contractor's Claims] to:
  - a) an extension of time for any such delay, if completion is or will be delayed, under Sub-Clause 8.4

[Extension of Time for Completion], and

- b) payment of any such Cost-plus profit, which shall be included in the Contract Price.
- 2.1.4 After receiving this notice, the Architect shall proceed in accordance with Sub-Clause 3.5 [Determinations] to agree or determine these matters.
- 2.1.5 However, if and to the extent that the Procuring Entity's failure was caused by any error or delay by the Contractor, including an error in, or delay in the submission of, any of the Contractor's Documents, the Contractor shall not be entitled to such extension of time, Cost or profit.

### 2.2 Permits, Licenses or Approvals

- 2.2.1 The Procuring Entity shall provide, at the request of the Contractor, such reasonable assistance as to allow the Contractor to obtain properly:
  - a) Copies of the Laws of Kenya which are relevant to the Contract but are not readily available, and
  - b) any permits, licenses or approvals required by the Laws of Kenya:
    - i) which the Contractor is required to obtain under Sub-Clause 1.13 [Compliance with Laws], ii) for the delivery of Goods, including clearance through customs, and iii) for the export of Contractor's Equipment when it is removed from the Site.

### 2.3 Procuring Entity's Personnel

The Procuring Entity shall be responsible for ensuring that the Procuring Entity's Personnel and the Procuring Entity's other contractor son the Site:

- a) co-operate with the Contractor's efforts under Sub-Clause 4.6 [Co-operation], and
- b) take action ssimilar to those which the Contractor is required to take under sub-paragraphs (a), (b) and (c) of Sub-Clause 4.8 [Safety Procedures] and under Sub-Clause 4.18 [Protection of the Environment].

#### 2.4 Procuring Entity's Financial Arrangements

The Procuring Entity shall make and maintain all necessary financial arrangements which will enable the Procuring Entity to pay the Contract Price punctually (as estimated at that time) in accordance with Clause14 [Contract Price and Payment].

# 3. THE ENGINEER

#### 3.1 Architect Duties and Authority

- 3.1.1 The Procuring Entity shall appoint the Architect who shall carry out the duties as signed to him in the Contract. The Architect staff shall include suitably qualified Assistants and other professionals who are competent to carry out these duties. The Architect Name and Address shall be provided in the **Special Conditions of Contract.**
- 3.1.2 The Architect shall have no authority to amend the Contract.

- 3.1.3 The Architect May exercise the authority attributable to the Architect as specified in or necessarily to be implied from the Contract. If the Architectis required to obtain the approval of the Procuring Entity before exercising a specified authority, the requirements shall be as stated in the Special Conditions of Contract. The Procuring Entity shall promptly inform the Contractor of any change to the authority attributed to the Engineer.
- 3.1.4 However, whenever the Architect exercises a specified authority for which the Procuring Entity's approvalis required, then (for the purposes of the Contract) the contractor shall require the Architect toprovideevidence of such approval before complying with the instruction. 3.1.5 Except as otherwise stated in these Conditions:
  - a) Whenever carrying out duties or exercising authority, specified in or implied by the Contract, the

Architect shallbedeemedtoactfortheProcuring Entity;

- b) the Architect has no authority to relieve either Party of any duties, obligations or responsibilities under the Contract;
- c) any approval, check, certificate, consent, examination, inspection, instruction, notice, proposal, request, test, or similar act by the Architect (including absence of disapproval) shall not relieve the Contractor from any responsibility he has under the Contract, including responsibility for errors, omissions, discrepancies and non-compliances; and
- d) anyact by the Architect in response to a Contractor's request shall be notified in writing to the Contractor within 14 days of receipt.
- 3.1.6 The following provisions shall apply:

The Architect shall obtain the specific approval of the Procuring Entity before taking action under thefollowing Sub-Clauses of these Conditions:

- a) Sub-Clause 4.12: agreeing or determining an extension of time and/or additional cost.
- b) Sub-Clause 13.1: instructing a Variation, except;
  - i) In an emergency situation as determined by the Engineer, or ii) If such a Variation would increase the Accepted Contract Amount by less than the percentage specified in the **Special Conditions of Contract.**
- c) Sub-Clause 13.3: Approving a proposal for Variation submitted by the Contractor in accordance with Sub Clause 13.1 or 13.2.
- d) Sub-Clause 13.4: Specifying the amount payable in each of the applicable three currencies.
- 3.1.7 Not withstanding the obligation, as set out above, to obtain approval, if, in the opinion of the Engineer, an emergency occurs affecting the safety of life or of the Works or of adjoining property, he may, without relieving the Contractor of any of his duties and responsibility under the Contract, instruct the Contractor to execute all such work or to do all such things as may, in the opinion of the Engineer, be necessary to abate or reduce the risk. The Contractor shall forth with comply, despite the absence of approval of the Procuring Entity, with any such instruction of the Engineer. The Architect shall determine an addition to the Contract Price, in respect of such instruction, in accordance with Clause 13 and shall notify the Contractor accordingly, with a copy to the Procuring Entity.

### 3.2 Delegation by the Engineer

3.2.1 The Architect may from time to time assign duties and delegate authority to assistants and may also revoke such assignment or delegation. These assistants may include a resident Engineer, and/or independent inspectors appointed to inspect and/ or test items of Plant and/or Materials. The assignment, delegation or revocation shall be in writing and shall not take effect until copies have been received by both Parties. However, unless otherwise agreed by both Parties, the Architect shall not delegate the authority to determine any matter in accordance with Sub-Clause 3.5 [Determinations].

3.2.2 Each assistant, to whom duties have been assigned or authority has been delegated, shall only be authorized

to issue instructions to the Contractor to the extent defined by the delegation. Any approval, check, certificate, consent, examination, inspection, instruction, notice, proposal, request, test, or similar act by an assistant, in accordance with the delegation, shall have the same effect as though the act had been an act of the Engineer. However:

- Any failure to disapprove any work, Plant or Materials shall not constitute approval, and shall therefore not prejudice the right of the Architect to reject the work, Plant or Materials;
- b) If the Contractor questions any determination or instruction of an assistant, the Contractor may refer the matter to the Engineer, who shall promptly confirm, reverse or vary the determination or instruction.

### 3.3 Instructions of the Engineer

- 3.3.1 The Architect may issue to the Contractor (at anytime) instructions and additional or modified Drawings which may benecessary for the execution of the Works and the remedying of any defects, all in accordance with the Contract. The Contractor shall only take instructions from the Engineer, or from an assistant to whom the appropriate authority has been delegated under Clause 3.2.1.
- 3.3.2 The Contractor shall comply with the instructions given by the Architect or delegated assistant, on any matter related to the Contract. Whenever practicable, their instructions shall be given in writing. If the Architect or a delegated assistant:
  - a) Gives an oral instruction,
  - b) receives a written confirmation of the instruction, from (or on behalf of) the Contractor, within two working days after giving the instruction, and
  - c) does not reply by issuing a written rejection and/or instruction within two working days after receiving the confirmation,

Then the confirmation shall constitute the written instruction of the Architect or delegated assistant (as the case may be).

### 3.4 Replacement of the Engineer

IftheProcuring Entity intends to replace the Engineer, the Procuring Entity shall, in not less than 21 days before theintendeddateofreplacement, give notice to the Contractor of the name, address and relevant experience of the intended person to replace the Engineer.

#### 3.5 Determinations

- 3.5.1 Whenever these Conditions provide that the Architect shall proceed in accordance with this Sub-Clause3.5 to agreeor determine any matter, the Architect shall consult with each Party in an endeavor to reach agreement. If agreement is not achieved, the Architect shall make a fair determination in accordance with the Contract, taking due regard of all relevant circumstances.
- 3.5.1 The Architect shall give notice to both Parties of each agree mentor determination, with supporting particulars, within 30 days from the receipt of the corresponding claim or request except when otherwise specified. Each Party shall give effect to each agreement or determination unless and until revised under Clause 20 [Claims, Disputes and Arbitration].

#### 4. THE CONTRACTOR

# 4.1 Contractor's General Obligations

4.1.1 The Contractor shall design (to the extent specified in the Contract), execute and complete the Works in accordance with the Contract and with the Architect instructions, ands hall remedy any defects in the Works.

- 4.1.2 The Contractor shall provide the Plant and Contractor's Documents specified in the Contract, and all Contractor's Personnel, Goods, consumables and other things and services, whether of a temporary or permanent nature, required in and for this design, execution, completion and remedying of defects.
- 4.1.3 All equipment, material, and services to be incorporated in or required for the Works shall have their origin in any eligible source country.
- 4.1.4 The Contractor shall be responsible for the adequacy, stability and safety of all Site operations and of all methods of construction. Except to the extent specified in the Contract, the Contractor (i) shall be responsible for all Contractor's Documents, Temporary Works, and such design of each item of Plant and Materials as is required for the item to be in accordance with the Contract, and (ii) shall not otherwise be responsible for the designor specification of the Permanent Works.
- 4.1.5 The Contractor shall, whenever required by the Engineer, submit details of the arrangements and methods which the Contractor proposes to adopt for the execution of the Works. No significant alteration to these arrangements and methods shall be made without this having previously been notified to the Engineer.
- 4.1.6 If the Contract specifies that the Contractor shall design any part of the Permanent Works, then unless otherwise stated in the Special Conditions:
  - a) The Contractor shall submit to the Architect the Contractor's Documents for this part in accordance with the procedures specified in the Contract;
  - b) these Contractor's Documents shall be in accordance with the Specification and Drawings, shall be written in the language for communications defined in Sub-Clause 1.4 [Law and Language], and shall include additional information required by the Architect to add to the Drawings for co-ordination of each Party's designs;
  - c) the Contractor shall be responsible for this part and it shall, when the Works are completed, befit for such purposes for which the part is intended as are specified in the Contract; and
  - d) prior to the commencement of the Tests on Completion, the Contractor shall submit to the Architectthe "as-built" documents and, if applicable, operation and maintenance manuals in accordance with the Specification and in sufficient detail for the Procuring Entity to operate, maintain, dismantle, reassemble, adjust and repair this part of the Works. Such part shall not be considered to be completed for the purposes of taking-over under Sub-Clause 10.1 [Taking Over of the Works and Sections] until these documents and manuals have been submitted to the Engineer.

### **4.2** Performance Security

- 4.2.1 The Contractor shall obtain (at his cost) a Performance Security for proper performance, in the amount stated in the **Special Conditions of Contract** and denominated in the currency (ies) of the Contract or in a freely convertible currency acceptable to the Procuring Entity. If an amount is not stated in the Special Conditions of Contract, this Sub-Clause shall not apply.
- 4.2.2 The Contractor shall deliver the Performance Security to the Procuring Entity within 30 days after receiving the Notification of Award and shall send a copy to the Engineer. The Performance Security shall be issued by a reputable bank selected by the Contractor and shall be in the form annexed to the Special Conditions, as stipulated by the Procuring Entity in the Special Conditions of Contract, or in another form approved by the Procuring Entity.
- 4.2.3 The Contractor shall ensure that the Performance Security is valid and enforceable until the Contractor has executed and completed the Works and remedied any defects. If the terms of the Performance Security specify its expiry date, and the Contractor has not become entitled to receive the Performance Certificate by the date 30 days prior to the expiry date, the Contractor shall extend the validity of the Performance Security until the Works have been completed and any defects have been remedied.
- 4.2.4 The Procuring Entity shall not make a claim under the Performance Security, except for amounts to which the Procuring Entity is entitled under the Contract.

- 4.2.5 The Procuring Entity shall indemnify and hold the Contractor harmless against and from all damages, losses and expenses (including legal fees and expenses) resulting from a claim under the Performance Security to the extent to which the Procuring Entity was not entitled to make the claim.
- 4.2.6 The Procuring Entity shall return the Performance Security to the Contractor within 14 days after receiving a copyof the Taking-Over Certificate.
- 4.2.7 Without limitation to the provisions of the rest of this Sub-Clause, whenever the Architect determines an addition or a reduction to the Contract Price as a result of a change in cost and/ or legislation, or as a result of a Variation, amounting to more than 25 percent of the portion of the Contract Price payable in a specific currency, the Contractor shall at the Architect request promptly increase, or may decrease, as the case may be, the value of the Performance Security in that currency by an equal percentage.

### 4.3 Contractor's Representative

- 4.3.1 The Contractor shall appoint the Contractor's Representative and shall give him all authority necessary to act on the Contractor's behalf under the Contract. The Contractor's Representative's Name and Address shall be provided in the **Special Conditions of Contract.**
- 4.3.2 Unless the Contractor's Representative **is named in the Contract**, the Contractor shall, prior to the Commencement Date, submit to the Architect for consent the name and particulars of the person the Contractor proposes to appoint as Contractor's Representative. If consent is with held or subsequently revoked in terms of Sub-Clause 6.9 [Contractor's Personnel], or if the appointed person fails to act as Contractor's Representative, the Contractor shall similarly submit the name and particulars of an other suitable person for such appointment.
- 4.3.3 The Contractor shall not, without the prior consent of the Engineer, revoke the appointment of the Contractor's Representative or appoint are placement.
- 4.3.4 The whole time of the Contractor's Representative shall be given to directing the Contractor's performance of the Contract. If the Contractor's Representative is to be temporarily absent from the Site during the execution of the Works, a suitable replacement person shall be appointed, subject to the Architect prior consent, and the Architect shall be notified accordingly.
- 4.3.5 The Contractor's Representative shall, on behalf of the Contractor, receive instructions under Sub-Clause 3.3 [Instructions of the Engineer].
- 4.3.6 The Contractor's Representative may delegate any powers, functions and authority to any competent person, and may at any time revoke the delegation. Any delegation or revocation shall not take effect until the Architect has received prior notice signed by the Contractor's Representative, naming the person and specifying the powers, functions and authority being delegated or revoked.
- 4.3.7 The Contractor's Representative shall be fluent in the language for communications defined in Sub-Clause1.4 [Law and Language]. If the Contractor's Representative's delegates are not fluent in the said language, the Contractor shall make competent interpreter savailable during all working hours in a number deemed sufficient by the Engineer.

### 4.4 Sub-contractors

- 4.4.1 The Contractor shall not subcontract the whole of the Works. The contractor may however subcontract the works as provided in Clause 34.2.
- 4.4.2 The Contractor shall be responsible for the acts or defaults of any Subcontractor, his agents or employees, as if theyweret heacts or defaults of the Contractor. Unless otherwise stated in the Special Conditions: a) The Contractor shall not be required to obtain consent to suppliers solely of Materials, or to a subcontract for which the Subcontractor is named in the Contract;
- b) The prior consent of the Procuring Entity shall be obtained to other proposed Subcontractors;
- c) the Contractor shall give the Procuring Entity not less than 14 days' notice of the intended date of the commencement of each Subcontractor's work, and of the commencement of such work on the Site; and

- d) each subcontract shall include provisions which would entitle the Procuring Entity to require the subcontract to be assigned to the Procuring Entity under Sub-Clause 4.5 [Assignment of Benefit of Subcontract] (if or when applicable) or in the event of termination under Sub-Clause 15.2 [Termination by Procuring Entity].
- 4.4.3 The Contractor shall ensure that the requirements imposed on the Contractor by Sub-Clause 1.12 [Confidential Details] apply equally to each Subcontractor.
- 4.4.4 Wher epracticable, the Contractor shall give fair and reasonable opportunity for contractors from Kenya to be appointed as Subcontractors.

# 4.5 Assignment of Benefit of Subcontract

If a Subcontractor's obligations extend beyond the expiry date of the relevant Defects Notification Period and the Engineer, prior to this date, instructs the Contractor to assign the benefit of such obligations to the Procuring Entity, then the Contractor shall do so. Unless otherwise stated in the assignment, the Contractor shall have no liability to the Procuring Entity for the work carried out by the Subcontractor after the assignment takes effect.

### 4.6 Co-operation

- 4.6.1 The Contractor shall, as specified in the Contract or as instructed by the Engineer, allow appropriate opportunities for carrying out work to:
  - a) The Procuring Entity's Personnel,
  - b) Any other contractors employed by the Procuring Entity, and
  - c) The personnel of any legally constituted public authorities, who may be employed in the execution on or near the Site of any work not included in the Contract.
- 4.6.2 Any such instruction shall constitute a Variation if and to the extent that it cause sthe Contractor to suffer delays and/ortoincur Unforeseeable Cost. Services for these personnel and other contractors may include the use of Contractor's Equipment, Temporary Works or access arrangements which are the responsibility of the Contractor.
- 4.6.3 If, under the Contract, the Procuring Entity is required to give to the Contractor possession of any foundation, structure, plant or means of access in accordance with Contractor's Documents, the Contractor shall submit such documents to the Architect in the time and manner stated in the Specification.

### 4.7 Setting Out of the Works

- 4.7.1 The Contractor shall set out the Works in relation to original points, lines and levels of reference specified in the Contractor notified by the Engineer. The Contractor shall be responsible for the correct positioning of all parts of the Works, and shall rectify any error in the positions, levels, dimensions or alignment of the Works.
- 4.7.2 The Procuring Entity shall be responsible for any errors in these specified or notified items of reference, but the Contractor shall use reasonable efforts to verify their accuracy before they are used.
- 4.73 If the Contractor suffers delay and/or incurs Cost from executing work which was necessitated by an errorin these items of reference, and an experienced contractor could not reasonably have discovered such error and avoided this delay and/ or Cost, the Contractor shall give notice to the Architect and shall be entitled subject to Sub-Clause 20.1 [Contractor's Claims] to:
  - a) an extension of time for any such delay, if completion is or will be delayed, under Sub-Clause 8.4 [Extension of Time for Completion], and
  - b) payment of any such costs accrued, which shall be included in the Contract Price.

4.7.4 After receiving this notice, the Architect shall proceed in accordance with Sub-Clause 3.5 [Determinations] to agree or determine (i) whether and (if so) to what extent the error could not reasonably have been discovered, and (ii) the matters described in sub-paragraphs (a) and (b) above related to thise.

# 4.8 Safety Procedures

The Contractor shall:

- a) Comply with all applicable safety regulations,
- b) Takec are for the safety of all persons entitled to be on the Site,
- c) Use reasonable efforts to keep the Site and Works clear of unnecessary obstruction so as to avoid danger to these persons,
- d) provide fencing, lighting, guarding and watching of the Works until completion and taking over under Clause 10 [Procuring Entity's Taking Over], and
- e) provide any Temporary Works (including roadways, footways, guards and fences) which may be necessary, because of the execution of the Works, for the use and protection of the public and of owners and occupiers of adjacent land.

### 4.9 Quality Assurance

- 4.9.1 The Contractor shall institute a quality assurance system to demonstrate compliance with the requirements of the Contract. The system shall be in accordance with the details stated in the Contract. The Architect shall be entitled audit any aspect of the system.
- 4.9.2 Details of all procedures and compliance documents shall be submitted to the Architectf or information before each design and execution stage is commenced. When any document of a technical nature is issued to the Engineer, evidence of the prior approval by the Contractor itself shall be apparent on the document itself.

Compliance with the quality assurance system shall not relieve the Contractor of any of his duties, obligations or responsibilities under the Contract.

### 4.10 Site Data

- 4.10.1 The Procuring Entity shall have made available to the Contractor for his information, prior to the Base Date, all relevant data in the Procuring Entity's possession on sub-surface and hydrological conditions at the Site, including environmental aspects. The Procuring Entity shall similarly make available to the Contractor all such data which come into the Procuring Entity's possession after the Base Date. The Contractor shall be responsible for interpreting all such data.
- 4.10.2 To the extent which was practicable (taking account of cost and time), the Contractor shall be deemed to have obtained all necessary information as to risks, contingencies and other circumstances which may influence or affect the Tender or Works. To the same extent, the Contractor shall be deemed to have inspected and examined the Site, its surroundings, the above data and other available information, and to have been satisfied before submitting the Tender as to all relevant matters, including (without limitation):
  - a) The form and nature of the Site, including sub-surface conditions,
  - b) the hydrological and climatic conditions,
  - c) the extent and nature of the work and Goods necessary for the execution and completion of the Works and the remedying of any defects,
  - d) the Laws, procedures and labour practices of Kenya, and
  - e) the Contractor's requirements for access, accommodation, facilities, personnel, power, transport, water and other services.

# 4.11 Sufficiency of the Accepted Contract Amount

- 4.11.1 TheContractor shall be deemed to:
  - a) Have satisfied itself as to the correctness and sufficiency of the Accepted Contract Amount, and
  - b) have based the Accepted Contract Amount on the data, interpretations, necessary information, inspections, examinations and satisfaction as to all relevant matters referred to in Sub-Clause 4.10 [Site Data].
- 4.11.2 Unless otherwise stated in the Contract, the Accepted Contract Amount covers all the Contractor's obligations under the Contract (including those under Provisional Sums, if any) and all things necessary for the proper execution and completion of the Works and the remedying of any defects.

# 4.12 Unforeseeable Physical Conditions

- 4.12.1 In this Sub-Clause, "physical conditions" means natural physical conditions and man-made and other physical obstructions and pollutants, which the Contractor encounters at the Site when executing the Works, including sub-surface and hydrological conditions but excluding climatic conditions.
- 4.12.2 If the Contractor encounters adverse physical conditions which he considers to have been Unforeseeable, the Contractor shall give notice to the Architect as soon as practicable.
- 4.12.3 This notice shall describe the physical conditions, so that they can be inspected by the Architect and shall set out the reasons why the Contractor considers them to be Unforeseeable. The Contractor shall continue executing the Works, using such proper and reasonable measures as are appropriate for the physical conditions, and shall comply with any instructions which the Architect may give. If an instruction constitutes a Variation, Clause 13 [Variations and Adjustments] shall apply.
- 4.12.4 If and to the extent that the Contractor encounters physical conditions which are Unforeseeable, gives such a notice, and suffers delay and/or incurs Cost due to these conditions, the Contractor shall be entitled subject to notice under Sub-Clause 20.1 [Contractor's Claims] to:
  - a) an extension of time for any such delay, if completion is or will be delayed, under Sub-Clause 8.4

[Extension of Time for Completion], and

- b) payment of any such Cost, which shall be included in the Contract Price.
- 4.12.5 Upon receiving such notice and inspecting and/or investigating these physical conditions, the Architect shall proceed in accordance with Sub-Clause 3.5 [Determinations] to agree or determine (i) whether and (if so) to what extent these physical conditions were Unforeseeable, and (ii) the matters described in sub-paragraphs (a) and (b) above related to this extent.
- 4.12.6 However, before additional Cost is finally agreed or determined under sub-paragraph (ii), the Architect may also review whether other physical conditions in similar parts of the Works (if any) were more favorable than could reasonably have been foreseen when the Contractor submitted the Tender. If and to the extent that these more favorable conditions were encountered, the Architect may proceed in accordance with Sub-Clause 3.5 [Determinations] to agree or determine the reductions in Cost which were due to these conditions, which may be included (as deductions) in the Contract Price and Payment Certificates. However, the net effect of all adjustments under sub-paragraph (b) and all these reductions, for all the physical conditions encountered in similar parts of the Works, shall not result in a net reduction in the Contract Price.
- 4.12.7 The Architect shall take account of any evidence of the physical conditions foreseen by the Contractorwhen submitting the Tender, which shall be made available by the Contractor, but shall not be bound by the Contractor's interpretation of any such evidence.

#### 4.13 Rights of Way and Facilities

Unless otherwise specified in the Contract the Procuring Entity shall provide effective access to and possession of the Site including special and/or temporary rights-of-way which are necessary for the Works. The Contractor shall obtain, at his risk and cost, any additional rights of way or facilities out side the Site which he may require for the purposes of the Works.

#### 4.14 Avoidance of Interference

- 4.14.1 The Contractor shall not interfere unnecessarily or improperly with:
  - a) The convenience of the public, or
  - b) The access to and use and occupation of all roads and foot paths, irrespective of whether they are public or in the possession of the Procuring Entity or of others.
- 4.14.2 The Contractor shall indemnify and hold the Procuring Entity harmless against and from all damages, losses and expenses (including legal fees and expenses) resulting from any such unnecessary or improper interference.

#### 4.15 Access Route

- 4.15.1 The Contractor shall be deemed to have been satisfied as to the suitability and availability of access routes to the Site at Base Date. The Contractor shall use reasonable efforts to prevent any road or bridge from being damaged by the Contractor's traffic or by the Contractor's Personnel. These efforts shall include the proper use of appropriate vehicles and routes.
- 4.15.2 Except as otherwise stated in these Conditions:
  - a) The Contractor shall (as be tween the Parties) be responsible for any maintenance which may be required for his use of access routes;
  - b) the Contractor shall provide all necessary signs or directions along access routes, and shall obtain any permission which may be required from the relevant authorities for his use of routes, signs and directions;
  - c) the Procuring Entity shall not be responsible for any claims which may arise from the use or otherwise of any access route;
  - d) the Procuring Entity does not guarantee the suitability or a vailability of particular access routes; and
  - e) Costs due to non-suitability or non-availability, for the use required by the Contractor, of access routes shall be borne by the Contractor.

#### 4.16 Transport of Goods

Unless otherwise stated in the Special Conditions:

- a) the Contractor shall give the Architect not less than 21 days' notice of the date on which any Plant or a major item of other Goods will be delivered to the Site;
- b) the Contractor shall be responsible for packing, loading, transporting, receiving, unloading, storing and protecting all Goods and other things required for the Works; and
- c) the Contractor shall indemnify and hold the Procuring Entity harmless against and from all damages, losses and expenses (including legal fees and expenses) resulting from thetransport of Goods and shall negotiate and pay all claims arising from their transport.

#### 4.17 Contractor's Equipment

The Contractor shall be responsible for all Contractor's Equipment. When brought on to the Site, Contractor's Equipment shall be deemed to be exclusively intended for the execution of the Works. The Contractor shall not remove from the Site any major items of Contractor's Equipment without the consent of the Engineer. However, consent shall not be required for vehicles transporting Goods or Contractor's Personnel off Site.

#### 4.18 Protection of the Environment

4.18.1 The contractor shall comply with the applicable environmental laws, regulations and policies.

- 4.18.2 The Contractor shall take all reasonable steps to protect the environment (both on and off the Site) and to limit damage and nuisance to people and property resulting from pollution, noise and other results of his operations.
- 4.18.3 The Contractors hall ensure that emissions, surfaced is charges and effluent from the Contractor's activities shall not exceed the values stated in the Specification or prescribed by applicable Laws.

### 4.19 Electricity, Water and Gas

- 4.19.1 The Contractor shall, except as stated below, be responsible for the provision of all power, water and other services he may require for his construction activities and to the extent defined in the Specifications, for the tests.
- 4.19.2 The Contractor shall be entitled to use for the purposes of the Works such supplies of electricity, water, gas and other services as may be available on the Site and of which details and prices are given in the Specifications. The Contractor shall, at his risk and cost, provide any apparatus necessary for his use of these services and for measuring the quantities consumed.
- 4.19.3 The quantities consumed and the amounts due (at these prices) for such services shall be agreed or determined by the Architect in accordance with Sub-Clause 2.5 [Procuring Entity's Claims] and Sub-Clause 3.5 [Determinations]. The Contractor shall pay these amounts to the Procuring Entity. **4.20 Procuring Entity's Equipment and Free-Issue Materials**
- 4.20.1 The Procuring Entity shall make the Procuring Entity's Equipment (if any) available for the use of the Contractor in the execution of the Works in accordance with the details, arrangements and prices stated in the Specification. Unless otherwise stated in the Specification:
  - a) The Procuring Entitys hall be responsible for the Procuring Entity's Equipment, except that
  - b) the Contractor shall be responsible for each item of Procuring Entity's Equipment whilst any of the Contractor's Personnel is operating it, driving it, directing it or in possession or control of it.
- 4.20.1 The appropriate quantities and the amounts due (at such stated prices) for the use of Procuring Entity's Equipment shall be agreed or determined by the Architect in accordance with Sub-Clause 2.5 [Procuring Entity's Claims] and Sub-Clause 3.5 [Determinations]. The Contractor shall pay these amounts to the Procuring Entity.
- 4.20.2 The Procuring Entity shall supply, free of charge, the "free-issue materials" (if any) in accordance with the details stated in the Specification. The Procuring Entity shall, at his risk and cost, provide these materials at the time and place specified in the Contract. The Contractor shall then visually inspect them and shall promptly give notice to the Architect of any shortage, defect or default in these materials. Unless otherwise agreed by both Parties, the Procuring Entity shall immediately rectify the notified shortage, defector default.
- 4.20.3 After this visual inspection, the free-issue materials shall come under the care, custody and control of the Contractor. The Contractor's obligations of inspection, care, custody and control shall not relieve the Procuring Entity of liability for any shortage, defect or default not apparent from a visual inspection. **4.21 Progress Reports**
- 4.21.1 Unless otherwise stated in the Special Conditions, monthly progress reports shall be prepared by the Contractor and submitted to the Architect in six copies. The first report shall cover the period up to the end of the first calendar month following the Commencement Date. Reports shall be submitted monthly thereafter, each within 7 days after the last day of the period to which it relates.
- 4.21.2 Reporting shall continue until the Contractor has completed all work which is known to be outstanding at the completion date stated in the Taking-Over Certificate for the Works. Each report shall include:

- a) charts and detailed descriptions of progress, including each stage of design (if any), Contractor's Documents, procurement, manufacture, delivery to Site, construction, erection and testing; and including these stages for work by each nominated Subcontractor (as defined in Clause 5 [NominatedSubcontractors]),
- b) photographs showing the status of manufacture and of progress on the Site;
- c) for the manufacture of each main item of Plant and Materials, the name of the manufacturer, manufacture location, percentage progress, and the actual or expected dates of: i) commencement of manufacture, ii) Contractor's inspections, iii) tests, and
  - iv) shipment and arrival at the Site;
- d) the details described in Sub-Clause 6.10 [Records of Contractor's Personnel and Equipment];
- e) copies of quality assurance documents, test results and certificates of Materials;
- f) list of notices given under Sub-Clause 2.5 [Procuring Entity's Claims] and notices given under Sub-Clause 20.1 [Contractor's Claims];
- g) safety statistics, including details of any hazardous incidents and activities relating to environmental aspects and public relations; and
- h) comparison so factual and planned progress, with details of any events or circumstances which may jeopardize the completion in accordance with the Contract, and the measures being (or to be) adopted to overcome delays.

### 4.22 Security of the Site

Unless otherwise stated in the Special Conditions:

- a) The Contractor shall be responsible for keeping unauthorized persons off the Site, and
- b) authorized persons shall be limited to the Contractor's Personnel and the Procuring Entity's Personnel; and to any other personnel notified to the Contractor, by the Procuring Entity or the Engineer, as authorized personnel of the Procuring Entity's other contractors on the Site. **4.23 Contractor's Operations on Site**
- 4.23.1 The Contractor shall confine his operations to the Site, and to any additional areas which may be obtained by the Contractor and agreed by the Architect as additional working areas. The Contractor shall take all necessary precautions to keep Contractor's Equipment and Contractor's Personnel within the Site and these additional areas, and to keep them off adjacentl and.
- 4.23.2 During the execution of the Works, the Contractor shall keep the Site free from all unnecessary obstruction and shall store or dispose of any Contractor's Equipment or surplus materials. The Contractor shall clear away and remove from the Site any wreckage, rubbish and Temporary Works which are no longer required.
- 4.23.3 Upon the issue of a Taking-Over Certificate, the Contractor shall clear away and remove, from that part of the Site and Works to which the Taking-Over Certificate refers, all Contractor's Equipment, surplus material, wreckage, rubbish and Temporary Works. The Contractor shall leave that part of the Site and the Works in a clean and safe condition. However, the Contractor may retain on Site, during the Defects Notification Period, such Goods as are required for the Contractor to fulfil obligations under the Contract.

#### 4.24 Fossils

- 4.24.1 All fossils, coins, articles of value or antiquity, and structures and other remains or items of geological or archaeological interest found on the Site shall be placed under the care and authority of the Procuring Entity. The Contractor shall take reasonable precautions to prevent Contractor's Personnel or other persons from removing or damaging any of these findings.
- 4.24.2 The Contractor shall, upon discovery of any such finding, promptly give notice to the Engineer, who shall issue instructions for dealing with it. If the Contractor suffers delay and/or incurs Cost from complying with

the instructions, the Contractor shall give a further notice to the Architect and shall be entitled subject to Sub-Clause 20.1 [Contractor's Claims] to:

- a) an extension of time for any such delay, if completion is or will be delayed, under Sub-Clause 8.4 [Extension of Time for Completion], and
- b) payment of any such Cost, which shall be included in the Contract Price.

  After receiving this further notice, the Architect shall proceed in accordance with Sub-Clause 3.5 [Determinations] to agree or determine these matters.

# 5. NOMINATED SUBCONTRACTORS

#### 5.1 Definition of "nominated Subcontractor"

In this Contract, "nominated Subcontractor" means a Subcontractor: a)

Who is nominated by the Procuring Entity, or

b) Contractor has nominated as a Subcontractor subject to Sub-Clause 5.2 [Objection to Notification].

# **5.2** Objection to Nomination

The Contractor shall not be under any obligation to employ a nominated Subcontractor against whom the Contractor raises reasonable objection by notice to the Procuring Entity as soon as practicable, with supporting particulars. An objection shall be deemed reasonable if it arises from (among other things) any of the following matters, unless the Procuring Entity agrees in writing to indemnify the Contractor against and from the consequences of the matter:

- a) there are reasons to believe that the Subcontractor does not have sufficient competence, resources or financial strength;
- b) the nominated Subcontractor does not accept to indemnify the Contractor against and from any negligence or misuse of Goods by the nominated Subcontractor, his agents and employees; or
- c) the nominated Subcontractor does not accept to enter into a subcontract which specifies that, for the subcontracted work (including design, if any), the nominated Subcontractor shall:
  - i) undertake to the Contractor such obligations and liabilities as will enable the Contractor to discharge hisobligations and liabilities under the Contract;
  - ii) indemnify the Contractor against and from all obligations and liabilities arising under or in connection with the Contract and from the consequences of any failure by the Subcontractor to perform these obligations or to fulfil these liabilities, and
  - iii) be paid only if and when the Contractor has received from the Procuring Entity payments for sums due under the Subcontract referred to under Sub-Clause 5.3 [Payment to nominated Subcontractors].

#### **5.3** Payments to nominated Subcontractors

The Contractor shall pay to the nominated Subcontractor the amounts shown on the nominated Subcontractor's invoices approved by the Contractor which the Architect certifies to be due in accordance with the subcontract. These amounts plus other charges shall be included in the Contract Price in accordance with sub-paragraph (b) of Sub-Clause 13.5 [Provisional Sums], except as stated in Sub-Clause 5.4 [Evidence of Payments].

#### **5.4** Evidence of Payments

- 5.4.1 Before issuing a Payment Certificate which includes an amount payable to a nominated Subcontractor, the Architect may request the Contractor to supply reasonable evidence that the nominated Subcontractor has received all amounts due in accordance with previous Payment Certificates, less applicable deductions for retention or otherwise. Unless the Contractor:
  - (a) Submits this reasonable evidence to the Engineer, or
  - (b) i) Satisfies the Architect in writing that the Contractor is reasonably entitled to withhold or refuse to pay these amounts, and
  - ii) Submits to the Architect reasonable evidence that the nominated Subcontractor has been notified of the Contractor's entitlement, then the Procuring Entity may (at his sole discretion) pay, directto

the nominated Subcontractor, part or all of such amounts previously certified (less applicable deductions) as are due to the nominated Subcontractor and for which the Contractor has failed to submit the evidence described in sub-paragraphs (a) or (b) above. The Contractor shall then repay, to the Procuring Entity, the amount which the nominated Subcontractor was directly paid by the Procuring Entity.

#### 6. STAFF AND LABOR

### 6.1 Engagement of Staff and Labor

Except as otherwise stated in the Specification, the Contractor shall make arrangements for the engagement of all staff and labor, local or otherwise, and for their payment, feeding, transport, and, when appropriate, housing. The Contractor is encouraged, to the extent practicable and reasonable, to employ staff and labor with appropriate qualifications and experience from sources within Kenya.

### 6.2 Rates of Wages and Conditions of Labor

6.2.1 The Contractor shall pay rates of wages, and observe conditions of labor, which are not lower than those established for the trade or industry where the work is carried out. If no established rates or conditions are applicable, the Contractor shall pay rates of wages and observe conditions which are not lower than the general level of wages and conditions observed locally by Procuring Entity's whose trade or industry is similar

to that of the Contractor.

6.2.2 The Contractor shall inform the Contractor's Personnel about their liability to pay personal income taxes in Kenya in respect of such of their salaries, wages, allowances and any benefits as are subject to tax under the Laws of Kenya for the time being in force, and the Contractor shall perform such duties in regard to such deductions there of as may be imposed on him by such Laws.

### 6.3 Persons in the Service of Procuring Entity

The Contractor shall not recruit, or attempt to recruit, staff and labour from amongst the Procuring Entity's Personnel.

#### 6.4 Lab or Laws

The Contractor shall comply with all the relevant labour Laws applicable to the Contractor's Personnel, including Laws relating to their employment, employment of children, health, safety, welfare, immigration and emigration, and shall allow them all their legal rights. The Contractor shall require his employees to obey all applicable Laws, including those concerning safety at work.

### 6.5 Working Hours

Nowork shall be carried out on the Site on locally recognized days of rest, or outside the normal working hours stated in the **Special Conditions of Contract**, unless: a) Otherwise stated in the Contract,

- b) The Architect gives consent, or
- c) The work is unavoidable, or necessary for the protection of life or property or for the safety of the Works, in which case the Contractor shall immediately advise the Engineer, provided that work done outside the normal working hours shall be considered and paid for as overtime.

#### 6.6 Facilities for Staff and Labor

Except as otherwise stated in the Specification, the Contractor shall provide and maintain all necessary accommodation and welfare facilities on site for the Contractor's Personnel. The Contractor shall also provide facilities for the Procuring Entity's Personnel as stated in the Specifications. The Contractor shall not permit any of the Contractor's Personnel to maintain any temporary or permanent living quarters within the structures forming part of the Permanent Works.

# 6.7 Health and Safety

- 6.7.1 The Contractor shall at all times take all reasonable precautions to maintain the health and safety of the Contractor's Personnel. In collaboration with loca lhealth authorities, the Contractor shall ensure that medical staff, first aid facilities, sick bay and ambulance service are available at all times at the Site and at any accommodation for Contractor's and Procuring Entity's Personnel, and that suitable arrangements are made for all necessary welfare and hygiene requirements and for the prevention of epidemics.
- 6.7.2 The Contractor shall appoint an accident prevention officer at the Site, responsible for maintaining safety and protection against accidents. This person shall be qualified for this responsibility and shall have the authority to issue instructions and take protective measures to prevent accidents. Throughout the execution of the Works, the Contractor shall provide what ever is required by this person to exercise this responsibility and authority.
- 6.7.3 The Contractor shall send, to the Engineer, details of any accident as soon as practicable after itsoccurrence. The Contractor shall maintain records and make reports concerning health, safety and welfare of persons, and damage to property, as the Architect may reasonably require.
- 6.7.4 The Contractor shall conduct an awareness programme on HIV and other sexually transmitted diseases via an approved service provider and shall undertake such other measures taken to reduce the risk of the transfer of these diseases between and among the Contractor's Personnel and the local community, to promote early diagnosis and to assist affected individuals.

# 6.8 Contractor's Superintendence

- 6.8.1 Throughout the execution of the Works, and as long thereafter as is necessary to fulfil the Contractor's obligations, the Contractor shall provide all necessary super intendence to plan, arrange, direct, manage, inspect and test the work.
- 6.8.2 Superintendence shall be given by a sufficient number of persons having adequate knowledge of the language for communications (defined in Sub-Clause 1.4 [Law and Language]) and of the operations to be carried out (including the methods and techniques required, the hazards likely to be encountered and methods of preventing accidents), for the satisfactory and safe execution of the Works.

### 6.9 Contractor's Personnel

- 6.9.1 The Contractor's Personnel shall be appropriately qualified, skilled and experienced in their respective trades or occupations. The Contractors Key personnel shall be named in the Special Conditions of Contract. The Architect may require the Contractor to remove (or cause to be removed) any person employed on the Site or Works, including the Contractor's Representative if applicable, who: a) Persists in any misconduct or lack of care,
- b) Carries out duties in competently or negligently,
- c) fails to conform with any provisions of the Contract,
- d) persists in any conduct which is prejudicial to safety, health, or the protection of the environment, or
- e) based on reasonable evidence, is determined to have engaged in Fraud and Corruption during the execution ofthe Works.
- 6.9.2 If appropriate, the Contractor shall then appoint (or cause to be appointed) a suitable replacement person.

# 6.10 Records of Contractor's Personnel and Equipment

The Contractor shall submit, to the Engineer, details showing the number of each class of Contractor's Personnel and of each type of Contractor's Equipment on the Site. Details shall be submitted each calendar month, in a form approved by the Engineer, until the Contractor has completed all work which is known to be outstanding at the completion date stated in the Taking-Over Certificate for the Works.

### 6.11 Disorderly Conduct

The Contractor shall at all times take all reasonable precautions to prevent any unlawful, riotous or disorderly conduct by or amongst the Contractor's Personnel, and to preserve peace and protection of persons and property on and near the Site.

### **6.12** Foreign Personnel

- 6.12.1 The Contractor shall not employ foreign personnel unless the contractor demonstrates that there are no Kenyans with the required skills.
- 6.12.2 The Contractor shall be responsible for the return of any foreign personnel to the place where they were recruited or to their domicile. In the event of the death in Kenya of any of these personnel or members of their families, the Contractor shall similarly be responsible for making the appropriate arrangements for their return or burial.

### 6.13 Supply of Water

The Contractor shall, having regard to local conditions, provide on the Sitea n adequate supply of drinking and other water for the use of the Contractor's Personnel.

### 6.14 Measures against Insect and Pest Nuisance

The Contractor shall a tall times take the necessary precautions to protect the Contractor's Personnel employed on the Site from insect and pest nuisance, and to reduce the danger to their health. The Contractor shall comply with all the regulations of the local health authorities, including use of appropriate insecticide.

### 6.15 Alcoholic Liquor or Drugs

The Contractor shall not, otherwise than in accordance with the Laws of Kenya, onsite, import, sell, give, barter or otherwise dispose of any alcoholic liquor or drugs, or permit or allow importation, sale, gift, barter or disposal there of by Contractor's Personnel.

### 6.16 Prohibition of Forced or Compulsory Labour

The Contractor shall not employ forced labor, which consists of any work or service, not voluntarily performed, that is exacted from an individual under threat of force or penalty, and includes any kind of involuntary or compulsory labor, such as indentured labor, bonded labor or similar labor-contracting arrangements.

#### 6.17 Prohibition of Harmful Child Labor

The Contractor shall not employ children in a manner that is economically exploitative, or is likely to be hazardous, or to interfere with, the child's education, or to be harmful to the child's health or physical, mental, spiritual, moral, or social development. Where the relevant labour laws of Kenya have provisions for employment of minors, the Contractor shall follow those laws applicable to the Contractor. Children below the age of 18 years shall not be employed in dangerous work.

# **6.18** Employment Records of Workers

The Contractor shall keep complete and accurate records of the employment of labour at the Site. The records shall include the names, ages, genders, hours worked and wages paid to all workers. These records shall be summarized on a monthly basis and submitted to the Engineer. These records shall be included in the details to be submitted by the Contractor under Sub-Clause 6.10 [Records of Contractor's Personnel and Equipment].

### 6.19 Workers' Organizations

The Contractor shall comply with the relevant labor laws that recognize workers' rights to form and to join workers' organizations of their choosing without interference.

### 6.20 Non-Discrimination and Equal Opportunity

The Contractor shall base the labour employment on the principle of equal opportunity and fair treatment and shall not discriminate with respect to aspects of the employment relationship, including recruitment and hiring, compensation (including wages and benefits), working conditions and terms of employment, access to training, promotion, termination of employ mentor retirement, and discipline.

### 7. PLANT, MATERIALS AND WORKMANSHIP

#### 7.1 Manner of Execution

The Contractor shall carry out the manufacture/assemble of plant, the production and manufacture of Materials, and all other execution of the Works:

- a) In the manner (if any) specified in the Contract,
- b) in a proper workman like and careful manner, in accordance with recognized good practice, and
- c) with properly equipped facilities and non-hazardous Materials, except as otherwise specified in the Contract.

# 7.2 Samples

The Contractor shall submit the following samples of Materials, and relevant information, to the Architect for consent prior to using the Material sin or for the Works:

- a) manufacturer's standard samples of Materials and samples specified in the Contract, all at the Contractor's cost, and
- b) additional samples instructed by the Architect as a Variation.

Each sample shall be labeled as to origin and intended use in the Works. 7.3

### **Inspection**

- 7.3.1 The Procuring Entity's Personnel shall at all reasonable times:
  - a) Have full access to all parts of the Site and to all places from which natural Materials are being obtained, and
  - b) during production, manufacture and construction (at the Site and elsewhere), be entitled to examine, inspect, measure and test the materials and workmanship, and to check the progress of manufacture of Plant and production and manufacture of Materials.
  - 7.3.2 The Contractor shall give the Procuring Entity's Personnel full opportunity to carry out these activities, including providing access, facilities, permissions and safety equipment. No such activity shall relieve the Contractor from any obligation or responsibility.
  - 7.3.3 The Contractor shall give notice to the Architect whenever any work is ready and before it is covered up, put out of sight, or packaged for storage or transport. The Architect shall then either carry out the examination, inspection, measurement or testing without unreasonable delay, or promptly give notice to the Contractor that the Architect does not require to do so. If the Contractor fails to give the notice, he shall, if and when required by the Engineer, uncover the work and there after reinstate and make good, all at the Contractor's cost.

## 7.4 Testing

- 7.2.1 This Sub-Clause shall apply to all tests specified in the Contract.
- 7.2.2 Except as otherwise specified in the Contract, the Contractor shall provide all apparatus, assistance, documents and other information, electricity, equipment, fuel, consumables, instruments, labor, materials, and suitably qualified and experienced staff, as are necessary to carry out the specified tests efficiently. The Contractor shall agree, with the Engineer, the time and placef ort he specified testing of any Plant, Materials and other parts of the Works.

- 7.2.3 The Architect may, under Clause 13 [Variations and Adjustments], vary the location or details of specified tests, or instruct the Contractor to carry out additional tests. If these varied or additional tests show that the tested Plant, Materials or workmanship is not in accordance with the Contract, the cost of carrying out this Variation shall be borne by the Contractor, not withstanding other provisions of the Contract.
- 7.2.4 The Architect shall give the Contractor not less than 24 hours' notice of the Architect intention to attend the tests. If the Architect does not attend at the time and place agreed, the Contractor may proceed with the tests, unless otherwise instructed by the Engineer, and the tests shall then be deemed to have been made in the Architect presence.
- 7.2.5 If the Contractor suffers delay and/ or incurs Cost from complying with these instructions or as a result of a delay for which the Procuring Entity is responsible, the Contractor shall give notice to the Architect and shall be entitled subject to Sub-Clause 20.1 [Contractor's Claims] to:
  - (a) an extension of time for any such delay, if completion is or will be delayed, under Sub-Clause 8.4

[Extension of Time for Completion], and

- (b) payment of any such Cost-plus profit, which shall be included in the Contract Price.
- 7.2.6 After receiving this notice, the Architect shall proceed in accordance with Sub-Clause 3.5 [Determinations] to agree or determine these matters.
- 7.2.7 The Contractor shall promptly forward to the Architect duly certified reports of the tests. When thespecified tests have be enpassed, the Architect shall endorse the Contractor's test certificate, or issue a certificate to him, to that effect. If the Architect has not attended the tests, he shall be deemed to have accepted the readings as accurate.

### 7.5 Rejection

- 7.5.1 If, as a result of an examination, inspection, measurement or testing, any Plant, Materials or workmanship is found to be defective or otherwise not in accordance with the Contract, the Architect may reject the Plant, Materials or workmanship by giving notice to the Contractor, with reasons. The Contractor shall then promptly make good the defect and ensure that the rejected item complies with the Contract.
- 7.5.2 If the Architect requires this Plant, Materials or workmanship to be retested, the tests shall be repeated under the same terms and conditions. If the rejection and retesting cause the Procuring Entity to incur additional costs, the Contractor shall subject to Sub-Clause 2.5 [Procuring Entity's Claims] pay these costs to the Procuring Entity.

#### 7.6 Remedial Work

- 7.6.1 Not withstanding any previous test or certification, the Architect may instruct the Contractorto:
  - (a) Remove from the Site and replace any Plant or Materials which is not in accordance with the Contract,
  - (b) remove and re-execute any other work which is not in accordance with the Contract, and
  - (c) execute any work which is urgently required for the safety of the Works, whether because of an accident, unforeseen able event or otherwise.
  - 7.6.2 The Contractor shall comply with the instruction within a reasonable time, which shall be the time (if any) specified in the instruction, or immediately if urgency is specified under sub-paragraph (c).
  - 7.6.3 If the Contractor fails to comply with the instruction, the Procuring Entity shall be entitled to employ and pay other persons to carry out the work. Except to the extent that the Contractor would have been entitled to payment for the work, the Contractor shall subject to Sub-Clause 2.5 [Procuring Entity's Claims] pay to the Procuring Entity all costs arising from this failure.
  - 7.6.4 If the contractor repeatedly delivers defective work, the Procuring Entity may consider termination in accordance with Clause 15.

# 7.7 Ownership of Plant and Materials

Except as otherwise provided in the Contract, each item of Plant and Materials shall become the property of the Procuring Entity at whichever is the earlier of the following times, free from liens and other encumbrances: a)

When it is in corporated in the Works;

b) when the Contractor is paid the corresponding value of the Plant and Materials under Sub-Clause 8.10 [Payment for Plant and Materials in Event of Suspension].

### 7.8 Royalties

Unless otherwise stated in the Specification, the Contractor shall pay all royalties, rents and other payments for: a) Natural materials obtained from outside the Site, and

b) the disposal of material from demolitions and excavations and of other surplus material (whether natural orman-made), except to the extent that disposal are as within the Site are specified in the Contract.

### 8. COMMENCEMENT, DELAYS AND SUSPENSION

#### 8.1 Commencement of Works

- 8.1.1 Except as otherwise specified in the Special Conditions of Contract, the Commencement Date shall be the date at which the following precedent condition shave all been fulfilled and the Architect notification recording the agreement of both Parties on such fulfilment and instructing to commence the Work is received by the Contractor:
  - (a) Signature of the Contract Agreement by both Parties, and if required, approval of the Contract by relevant authorities of Kenya;
  - (b) except if otherwise specified in the Special Conditions of Contract, effective access to and possession of the Site given to the Contractor together with such permission(s) under (a) of Sub-Clause 1.13 [Compliance with Laws] as required for the commencement of the Works.
  - (c) Receipt by the Contractor of the Advance Payment under Sub-Clause 14.2 [Advance Payment] provided that the corresponding bank guarantee has been delivered by the Contractor.
- 8.1.2 If the said Architect instruction is not received by the Contractor within 180 days from his receipt of the Letter of Acceptance, the Contractor shall be entitled to terminate the Contract under Sub-Clause 1 6.2 [Termination Contractor].
- 8.1.3 The Contractor shall commence the execution of the Works as soon as is reasonably practicable after the Commencement Date and shal lthen proceed with the Works with due expedition and without delay.

#### **8.2** Time for Completion

The Contractor shall complete the whole of the Works, and each Section (if any), within the Time for Completion for the Works or Section (as the case may be), including: a) Achieving the passing of the Testson Completion, and

b) completing all work which is stated in the Contract as being required for the Works or Section to be considered to be completed for the purposes of taking-over under Sub-Clause 10.1 [Taking Over of the Works and Sections].

### 8.3 Programme

- 8.3.1 The Contractor shall submit a detailed time programme to the Architect within 1 4 days after receiving the notice under Sub-Clause 8.1 [Commencement of Works]. The Contractor shall also submit a revised programme whenever the previous programme is inconsistent with actual progress or with the Contractor's obligations. Each programme shall include:
  - (a) The order in which the Contractor intends to carry out the Works, including the anticipated timing of each stage of design (if any), Contractor's Documents, procurement, manufacture of Plant, delivery to Site, construction, erection and testing,

- (b) each of these stages for work by each nominated Subcontractor (as defined in Clause 5 [Nominated Subcontractors]),
- (c) the sequence and timing of inspections and tests specified in the Contract, and
- (d) a supporting report which includes:
- i) a general description of the methods which the Contractor intends to adopt, and of the major stages, in the execution of the Works, and
- ii) details showing the Contractor's reasonable estimate of the number of each class of Contractor's

Personnel and of each type of Contractor's Equipment, required on the Site for each major stage.

- 8.3.2 Unless the Engineer, within 14 days after receiving a programme, gives notice to the Contractor stating the extent to which it does not comply with the Contract, the Contractor shall proceed in accordance with the programme, subject to his other obligations under the Contract. The Procuring Entity's Personnel shall be entitled to rely upon the programme when planning their activities.
- 8.3.3 The Contractor shall promptly give notice to the Architect of specific probable future events or circumstances which may adversely affect the work, increase the Contract Price or delay the execution of the Works.
- 8.3.4 If, at anytime, the Architect gives notice to the Contractor that a programme fails (to the extent stated) to comply with the Contractor to be consistent with actual progress and the Contractor's stated intentions, the Contractor shall submit a revised programme to the Architect in accordance with this Sub-Clause.

# **8.4** Extension of Time for Completion

- 8.4.1 The Contractor shall be entitled subject to Sub-Clause 20.1 [Contractor's Claims] to an extension of the Time for Completion if and to the extent that completion for the purposes of Sub-Clause 10.1 [Taking Over of the Works and Sections] is or will be delayed by any of the following causes:
  - a) a Variation (unless an adjustment to the Time for Completion has been agreed under Sub-Clause 13.3 [Variation Procedure]) or other substantial change in the quantity of an item of work included in the Contract,
  - b) a cause of delay giving an entitlement to extension of time under a Sub-Clause of these Conditions, c) exceptionally adverse climatic conditions,
  - d) Unforeseeable shortages in the availability of personnel or Goods caused by epidemic or governmental actions, or
  - e) any delay, impediment or prevention caused by or attributable to the Procuring Entity, the Procuring Entity's Personnel, or the Procuring Entity's other contractors.
- 8.4.2 If the Contractor considers itself to be entitled to an extension of the Time for Completion, the Contractor shall give notice to the Architect in accordance with Sub-Clause 20.1 [Contractor's Claims]. When determining each extension of time under Sub-Clause 20.1, the Architect shall review previous determinations and may increase, but shall not decrease, the total extension of time.

# 8.5 Delays Caused by Authorities

If the following conditions apply, namely:

- a) The Contractor has diligently followed the procedures laid down by the relevant legally constituted public authorities in Kenya,
- b) These authorities delay or disrupt the Contractor's work, and
- c) the delay or disruption was Unforeseeable, then this delay or disruption will be considered as a cause of delay under sub-paragraph (b) of Sub-Clause 8.4 [Extension of Time for Completion].

### 8.6 Rate of Progress

- 8.6.1 If, at anytime:
  - a) Actual progress is too slow to complete within the Time for Completion, and/or
  - b) Progress has fallen (or will fall) behind the current programme under Sub-Clause 8.3 [Programme], other than as a result of a cause listed in Sub-Clause 8.4 [Extension of Time for Completion], then the Architect may instruct the Contractor to submit, under Sub-Clause 8.3 [Programme], a revised programme and supporting report describing the revised methods which the Contractor proposes to adopt in order to expedite progress and complete within the Time for Completion.
  - 8.6.2 Unless the Architect notifies otherwise, the Contractor shall adopt these revised methods, which mayrequire increases in the working hours and/or in the numbers of Contractor's Personnel and/or Goods, at the risk and cost of the Contractor. If these revised methods cause the Procuring Entity to incur additional costs, the Contractor shall subject to notice under Sub-Clause 2.5 [Procuring Entity's Claims] pay these costs to the Procuring Entity, in addition to delay damages (if any) under Sub-Clause 8.7 below.
  - 8.6.3 Additional costs of revised methods including acceleration measures, instructed by the Architect to reduce delays resulting from causes listed under Sub-Clause 8.4 [Extension of Time for Completion] shall be paid by the Procuring Entity, without generating, however, any other additional payment benefit to the Contractor.

# 8.7 Delay Damages

- 8.7.1 If the Contractor fails to comply with Sub-Clause 8.2 [Time for Completion], the Contractor shall subject to notice under Sub-Clause 2.5 [Procuring Entity's Claims] pay delay damages to the Procuring Entity for this default. These delay damages shall be the sum stated in the **Special Conditions of Contract**, which shall be paid for everyday which shall elapse between the relevant Time for Completion and the date stated in the taking-Over Certificate. However, the total amount due under this Sub-Clause shall not exceed the maximum amount of delay damages (if any) stated in the Special Conditions of Contract.
- 8.7.2 These delay damages shall be the only damages due from the Contractor for such default, other than in the event of termination under Sub-Clause 15.2 [Termination by Procuring Entity] prior to completion of the Works. These damages shall not relieve the Contractor from his obligation to complete the Works, or from any other duties, obligations or responsibilities which he may have under the Contract.

#### 8.8 Suspension of Work

- 8.8.1 The Architect may at anytime instruct the Contractor to suspend progress of part or all of the Works. During such suspension, the Contractor shall protect, store and secure such part or the Works a gainst any deterioration, loss or damage.
- 8.8.2 The Architect may also notify the cause for the suspension. If and to the extent that the cause is notified and is the responsibility of the Contractor, the following Sub-Clauses 8.9, 8.10 and 8.11 shall not apply.

#### 8.9 Consequences of Suspension

- 8.9.1 If the Contractor suffers delay and/or incurs Cost from complying with the Architect instructions under Sub-Clause 8.8 [Suspension of Work] and/or from resuming the work, the Contractor shall give notice to the Architect and shall be entitled subject to Sub-Clause 20.1 [Contractor's Claims] to:
  - a) an extension of time for any such delay, if completion is or will be delayed, under Sub-Clause 8.4 [Extension of Time for Completion], and
  - b) Payment of any such Cost, which shall be included in the Contract Price.
- 8.9.2 After receiving this notice, the Architect shall proceed in accordance with Sub-Clause3.5 [Determinations] to agree or determine these matters.
- 8.9.3 The Contractor shall not be entitled to an extension of time for, or to payment of the Cost incurred in, making good the consequences of the Contractor's faulty design, workmanship or materials, or of the Contractor's failure to protect, store or secure in accordance with Sub-Clause 8.8 [Suspension of Work].

#### 8.10 Payment for Plant and Materials in Event of Suspension

The Contractor shall be entitled to payment of the value (as at the date of suspension) of Plant and/ or Materials which have not been delivered to Site, if:

- a) The work on Plant or delivery of Plant and/ or Materials has been suspended for more than 30 days, and
- b) the Contractor has marked the Plant and/or Materials as the Procuring Entity's property in accordance with the Architect instructions.

### 8.11 ProlongedSuspension

If the suspension under Sub-Clause 8.8 [Suspension of Work] has continued for more than 84 days, the Contractor may request the Architect permission to proceed. If the Architect does not give permission within 30 days after being requested to do so, the Contractor may, by giving notice to the Engineer, treat the suspension as an omission under Clause 13 [Variations and Adjustments] of the affected part of the Works. If the suspension affects the whole of the Works, the Contractor may give notice of termination under SubClause 16.2 [Termination by Contractor].

### 8.12 Resumption of Work

After the permission or instruction to proceed is given, the Contractor and the Architect shall jointly examine the Works and the Plant and Materials affected by the suspension. The Contractor shall make good any deterioration or defect in or loss of the Works or Plant or Materials, which has occurred during the suspension after receiving from the Architect an instruction to this effect under Clause 13 [Variations and Adjustments].

#### 9. TESTS ON COMPLETION

# 9.1 Contractor's Obligations

- 9.1.1 The Contractor shall carry out the Tests on Completion in accordance with this Clause and Sub-Clause 7.4 [Testing], after providing the documents in accordance with sub-paragraph (d) of Sub-Clause 4.1 [Contractor's General Obligations].
- 9.1.2 The Contractor shall give to the Architect not less than 21 days' notice of the date after which the Contractor will be ready to carry out each of the Tests on Completion. Unless otherwise agreed, Tests on Completion shall be carried out within 14 days after this date, on such day or days as the Architect shall instruct.
- 9.1.3 In considering the results of the Tests on Completion, the Architect shall make allowances for the effect of any use of the Works by the Procuring Entity on the performance or other characteristics of the Works. As soon as the Works, or a Section, have passed any Tests on Completion, the Contractor shall submit a certified report of the resultsof these Tests to the Engineer.

# 9.2 Delayed Tests

- 9.2.1 If the Tests on Completion are being unduly delayed by the Procuring Entity, Sub-Clause 7.4 [Testing] (fifth paragraph) and/ or Sub-Clause 10.3 [Interference with Tests on Completion] shall be applicable.
- 9.2.2 If the Tests on Completion are being unduly delayed by the Contractor, the Architect may by notice require the Contractor to carry out the Tests within 21 days after receiving the notice. The Contractor shall carry out the Testson such day or days within that period as the Contractor may fix and of which he shall give notice to the Engineer.
- 9.2.3 If the Contractor fails to carryout the Tests on Completion within the period of 21 days, the Procuring Entity's Personnel may proceed with the Test sat the risk and cost of the Contractor. The Tests on Completion shall then be deemed to have been carried out in the presence of the Contractor and the results of the Tests shall be accepted asaccurate.

#### 9.3 Retesting of related works

If the Works, or a Section, fail to pass the Tests on Completion, Sub-Clause 7.5 [Rejection] shall apply, and the Architect or the Contractor may require the failed Tests, and Tests on Completion on any related work, to be repeated under the same terms and conditions.

# **9.4** Failure to Pass Tests on Completion

- 9.4.1 If the Works, or a Section, fail to pass the Tests on Completion repeated under Sub-Clause 9.3 [Retesting], the Architect shall be entitled to:
  - a) Order further repetition of Tests on Completion under Sub-Clause 9.3; or
  - b) if the failure deprives the Procuring Entity of substantially the whole benefit of the Works or Section, reject the Works or Section (as the case may be), in which event the Procuring Entity shall have the same remedies as are provided in sub-paragraph (c) of Sub-Clause 1 1.4 [Failure to Remedy Defects].

# 10. PROCURING ENTITY'S TAKING OVER

# **10.1** Taking Over of the Works and Sections

- 10.1.1 Except as stated in Sub-Clause 9.4 [Failure to Pass Tests on Completion], the Works shall be taken over by the Procuring Entity when (i) the Works have been completed in accordance with the Contract, including the matters described in Sub-Clause 8.2 [Time for Completion] and except as allowed in sub-paragraph (a) below, and (ii) a Taking-Over Certificate for the Works has been issued, or is deemed to have been issued in accordance with this Sub-Clause.
- 10.1.2 The Contractor may apply by notice to the Architect for a Taking-Over Certificate not earlier than 14 days before the Works will, in the Contractor's opinion, be complete and ready for taking over. If the Works are divided into Sections, the Contract or may similarly apply for a Taking-Over Certificate for each Section.
- 10.1.3 The Architect shall, within 30 days after receiving the Contractor's application:
  - a) Issue the Taking-Over Certificate to the Contract or, stating the date on which the Works or Section were completed in accordance with the Contract, except for any minor out standing work and defects which will not substantially affect the use of the Works or Section for their intended purpose (either until or whilst this work is completed and these defects are remedied); or
  - b) reject the application, giving reasons and specifying the work required to be done by the Contractor to enable the Taking-Over Certificate to be issued. The Contractor shall then complete this work before issuing a further notice undert his Sub-Clause.
- 10.1.4 If the Architect fails either to issue the Taking-Over Certificate or to reject the Contractor's application within the period of 30 days, and if the Works or Section (as the case may be) are substantially in accordance with the Contract, the Taking-Over Certificate shall be deemed to have been issued on thel ast day of that period.

#### **10.2** Taking Over of Parts of the Works

- 10.2.1 The Architect may, at the sole discretion of the Procuring Entity, issue a Taking-Over Certificate for any part of the Permanent Works.
- 10.2.2 The Procuring Entity shall not use any part of the Works (other than as a temporary measure which is either specified in the Contract or agreed by both Parties) unless and until the Architect has issued a Taking-Over Certificate for this part. However, if the Procuring Entity does use any part of the Works before the Taking-

# Over Certificate is issued:

- a) The part which is used shall be deemed to have been taken over as from the date on which it is used,
- b) the Contractor shall cease to be liable for the care of such part as from this date, when responsibility shall pass to the Procuring Entity, and

- c) if requested by the Contractor, the Architect shall issue a Taking-Over Certificate for this part.
- 10.2.3 After the Architect has issued a Taking-Over Certificate for a part of the Works, the Contractor shall be given the earliest opportunity to take such steps as may be necessary to carry out any outstanding Tests on Completion. The Contractor shall carry out these Tests on Completion as soon as practicable before the expiry date of the relevant Defects Notification Period.
- 10.2.4 If the Contractor incurs Cost as a result of the Procuring Entity taking over and/or using a part of the Works, other than such use as is specified in the Contractor agreed by the Contractor, the Contractor shall (i) give notice to the Architect and (ii) be entitled subject to Sub-Clause 20.1 [Contractor's Claims] to payment of any such accrued costs, which shall be included in the Contract Price. After receiving this notice, the Architect shall proceed in accordance with Sub-Clause 3.5 [Determinations] to agree or determine this accrued cost.
- 10.2.5 If a Taking-Over Certificate has been issued for a part of the Works (other than a Section), the delay damages there after for completion of the remainder of the Works shall be reduced. Similarly, the delay damages for the remainder of the Section (if any) in which this part is included shall also be reduced. For any period of delay after the date stated in this Taking-Over Certificate, the proportional reduction in these delay damages shall be calculated as the proportion which the value of the part so certified bears to the value of the Works or Section (as the case may be) as a whole. The Architect shall proceed in accordance with Sub-Clause 3.5

[Determinations] to agree or determine these proportions. The provisions of this paragraph shall only apply

to the daily rate of delay damages under Sub-Clause 8.7 [Delay Damages] and shall not affect the maximum amount of these damages.

### 10.3 Interference with Tests on Completion

- 10.3.1 If the Contractor is prevented, for more than 14 days, from carrying out the Tests on Completion by a cause for which the Procuring Entity is responsible, the Procuring Entity shall be deemed to have taken over the Works or Section (as the case may be) on the date when the Tests on Completion would otherwise have been completed.
- 10.3.2 The Architect shall then issue a Taking-Over Certificate accordingly, and the Contractor shall carry out the Tests on Completion as soon as practicable, before the expiry date of the Defects Notification Period. The Architect shall require the Tests on Completion to be carried out by giving 14 days' notice and in accordance with the relevant provisions of the Contract.
- 10.3.3 If the Contractor suffers delay and/or incurs Cost as a result of this delay in carrying out the Tests on Completion, the Contractor shall give notice to the Architect and shall be entitled subject to Sub-Clause 20.1 [Contractor's Claims] to:
- a) an extension of time for any such delay, if completion is or will be delayed, under Sub-Clause 8.4 [Extension of Time for Completion], and
- b) payment of any such accrued costs, which shall be included in the Contract Price.
- 10.3.4 After receiving this notice, the Architect shall proceed in accordance with Sub-Clause 3.5 [Determinations] to agree or determine these matters.

#### **10.4** Surfaces Requiring Reinstatement

Except as otherwise stated in a Taking-Over Certificate, a certificate for a Section or part of the Works shall not be deemed to certify completion of any ground or other surfaces requiring reinstatement.

#### 11. DEFECTS LIABILITY

#### 11.1 Completion of Outstanding Work and Remedying Defects

- 11.1.1 In order that the Works and Contractor's Documents, and each Section, shall be in the condition required by the Contract (fairwear and tear excepted) by the expiry date of the relevant Defects Notification Period or as soon as practicable there after, the Contractor shall:
- a) complete any work which is outstanding on the date stated in a Taking-Over Certificate, within such reasonable time as is instructed by the Engineer, and
- b) execute all work required to remedy defects or damage, as may be notified by (or on behalf of) the Procuring Entity on or before the expiry date of the Defects Notification Period for the Works or Section (as the case may be).
- 11.1.2 If a defect appears or damage occurs, the Contractor shall be notified accordingly by the Engineer.

### 11.2 Cost of Remedying Defects

- 11.2.1 All work referred to in sub-paragraph (b) of Sub-Clause 11.1 [Completion of Outstanding Work and Remedying Defects] shall be executed at the risk and cost of the Contractor, if and to the extent that the work is attributable to:
- a) Any design for which the Contractor is responsible,
- b) Plant, Materials or workmanship not being in accordance with the Contract, or
- c) Failure by the Contractor to comply with any other obligation.
- 11.2.2 If and to the extent that such work is attributable to any other cause, the Contractor shall be notified promptly by (or on behalf of) the Procuring Entity, and Sub-Clause 13.3 [Variation Procedure] shall apply.

# 11.3 Extension of Defects Notification Period

11.3.1 The Procuring Entity shall be entitled subject to Sub-Clause 2.5 [Procuring Entity's Claims] to an extension of the Defects Notification Period for the Works or a Section if and to the extent that the Works, Section or a major item of Plant (as the case may be, and after taking over) cannot be used for the purposes for which they

are intended by reason of a defect or by reason of damage attributable to the Contractor. However, a Defects Notification Period shall not be extended by more than two years.

11.3.2 If delivery and/ or erection of Plant and/ or Materials was suspended under Sub-Clause 8.8 [Suspension of

Work] or Sub-Clause 16.1 [Contractor's Entitlement to Suspend Work], the Contractor's obligations under this Clause shall not appl yto any defectsor damage occurring more than two years after the Defects Notification Period for the Plant and/ or Materials would otherwise have expired.

#### 11.4 Failure to Remedy Defects

- 11.4.1 If the Contractor fails to remedy any defect or damage within a reasonable time, a date may be fixed by the Engineer, on or by which the defect or damage is to be remedied. The Contractor shall be given reasonable notice of this date.
- 11.4.2 If the Contractor fails to remedy the defect or damage by this notified date and this remedial work was to be executed at the cost of the Contractor under Sub-Clause 11.2 [Costo f Remedying Defects], the Procuring Entity may (at his option):
  - a) Carry out the work itself or by others, in a reasonable manner and at the Contractor's cost, but the Contractor shall have no responsibility for this work; and the Contractor shall subject to Sub-Clause 2.5 [Procuring Entity's Claims] pay to the Procuring Entity the costs reasonably incurred by the Procuring Entity in remedying the defect or damage;
  - b) Require the Architect to agree or determine a reasonable reduction in the Contract Price in accordance with Sub-Clause 3.5 [Determinations]; or
  - c) if the defect or damage deprives the Procuring Entity of substantially the whole benefit of the Works or any major part of the Works, terminate the Contractas a whole, or in respect of such major part which cannot be put to the intended use. Without prejudice to any other rights,

under the Contractor otherwise, the Procuring Entity shall then be entitled to recover all sums paid for the Works or for such part (as the case may be), plus financing costs and the cost of dismantling the same, clearing the Site and returning Plant and Materials to the Contractor.

#### 11.5 Removal of Defective Work

If the defector damage cannot be remedied expeditiously on the Site and the Procuring Entity gives consent, the Contractor may remove from the Site for the purposes of repair such items of Plant as are defective or damaged. This consent may require the Contractor to increase the amount of the Performance Security by the full replacement cost of these items, or to provide other appropriate security.

#### 11.6 Further Tests

- 11.6.1 If the work of remedying of any defector damage may affect the performance of the Works, the Architect may require the repetition of any of the tests described in the Contract. The requirement shall be made by notice within 14 days after the defect or damage is remedied.
- 11.6.2 These tests shall be carried out in accordance with the terms applicable to the previous tests, except that they shall be carried out at the risk and cost of the Party liable, under Sub-Clause 11.2 [Cost of Remedying Defects], for the cost of the remedial work.

### 11.7 Right of Access

Unti Ithe Completion Certificate has been issued, the Contractor shall have such right of access to the Works as is reasonably required in order to comply with this Clause, except as may be inconsistent with the Procuring Entity's reasonable security restrictions.

#### 11.8 Contractor to Search

The Contractor shall, if required by the Engineer, search for the cause of any defecton parts of the works that have already accepted, under the direction of the Engineer. Unless the defect is to be remedied at the cost of the Contractor under Sub-Clause 11.2 [Cost of Remedying Defects], the Cost of the search plus profit shall be agreed or determined by the Architect in accordance with Sub-Clause 3.5 [Determinations] and shall be included in the Contract Price.

# 11.9 Completion Certificate

11.9.1 Performance of the Contractor's obligations shall not be considered to have been completed until the Architect has issued the Completion Certificate to the Contractor, stating the date on which the Contractor completed

his obligations under the Contract.

- 11.9.2 The Architect shall issue the Completion Certificate within 30days after the latest of the expiry dates of the Defects Liability Period, or as soon there after as the Contractor has supplied all the Contractor's Documents and completed and tested all the Works, including remedying any defects. A copy of the Completionn Certificate shall be issued to the Procuring Entity. 11.9.3 Only the Completion Certificate shall be deemed to constitute acceptance of the Works.
- 11.10 Unfulfilled Obligations After the Completion Certificate has been issued, each Party shall remain liable for the fulfilment of any obligation which remains unperformed at that time. For the purposes of determining the nature and extent of unperformed obligations, the Contract shall be deemed to remain in force.

#### 11.11 Clearance of Site

11.11.1 Upon receiving the Completion Certificate, the Contractor shall remove any remaining Contractor's Equipment, surplus material, wreckage, rubbish and Temporary Works from the Site.

- 11.11.2 If all these items have not been removed within 30 days after receipt by the Contractor of the Completion Certificate, the Procuring Entity may sell or otherwise dispose of any remaining items. The Procuring Entity shall be entitled to be paid the costs incurred in connection with, or attributable to, such sale or disposal and restoring the Site.
- 11.11.3 Any balance of the moneys from the sale shall be paid to the Contractor. If these moneys are less than the Procuring Entity's costs, the Contractor shall pay the outstanding balance to the Procuring Entity.

#### 12. MEASUREMENT AN DEVALUATION

#### 12.1 Works to be Measured

- 12.1.1 The Works shall be measured, and valued for payment, in accordance with this Clause. The Contractorshall show in each application under Sub-Clauses 14.3 [Application for Interim Payment Certificates], 14.10 [Statement on Completion] and 14.11 [Application for Final Payment Certificate] the quantities and other particulars detailing the amounts which he considers to be entitled under the Contract.
- 12.1.2 Whenever the Architect requires any part of the Works to be measured, reasonable notice shall be given to the Contractor's Representative, who shall:
- a) promptly either attend or send another qualified representative to assist the Architect in making the measurement, and
- b) supply any particulars requested by the Engineer.
- 12.1.3 If the Contractor fails to attend or send a representative, the measurement made by the Architect shall be accepted as accurate.
- 12.1.4 Except as otherwise stated in the Contract, wherever any Permanent Works are to be measured from records, these shall be prepared by the Engineer. The Contractor shall, as and when requested, attend to examine and agreet her ecords with the Engineer, and shall sign the same when agreed. If the Contractor does not attend, the records shall be accepted as accurate.
- 12.1.5 If the Contractor examines and disagrees the records, and/ or does not sign them as agreed, then the Contractor shall give notice to the Architect of the respects in which the records are asserted to be inaccurate. After receiving this notice, the Architect shall review the records and either confirm or vary them and certify the paymentofthe undisputed part. If the Contractor does not so give notice to the Architect within 14 days after being requested to examine the records, they shall be accepted as accurate.

# 12.2 Method of Measurement

Except as otherwise stated in the Contract:

- a) Measurement shall be made of the net actual quantity of each item of the Permanent Works, and
- b) the method of measurement shall be in accordance with the Bill of Quantities or other applicable Schedules.

### 12.3 Evaluation

- 12.3.1 Except as otherwise stated in the Contract, the Architect shall proceed in accordance with Sub-Clause 3.5 [Determinations] to agree or determine the value of workd one by evaluating each item of work, applying the measurement agreed or determined in accordance with the above Sub-Clauses 12.1 and 12.2 and the appropriate rate or price for the item.
- 12.3.2 For each item of work, the appropriate rate or price for the item shall be the rate or price specified for such item in the Contractor, if there is no such item, specified for similar work.
- 12.3.3 Any item of work included in the Bill of Quantities for which no rate or price was specified shall be considered as included in other rates and prices in the Bill of Quantities and will not be paid for separately.

- 12.3.4 However, for a new item of work, a new rate or price shall be appropriate for such item of work if:
  - a) The work is instructed under Clause 13 [Variations and Adjustments],
  - b) no rate or price is specified in the Contract for this item, and
  - c) no specified rate or price is appropriate because the item of work is not of similar character, or is not executed under similar conditions, as any item in the Contract.
- 12.3.5 Each new rate or price shall be derived from any relevant rates or prices in the Contract. If no rates or prices are relevant for the new item of work, it shall be derived from the reasonable Cost of executing such work, prevailing market rates, together with profit, taking account of any other relevant matters.
- 12.3.6 Until such time as an appropriate rate or price is agreed or determined, the Architect shall determine a

provisional rate or price for the purposes of Interim Payment Certificates as soon as the concerned work commences.

12.3.7 Where the contract price is different from the corrected tender price, in order to ensure the contractor is not paid less or more relative to the contract price (*which would be the tender price*), payment valuation certificates and variation orders on omissions and additions valued based on rates in the Bill of Quantities or schedule of rates in the Tender, will be adjusted by a <u>plus or minus</u> percentage. The percentage already worked out during tender evaluation is worked out as follows: *(corrected tender price tender price)/ tender price X 100.* 

#### 12.4 Omissions

Whenever the omission of any work forms part (or all) of a Variation, the value of which has not been agreed, if:

- a) The Contractor will incur (or has incurred) cost which, if the work had not been omitted, wouldhavebeen deemed to be covered by a sum forming part of the Accepted Contract Amount;
- b) The omission of the work will result (or has resulted) in this sum not forming part of the Contract Price; and
- c) this cost is not deemed to be included in the evaluation of any substituted work; then the Contractor shall give notice to the Architect accordingly, with supporting particulars. Upon receiving this notice, the Architect shall proceed in accordance with Sub-Clause 3.5 [Determinations] to agree or determine this cost, which shall be included in the Contract Price.

#### 13. VARIATIONS AND ADJUSTMENTS

# 13.1 Right to Vary

- 13.1.1 Variations may be initiated by the Architect at any time prior to issuing the Taking-Over Certificate for the Works, either by an instruction or by a request for the Contractor to submit a proposal. No Variation instructed by the Architect under this Clause shall in any way vitiate or in validate the Contract.
- 13.1.2 The Contractor shall execute and be bound by each Variation, unless the Contractor promptly gives notice to the Architect stating (with supporting particulars) that (i) the Contractor cannot readily obtain the Goods required for the Variation, or (ii) such Variation triggers a substantial change in the sequence or progress of the Works. Upon receiving this notice, the Architect shall cancel, confirm or vary the instruction.
- 13.1.3 Each Variation may include:
  - a) changes to the quantities of any item of work included in the Contract (however, such changes do not necessarily constitute a Variation),
  - b) changes to the quality and otherc haracteristics of any item of work,
  - c) changes to the levels, positions and/ or dimensions of any part of the Works,
  - d) omission of any work unless it is to be carried out by others,
  - e) any additional work, Plant, Materials or services necessary for the Permanent Works, including any associated Tests on Completion, boreholes and other testing and exploratory work, or

- f) changes to the sequence or timing of the execution of the Works.
- 13.1.4 The Contractor shall not make any alteration and/or modification of the Permanent Works, unless and until the Architect instructs after obtaining approval of the Procuring Entity.

#### 13.2 Variation Order Procedure

- 13.2.1 Priortoany Variation Order under Sub-Clause 13.1.4 the Architect shall notify the Contractor of the nature and form of such variation. As soon as possible after having received such notice, the Contractor shall submit to the Engineer:
  - a) A description of work, if any, to be performed and a programme for its execution, and
  - b) the Contractor's proposals for any necessary modifications to the Programme according to Sub-Clause
  - 8.3 or to any of the Contractor's obligations under the Contract, and
    - c) the Contractor's proposals for adjustment to the Contract Price.

Following the receipt of the Contractor's submission the Architect shall, after due consultation with the Employer and the Contractor, decide as soon as possible whether or not the variation shall be carried out. If the Architect decides that the variation shall be carried out, he shall issue a Variation Order clearly identified as such in accordance with the Contractor's submission or as modified by agreement.

If the Architect and the Contractor are unable to agree the adjustment of the Contract Price, the provisions of Sub-Clause 13.2.2 shall apply.

# 13.2.2 Disagreement on Adjustment of the Contract Price

If the Contractor and the Architecture unable to agree on the adjustment of the Contract Price, the adjustment shall be determined in accordance with the rates specified in the Bills of Quantities or Schedule of Daywork Prices. If the rates contained in the Bills of Quantities or Dayworks Prices are not directly applicable to the specific work in question, suitable rates shall be established by the Architect reflecting the level of pricing in the Dayworks Prices. Where rates are not contained in the said Prices, the amount shall be such as is in all the circumstances reasonable, reflecting a market price. Due account shall be taken of any over-or underrecovery of overheads by the Contractor in consequence of the variation. The Contractor shall also be entitled to be paid:

- a) The cost of any partial execution of the Work srendered useless by any such variation,
- b) The cost of making necessary alterations to Plant already manufactured or in the course of manufacture or of any work done that has to be altered in consequence of such a variation,
- c) any additional costs incurred by the Contractor by the disruption of the progress of the Works as detailed in the Programme, and
- d) the net effect of the Contractor's financec osts, including interest, caused by the variation.

The Architect shall on this basis determine the rates or prices to enable on-account payment to be included in certificates of payment.

#### 13.2.3 Contractor to Proceed

On receipt of a Variation Order, the Contractor shall forth with proceed to carry out the variation and be bound to these Conditions in so doing as if such variation was stated in the Contract. The work shall not be delayed pending the granting of an extension of the Time for Completion or an adjustment to the Contract Price under Sub-Clause 31.3.

# 13.3 Value Engineering

- 13.3.1 TheContractor may, at anytime, submit to the Architect written proposal which (in the Contractor's opinion) will, if adopted, (i) accelerate completion, (ii) reduce the cost to the Procuring Entity of executing, maintaining or operating the Works, (iii) improve the efficiency or value to the Procuring Entity of the completed Works, or
- (iv) otherwise be of benefit to the Procuring Entity.

- 13.3.2 The proposal shall be prepared at the cost of the Contractor and shall include the items listed in Sub-Clause 13.3 [Variation Procedure].
- 13.2.3 If a proposal, which is approved by the Engineer, includes a change in the design of part of the Permanent Works, then unless otherwise agreed by both Parties: a) The Contractor shall design this part,
  - b) sub-paragraphs (a) to (d) of Sub-Clause 4.1 [Contractor's General Obligations] shall apply, and
  - c) if this change results in a reduction in the contract value of this part, the Architect shall proceed in accordance with Sub-Clause 3.5 [Determinations] to agree or determine a fee, which shall be included in the Contract Price. This fee shall behalf (50%) of the difference between the following amounts:
    - i) such reduction in contract value, resulting from the change, excluding adjustments under Sub-Clause 13.8 [Adjustments for Changes in Legislation] and Sub-Clause 13.8 [Adjustments for Changes in Cost], and ii) the reduction (if any) in the value to the Procuring Entity of the varied works, taking account of any improvement in quality, anticipated life or operational efficiencies.
- 13.3.4 However, if the amount established in item 13.2.3 (c) (i) is less than amount established in item 13.2.3 (c (ii), there shall not be a fee. However, if the if the amount established in item 13.2.3 (c) (i) is more than amount established in item 13.2.3 (c (ii), it shall result in a price variation to the Procuring Entity.

# 13.4 Variation Procedure for Value Engineering proposal

- 13.4.1 If the Architect requests a proposal, prior to instructing a Variation, the Contractor shall respond in writing a soon as practicable, either by giving reasons why he cannot comply (if this is the case) or by submitting: a) A description of the proposed work to be performed and a programme for its execution,
- b) the Contractor's proposal for any necessary modifications to the programme according to Sub-Clause 8.3 [Programme] and to the Time for Completion, and
- c) the Contractor's proposal for evaluation of the Variation.
- 13.4.2 The Architect shall, as soon as practicable after receiving such proposal (under Sub-Clause 13.2 [Value Project Engineering] or otherwise), respond with approval, disapproval or comments. The Contractor shall not delay any work whilst a waiting a response.
- 13.4.3 Each instruction to execute a Variation, with any requirements for the recording of Costs, shall be issued by the Architect to the Contractor, who shall acknowledge receipt.
- 13.4.4 Each Variation shall be evaluated in accordance with Clause 12 [Measurement and Evaluation], unless the Architect instructs or approves otherwise in accordance with this Clause.

#### 13.5 Paymentin Applicable Currencies

If the Contract provides for payment of the Contract Price in more than one currency, then whenever an adjustment is agreed, approved or determined as stated above, the amount payable in each of the applicable currencies shall be specified. For this purpose, reference shall be made to the actual or expected currency proportions of the Cost of the varied work, and to the proportions of various currencies specified for payment of the Contract Price.

#### 13.6 Provisional Sums

- 13.6.1 Each Provisional Sum shall only be used, in whole or inpart, in accordance with the Architect instructions, and the Contract Price shall be adjusted accordingly. The total sum paid to the Contractor shall include onlysuch amounts, for the work, supplies or services to which the Provisional Sum relates, as the Architect shall have instructed. For each Provisional Sum, the Architect May instruct:
  - a) Work to be executed (including Plant, Materialso r services to be supplied) by the Contractor and valued under Sub-Clause 13.3 [Variation Procedure]; and/or
  - b) Plant, Materials or services to be purchased by the Contractor, from a nominated Subcontractor (as defined in Clause 5 [Nominated Subcontractors]) or otherwise; and for which there shall be included in the Contract Price:

- i) The actual amounts paid (or due to be paid) by the Contractor, and
- ii) a sum for overhead charges and profit, calculated as a percentage of these actual amounts by applying the relevant percentage rate (if any) stated in the appropriate Schedule. If there is no such rate, the percentage rate stated in **the Special Conditions of Contract** shall be applied.
- 13.6.2 The Contractor shall, when required by the Engineer, produce quotations, invoices, vouchers and accounts or receipts in substantiation.

#### 13.7 Dayworks

- 13.7.1 For work of a minor or incidental nature, the Architect may instruct that a Variation shall be executed on a daywork basis. The work shall then be valued in accordance with the Daywork Schedule included in the Contract, and the following procedure shall apply. If a Daywork Schedule is not included in the Contract, this Sub-Clause shall not apply.
- 13.7.2 Before ordering Goods for the work, the Contractor shall submit quotations to the Engineer. When applying for payment, the Contractor shall submit invoices, vouchers and accounts or receipts for any Goods.
- 13.7.3 Except for any items for which the Daywork Schedule specifies that payment is not due, the Contractor shall delive reach day to the Architect accurate statements induplicate which shall include the following details of the resources used in executing the previous day's work:
- a) The names, occupations and time of Contractor's Personnel,
- b) the identification, type and time of Contractor's Equipment and Temporary Works, and
- c) the quantities and types of Plant and Materials used.
- 13.7.4 One copy of each statement will, if correct, or when agreed, be signed by the Architect and returned to the Contractor. The Contractor shall then submit priced statements of these resources to the Engineer, prior to their inclusion in the next Statement under Sub-Clause 14.3 [Application for Interim Payment Certificates].

# 13.8 Adjustments for Changes in Legislation

- 13.8.1 The Contract Price shall be adjusted to take account of any increase or decrease in Cost resulting from a change in the Laws of Kenya (including the introduction of new Laws and the repeal or modification of existing Laws) or in the judicial or official governmental interpretation of such Laws, made after the Base Date, which affect the Contractor in the performance of obligations under the Contract.
- 13.8.2 If the Contractor suffers (or will suffer) delay and/or incurs (or will incur) additional Cost as a result of these changes in the Laws or in such interpretations, made after the Base Date, the Contractor shall give notice to the Architect and shall be entitled subject to Sub-Clause 20.1 [Contractor's Claims] to:
- a) an extension of time for any such delay, if completion is or will be delayed, under Sub-Clause 8.4 [Extension of Time for Completion], and
- b) payment of any such Cost, which shall be included in the Contract Price.
- 13.8.3 After receiving this notice, the Architect shall proceed in accordance with Sub-Clause 3.5 [Determinations] to agree or determine these matters.
- 13.8.4 Not withstanding the foregoing, the Contractor shall not be entitled to an extension of time if the relevant delay has already been taken into account in the determination of a previous extension of time and such Cost shall not be separately paid if the same shall already have been taken into account in the indexing of any inputs to the table of adjustment data in accordance with the provisions of Sub-Clause 13.8 [Adjustments for Changes in Cost].

#### 13.9 Adjustments for Changes in Cost

- 13.9.1 In this Sub-Clause, "table of adjustment data" means the completed table of adjustment data for local and foreign currencies included in the Schedules. If there is no such table of adjustment data, this Sub-Clause shall not apply.
- 13.9.2 If this Sub-Clause applies, the amounts payable to the Contractor shall be adjusted for rises or falls in the cost of labor, Goods and other inputs to the Works, by the addition or deduction of the amounts determined by the formulae prescribed in this Sub-Clause. To the extent that full compensation for any rise or fall in Costs is not covered by the provisions of this or other Clauses, the Accepted Contract Amount shall be deemed to have included a mounts to cover the contingency of other rises and falls in costs.
- 13.9.3 The adjustment to be applied to the amount otherwise payable to the Contractor, as valued in accordance with the appropriate Schedule and certified in Payment Certificates, shall be determined from formulae for each of the currencies in which the Contract Price is payable. No adjustment is to be applied to work valued on the basis of Cost or current prices. The formulae shall be of the following general type:

**Price Adjustment Formula** Prices shall be adjusted for fluctuations in the cost of inputs only if **provided for in the SCC.** If so provided, the amounts certified in each payment certificate, before deducting for Advance Payment, shall be adjusted by applying the respective price adjustment factor to the payment amounts due in each currency. A separate formula of the type specified below applies:

#### P = A + B Im/Io where:

**P** is the adjustment factor for the portion of the Contract Price payable.

A and B a recoefficients **specified in the SCC**, representing then on adjustable and adjustable portions, respectively, of the Contract Price payable and

I m is the index prevailing at the end of the month being invoiced and Ioc is the index prevailing 30 days before Bid opening for inputs payable.

- **NOTE:** The sum of the two coefficients A and B should be 1 (one) in the formula for each currency. Normally, both coefficients shall be the same in the formulae for all currencies, since coefficient A, for the non adjustable portion of the payments, is a very approximate figure (usually 0.15) to take account of fixed cost elements or other nonadjustable components. The sum of the adjustments for each currency are added to the Contract Price.
- 13.9.4 The cost indices or reference prices stated in the table of adjustment data shall be used. If their source is in doubt, itshall be determined by the Engineer. Forth is purpose, reference shall be made to the values of the indices at stated dates (quoted in the fourth and fifth columns respectively of the table) for the purposes of clarification of the source; although these dates (and thus these values) may not correspond to the base cost indices.
- 13.9.5 Incases where the "currency of index" is not the relevant currency of payment, each index shall be converted into the relevant currency of payment at the selling rate, established by the Central Bank of Kenya, of this relevant currency on the above date for which the index is required to be applicable.
- 13.9.6 Until such time as each current cost index is available, the Architect shall determine a provisional index for

the issue of Interim Payment Certificates. When a current cost index is available, the adjustment shall be recalculated accordingly.

- 13.9.7 If the Contractor fails to complete the Works within the Time for Completion, adjustment of prices there after shall be made using either (i) each index or price applicable on the date 49 days prior to the expiry of the Time for Completion of the Works, or (ii) the current index or price, whichever is more favorable to the Procuring Entity.
- 13.9.8 The weightings (coefficients) for each of the factors of cost stated in the table(s) of adjustment data shall only be adjusted if they have been rendered unreasonable, unbalanced or in applicable, as a result of Variations.

#### 14. CONTRACT PRICE AND PAYMENT

#### 14.1 The Contract Price

- 14.1.1 Unless otherwise stated in the Special Conditions:
- a) The value of the payment certificate shall be agreed or determined under Sub-Clause 12.3 [Evaluation] and be subject to adjustments in accordance with the Contract;
- b) the Contractor shall pay all taxes, duties and fees required to be paid by him under the Contract, and the Contract Price shall not be adjusted for any of these costs except as stated in Sub-Clause 13.7 [Adjustments for Changes in Legislation];
- c) any quantities which may be set out in the Bill of Quantities or other Schedule are estimated quantities and are not to be taken as the actual and correct quantities:
  - i) of the Works which the Contractor is required to execute, or
  - ii) for the purposes of Clause 12 [Measurement and Evaluation]; and
- d) the Contractor shall submit to the Engineer, within 30 days after the Commencement Date, a proposed breakdown of each lump sum price in the Schedules. The Architect may take account of the break down when preparing Payment Certificates but shall not be bound by it.
- 14.1.2 Notwithstanding the provisions of subparagraph (b), Contractor's Equipment, including essential spare parts there for, imported by the Contractor for the sole purpose of executing the Contract shall not be exempt from the payment of import duties and taxes upon importation.

# 14.2 Advance Payment

- 14.2.1 The Procuring Entity shall make an advance payment, as an interest-free loan for mobilization and cashflow support, when the Contractor submits a guarantee in accordance with this Clause. The total advance payment, the number and timing of instalments (if more than one), and the applicable currencies and proportions, shall be as stated in the **Special Conditions of Contract.**
- 14.2.2 Unless and until the Procuring Entity receives this guarantee, or if the total advance payment is not stated in the Special Conditions of Contract, this Sub-Clause shall not apply.
- 14.2.3 The Architect shall deliver to the Procuring Entity and to the Contractor an Interim Payment Certificate for the advance payment or its first instalment after receiving a Statement (under Sub-Clause 14.3 [Application for Interim Payment Certificates]) and after the Procuring Entity receives (i) the Performance Security in accordance with Sub-Clause 4.2 [Performance Security] and (ii) a guarantee in amounts and currencies equal to the a dvance payment. This guarantee shall be issued by a reputable bank or financial institutions elected by the Contractor and shall be in the form annexed to the Special Conditions or in another form approved by the Procuring Entity.
- 14.2.4 The Contractor shall ensure that the guarantee is valid and enforceable until the advance payment has been repaid, but its amount shall be progressively reduced by the amount repaid by the Contractor as indicated in the Payment Certificates. If the terms of the guarantee specify its expiry

date, and the advance payment has not been repaid by the date 30 days prior to the expiry date, the Contractor shall extend the validity of the guarantee until the advance payment has been repaid.

- 14.2.5 Unless stated otherwise in **the Special Conditions of Contract**, the advance payment shall be repaid through percentage deductions from the interim payments determined by the Architect in accordance with Sub-Clause 14.6 [Issue of Interim Payment Certificates], as follows:
- a) Deductions shall commence in the next interim Payment Certificate following that in which the total of all certified interim payments (excluding the advance payment and deductions and repayments of retention) exceeds 30 percent (30%) of the Accepted Contract Amount less Provisional Sums; and
- deductions shall be made at the amortization rate stated in the **Special Conditions of Contract** of the amount of each Interim Payment Certificate (excluding the advance payment and deductions for its repayments as well as deductions for retention money) in the currencies and proportions of the advance payment until such time as the advance payment has been repaid; provided that the advance payment shall be completely repaid prior to the time when 90 percent (90%) of the Accepted Contract Amount less Provisional Sums has been certified for payment.
- 14.2.6 If the advance payment has not been repaid prior to the issue of the Taking-Over Certificate for the Works or prior to termination under Clause 15 [Termination by Procuring Entity], Clause 16 [Suspension and Termination by Contractor] or Clause 19 [Force Majeure] (as thec ase may be), the whole of the balance then outstanding shall immediately become due and in case of termination under Clause 15 [Termination by Procuring Entity], except for Sub-Clause 14.2.7 [Procuring Entity's Entitlement to Termination for Convenience], payable by the Contractor to the Procuring Entity.

# 14.3 Application for Interim Payment Certificates

14.3.1 The Contractor shall submit a Statement (in number of copies indicated in the **Special Conditions of Contract**) to the Architect after the end of each month, in aform approved by the Engineer, showing in detail

the amounts to which the Contractor considers itself to be entitled, together with supporting documents which shall include there porton the progress during this month in accordance with Sub-Clause4.21 [Progress Reports].

- 14.3.2 The Statement shall include the following items, as applicable, which shall be expressed in the various currencies in which the Contract Price is payable, in the sequence listed:
- a) the estimated contract value of the Works executed and the Contractor's Documents produced up to the end of the month (including Variations but excluding items described in sub-paragraphs (b) to (g) below);
- b) any amounts to be added and deducted for changes in legislation and changes in cost, in accordance with Sub-Clause 13.7 [Adjustments for Changes in Legislation] and Sub-Clause 13.8 [Adjustments for Changes in Cost];
- any amount to be deducted for retention, calculated by applying the percentage of retention stated in the Special Conditions of Contract to the total of the above amounts, until the amount so retained by the Procuring Entity reaches the limit of Retention Money (if any) stated in the Special Conditions of Contract;
- d) any amounts to be added for the advance payment and (if more than one instalment) and to be deducted for its repayments in accordance with Sub-Clause 14.2 [Advance Payment];
- e) any amounts to be added and deducted for Plant and Materials in accordance with Sub-Clause 14.5 [Plant and Materials intended for the Works];
- f) any other additions or deductions which may have become due under the Contractor otherwise, including those under Clause 20 [Claims, Disputes and Arbitration]; and
- g) the deduction of amounts certified in all previous Payment Certificates.

#### 14.4 Schedule of Payments

- 14.4.1 I fthe Contract includes a schedule of payments specifying the instalments in which the Contract Price will be paid, then unless otherwise stated in this schedule:
- a) The instalments quoted in this schedule of payments shall be the estimated contract values for the purposes of sub-paragraph (a) of Sub-Clause 14.3 [Application for Interim Payment Certificates];
- b) Sub-Clause 14.5 [Plant and Materials intended for the Works] shall not apply; and
- c) If these instalments are not defined by reference to the actual progress achieved in executing the Works, and if actual progress is found to be less or more than that on which this schedule of payments was based, then the Architect may proceed in accordance with Sub-Clause 3.5 [Determinations] to agree or determine revised instalments, which shall take account of the extent to which progress is less or more than that on which the instalments were previously based.
- 14.4.2 If the Contract does not include a schedule of payments, the Contractor shall submit non-binding estimates

of the payments which he expects to become due during each quarterly period. The first estimate shall be submitted within 42 days after the Commencement Date. Revised estimates shall be submitted at quarterly intervals, until the Taking-Over Certificate has been issued for the Works.

#### 14.5 Plant and Materials intended for the Works

14.5.1 If this Sub-Clause applies, Interim Payment Certificates shall include, under sub-paragraph (e) of Sub-Clause 14.3, (i) an amount for Plant and Materials which have been sent to the Site for incorporation in the Permanent Works, and (ii) a reduction when the contract value of such Plant and Materials is included as part of the

Permanent Works under sub-paragraph (a) of Sub-Clause 14.3 [Application for Interim Payment Certificates].

- 14.5.2 If the lists referred to in sub-paragraphs (b)(i) or (c)(i) below are not included in the Schedules, this SubClause shall not apply.
- 14.5.3 The Architect shall determine and certify each addition if the following conditions a resatisfied: a) The Contractor has:
  - i) kept satisfactory records (including the orders, receipts, Costs and use of Plant and Materials) which are available for inspection, and
  - (ii) submitted statement of the Cost of acquiring and delivering the Plant and Materials to the Site, supported by satisfactory evidence;

and either:

- b) the relevant Plant and Materials:
  - i) are those listed in the Schedules for payment when shipped, ii) have been shipped to Kenya, enroute to the Site, in accordance with the Contract; and iii) are described in a clean shipped bill of lading or other evidence of shipment, which has been submitted to the Architect together with evidence of payment of freight and insurance, any other documents reasonably required, and a bank guarantee in a form and issued by an entity approved by the Procuring Entity in amounts and currencies equal to the amount due under this Sub-Clause: this guarantee may be in a similar form to the form referred to in Sub-Clause14.2 [Advance Payment] and shall be valid until the Plant and Materials are properly stored on Site and protected against loss, damage or deterioration; or
- c) the relevant Plant and Materials:
  - i) are those listed in the Schedules for payment when delivered to the Site, and
  - ii) have been delivered to and are properly stored on the Site, are protected against loss, damage or deterioration and appear to be in accordance with the Contract.
- 14.5.4 The additional amount to be certified shall be the equivalent of eighty percent (80%) of the Architect determination of the cost of the Plant and Materials (including delivery to Site), taking account of the documents mentioned in this Sub-Clause and of the contract value of the Plant and Materials.

14.5.5 The currencies for this additional amount shall be the same as those in which payment will become due when the contract value is included under sub-paragraph (a) of Sub-Clause 14.3 [Application for Interim Payment Certificates]. At that time, the Payment Certificate shall include the applicable reduction which shall be equivalent to, and in the same currencies and proportions as, this additional amount for the relevant Plant and Materials.

# 14.6 Issue of Interim Payment Certificates

- 14.6.1 No amount will be certified or paid until the Procuring Entity has received and approved the Performance Security. Thereafter, the Architect shall, within 30 days after receiving a Statement and supporting documents, deliver to the Procuring Entity and to the Contractor an Interim Payment Certificate which shall state the amount which the Architect fairly determines to be due, with all supporting particulars for any reduction or withholding made by the Architect on the Statemen tif any.
- 14.6.2 However, prior to issuing the Taking-Over Certificate for the Works, the Architect shall not be bound to issue an Interim Payment Certificate in an amount which would (after retention and other deductions) be less than the minimum amount of Interim Payment Certificates (if any) stated in the **Special Conditions of Contract**. In this event, the Architect shall give notice to the Contractor accordingly.
- 14.6.3 An Interim Payment Certificate shall not be withheld for any other reason, although:
- if anything supplied or work done by the Contractor is not in accordance with the Contract, the cost of rectification or replacement may be withheld until rectification or replacement has been completed; and/or
- b) if the Contractor was or is failing to perform any work or obligation in accordance with the Contract, and had been so notified by the Engineer, the value of this work or obligation may be withheld until the work or obligation has been performed.
- 4.6.4 The Architect may in any Payment Certificate make any correction or modification that should properly be made to any previous Payment Certificate. A Payment Certificate shall not be deemed to indicate the Architect acceptance, approval, consent or satisfaction.

# 14.7 Payment

- 14.7.1 The Procuring Entity shall pay to the Contractor:
- a) The advance payment shall be paid within 60 days after signing of the contract by both parties or within 60 days after receiving the documents in accordance with Sub-Clause 4.2 [Performance Security] and Sub-Clause 14.2 [Advance Payment], which ever is later;
- b) The amount certified in each Interim Payment Certificate within 60 days after the Architect Issues Interim Payment Certificate; and
- c) the amount certified in the Final Payment Certificate within 60 days after the Procuring Entity Issues Interim Payment Certificate; or after determination of any disputed amount shown in the Final Statement
  - in accordance with Sub-Clause 16.2 [Terminationby Contractor].
- 14.7.2 Payment of the amount due in each currency shall be made into the bank account, nominated by the Contractor, in the payment country (forth is currency) specified in the Contract.

### 14.8 Delayed Payment

14.8.1 If the Contractor does not receive payment in accordance with Sub-Clause 14.7 [Payment], the Contractor shall be entitled to receive financing charges (simple interest) monthly on the amount unpaid during the period of delay. This period shall be deemed to commence on the date for payment specified in Sub-Clause 14.7 [Payment], irrespective (in the case of its sub-paragraph (b) of the date on which any Interim Payment Certificate isissued.

- 14.8.2 These financing charges shall be calculated at the annual rate of three percentage points above the mean rate of the Central Bank in Kenya of the currency of payment, or if not available, the interbank offered rate, and shall be paid in such currency.
- 14.8.3 The Contractor shall be entitled to this payment without formal notice and certification, and without prejudice to any other right or remedy.

# 14.9 Payment of Retention Money

- 14.9.1 When the Taking-Over Certificate has been issued for the Works, the first half of the Retention Money shall be certified by the Architect for payment to the Contractor. If a Taking-Over Certificate is issued for a Section or part of the Works, a proportion of the Retention Money shall be certified and paid. This proportion shall behalf (50%) of the proportion calculated by dividing the estimated contract value of the Section or part, by the estimated final Contract Price.
- 14.9.2 Promptly after the latest of the expiry dates of the Defects Liability Periods, the outstanding balance of the Retention Money shall be certified by the Architect for payment to the Contractor. If a Taking-Over Certificate was issued for a Section, a proportion of the second half of the Retention Money shall be certified and paid promptly after the expiry date of the Defects Notification Period for the Section. This proportion shall behalf (50%) of the proportion calculated by dividing the estimated contract value of the Section by the estimated final Contract Price.
- 14.9.3 However, if any work remains to be executed under Clause 11 [Defects Liability], the Architects hall be entitled to withhold certification of the estimated cost of this work until it has been executed.
- 14.9.4 When calculating these proportions, no account shall be taken of any adjustments under Sub-Clause 13.7 [Adjustments for Changes in Legislation] and Sub-Clause 13.8 [Adjustments for Changes in Cost].
- 14.9.5 Unless otherwise stated in the Special Conditions, when the Taking-Over Certificate has been issued for the Works and the first half of the Retention Money has been certified for payment by the Engineer, the Contractor shall be entitled to substitute a Retention Money Security guarantee, in the form annexed to the Special Conditions or in another form approved by the Procuring Entity and issued by a reputable bank or financial institution selected by the Contractor, for the second half of the Retention Money.
- 14.9.6 The Procuring Entity shall return the Retention Money Security guarantee to the Contractor within 14 days after receiving a copy of the Completion Certificate.

### 14.10 Statement at Completion

14.10.1 Within 84 days after receiving the Taking-Over Certificate for the Works, the Contractor shall submit to the Architect three copies of a Statement at completion with supporting documents, in accordance with Sub-

Clause 14.3 [Application for Interim Payment Certificates], showing:

- a) the value of all work done in accordance with the Contract up to the date stated in the Taking-Over Certificate for the Works,
- b) any further sums which the Contractor considers to be due, and
- an estimate of any other amounts which the Contractor considers will become due to him under the Contract. Estimated amounts shall be shown separately in this Statement at completion.
- 14.10.2 The Architect shall then certify in accordance with Sub-Clause 14.6 [Issue of Interim Payment Certificates].

### 14.11 Application for Final Payment Certificate

- 14.11.1 Within 60 days after receiving the Completion Certificate, the Contractor shall submit, to the Engineer, six copies of a draft final statement with supporting documents showing in detail in a form approved by the Engineer:
  - a) The value of all work done in accordance with the Contract, and
  - b) Any further sums which the Contractor considers to be due to him under the Contractor otherwise.
- 14.11.2 If the Architect disagrees with or cannot verify any part of the draft final statement, the Contractor shall submit such further information as the Architect may reasonably require within 30 days from receipt of said draft and shall make such changes in the draft as may be agreed between them. The Contractor shall then prepare and submit to the Architect the final statement as agreed. This agreed statement is referred to in these Conditions as the "Final Statement".
- 14.11.3 However, if, following discussions between the Architect and the Contractor and any changes to the draft final statement which are agreed, it be comes evident that a dispute exists, the Architect shall deliver to the Procuring Entity (with a copy to the Contractor) an Interim Payment Certificate for the agreed parts of the draft final statement. Thereafter, if the dispute is finally resolved under Sub-Clause 20.4 [Obtaining Dispute Board's Decision] or Sub-Clause 20.5 [Amicable Settlement], the Contractor shall then prepare and submit to the Procuring Entity (with a copy to the Engineer) a Final Statement.

### 14.12 Discharge

When submitting the Final Statement, the Contractor shall submit a discharge which confirms that the total of the Final Statement represents full and final settlement of all moneys due to the Contractor under or in connection with the Contract. This discharge may state that it becomes effective when the Contractor has received the Performance Security and the out standing balance of this total, in which event the discharge shall be effective on such date.

# 14.13 Issue of Final Payment Certificate

- 14.13.1 Within 30days after receiving the Final Statement and discharge in accordance with Sub-Clause 14.11 [Application for Final Payment Certificate] and Sub-Clause 14.12 [Discharge], the Architect shall deliver, to the Procuring Entity and to the Contractor, the Final Payment Certificate which shall state: a) The amount which he fairly determines is finally due, and
- b) After giving credit to the Procuring Entity for all amounts previously paid by the Procuring Entity and for all sums to which the Procuring Entity is entitled, the balance (if any) due from the Procuring Entity to the Contractor or from the Contractor to the Procuring Entity, as the case may be.
- 14.13.2 If the Contractor has not applied for a Final Payment Certificate in accordance with Sub-Clause 14.11 [Application for Final Payment Certificate] and Sub-Clause 14.12 [Discharge], the Architect shall request the Contractor to do so. If the Contractor fails to submit an application within a period of 30 days, the Architect shall issue the Final Payment Certificate for such amount as he fairly determines to be due.

# 14.14 Cessation of Procuring Entity's Liability

- 14.14.1 The Procuring Entity shall not be liable to the Contractor for any matter or thing under or in connection with the Contract or execution of the Works, except to the extent that the Contractor shall have included an amount expressly for it:
- a) in the Final Statement and also,
- b) (except for matters or things arising after the issue of the Taking-Over Certificate for the Works) in the Statement at completion described in Sub-Clause 14.10 [Statement at Completion].
- 14.14.2 However, this Sub-Clause shall not limit the Procuring Entity's liability under his in demnification obligations, or the Procuring Entity's liability in any case of fraud, deliberate default or reckless misconduct by the Procuring Entity.

### 14.15 Currencies of Payment

The Contract Price shall be paid in the currency or currencies named in the Schedule of Payment Currencies. If more than one currency is so named, payments shall be made as follows:

- a) If the Accepted Contract Amount was expressed in Local Currency only:
  - i) the proportions or amounts of the Local and Foreign Currencies, and the fixed rates of exchange to be used for calculating the payments, shall be as stated in the Schedule of Payment Currencies, except as otherwise agreed by both Parties;
  - ii) payments and deductions under Sub-Clause 13.5 [Provisional Sums] and Sub-Clause 13.7 [Adjustments for Changes in Legislation] shall be made in the applicable currencies and proportions; and
  - iii) otherpaymentsanddeductions under sub-paragraphs (a) to (d) of Sub-Clause 14.3 [Application for Interim Payment Certificates] shall be made in the currencies and proportions specified in sub-paragraph (a) (i) above;
- b) payment of the damages specified in the Special Conditions of Contract, shall be made in the currencies and proportions specified in the Schedule of Payment Currencies;
- c) other payments to the Procuring Entity by the Contractor shall be made in the currency in which the sum was expended by the Procuring Entity, or in such currency as may be agreed by both Parties;
- d) if any amount payable by the Contractor to the Procuring Entity in a particular currency exceeds the sum payable by the Procuring Entity to the Contractor in that currency, the Procuring Entity may recover the balance of this amount from the sums otherwise payable to the Contractor in other currencies; and
- e) if no rates of exchange are stated in the Schedule of Payment Currencies, they shall be those prevailing on the Base Date and determined by the Central Bank of Kenya.

#### 15. TERMINATION BY PROCURING ENTITY

### 15.1 Notice to correct any defects or failures

If the Contractor fails to carry out any obligation under the Contract, the Architect may by notice require the Contractor to make good the failure and to remedy it within 30 days.

# 15.2 Termination by Procuring Entity

- 15.2.1 The Procuring Entity shall be entitled to terminate the Contract if the Contractor breaches the contract based on following circumstances which shall include but not limited to:
- a) fails to comply with Sub-Clause 4.2 [Performance Security] or with a notice under Sub-Clause 15.1 [Notice to Correct],
- b) abandons the Works or otherwise plainly demonstrates the intention not to continue performance of his obligations under the Contract,
- c) without reasonable excuse fails:
  - i) to proceed with the Works in accordance with Clause 8 [Commencement, Delays and Suspension], or ii) to comply with a notice issued under Sub-Clause 7.5 [Rejection] or Sub-Clause 7.6 [Remedial

Work], within 30 days after receiving it,

- d) subcontracts the major part or whole of the Works or assigns the Contract without the consent of the Procuring Entity,
- e) becomes bankrupt or insolvent, goes into liquidation, has a receiving or administration order made against him, compounds with his creditors, or carries on business under a receiver, trustee or manager for the benefit of his creditors, or if any act is done or event occurs which (under applicable Laws) has a similar effect to any of theseacts or events, or
- f) gives or offers to give (directly or indirectly) to any person any bribe, gift, gratuity, commission or other thing of value, as an induce mentor reward:
- i) for doing or for bearing to do any action in relation to the Contract, or ii) for showing or for bearing to show favor or disfavor to any person in relation to the Contract, or iii) if any of the Contractor's Personnel, agents or Subcontractors gives or offers to give (directly or indirectly) to any person any such induce mentor reward as is described in this sub-paragraph (f).

- However, lawful inducements and rewards to Contractor's Personnel shall not entitle termination, or
- g) If the contract or repeatedly fails to remedy delivers defective work,
- h) based on reasonable evidence, has engaged in Fraud and Corruption as defined in paragraph 2.2 of the Appendix B to these General Conditions, incompeting for or in executing the Contract.
- 15.2.2 In any of these events or circumstances, the Procuring Entity may, upon giving 14 days' notice to the Contractor, terminate the Contract and expel the Contractor from the Site. However, in the case of sub- paragraph (e) or (f) or (g) or (h), the Procuring Entity may by notice terminate the Contract immediately.
- 15.2.3 The Procuring Entity's election to terminate the Contract shall not prejudice any other rights of the Procuring Entity, under the Contractor otherwise.
- 15.2.4 The Contractor shall then leave the Site and deliver any required Goods, all Contractor's Documents, and other design documents made by or for him, to the Engineer. However, the Contractor shall use his best efforts to comply immediately with any reasonable instructions included in the notice (i) for the assignment of any subcontract, and (ii) for the protection of life or property or for the safety of the Works.
- 15.2.5 After termination, the Procuring Entity may complete the Works and/ or arrange for any other entities to do so. The Procuring Entity and these entities may then use any Goods, Contractor's Documents and other design documents made by or on behalf of the Contractor.
- 15.2.6 The Procuring Entity shall then give notice that the Contractor's Equipment and Temporary Works will be released to the Contractor at or near the Site. The Contractor shall promptly arrange their removal, at the risk and cost of the Contractor. However, if by this time the Contractor has failed to make a payment due to the Procuring Entity, these items may be sold by the Procuring Entity in order to recover this payment. Any balance of the proceeds shall then be paid to the Contractor.

#### 15.3 Valuation at Date of Termination

Assoon as practicable after a notice of termination under Sub-Clause 15.2 [Termination by Procuring Entity] has taken effect, the Architect shall proceed in accordance with Sub-Clause 3.5 [Determinations] to agree or determine the value of the Works, Goods and Contractor's Documents, and any other sums due to the Contractor for work executed in accordance with the Contract.

# 15.4 Payment after Termination

After a notice of termination under Sub-Clause 15.2 [Termination by Procuring Entity] has taken effect, the Procuring Entity may:

- a) Proceed in accordance with Sub-Clause 2.5 [Procurin Entity's Claims],
- b) withhold further payments to the Contractor until the costs of execution, completion and remedying of any defects, damages for delay in completion (if any), and all other costs incurred by the Procuring Entity, have been established, and/ or
- c) recover from the Contractor any losses and damages incurred by the Procuring Entity and any extra costs of completing the Works, after allowing for any sum due to the Contractor under Sub-Clause 15.3 [Valuation at Date of Termination]. After recovering any such losses, damages and extra costs, the Procuring Entity shall pay any balance to the Contractor.

# 15.5 Procuring Entity's Entitlement to Termination for Convenience

The Procuring Entity shall be entitled to terminate the Contract, at any time at the Procuring Entity's convenience, by giving notice of such termination to the Contractor. The termination shall take effect 30 days after the later of the dates on which the Contractor receives this notice or the Procuring Entity returns the Performance Security. The Procuring Entity shall not terminate the Contract under this Sub-Clausein order to execute the Works itself or to arrange for the Works to be executed by another contractor or to avoid a termination of the Contract by the Contractor under Clause 16.2 [Termination by Contractor]. After this termination, the Contractor shall proceed in accordance with Sub-Clause 16.3 [Cessation of Work and

Removal of Contractor's Equipment] and shall be paid in accordance with Sub-Clause 16.4 [Payment on Termination].

# 15.6 Fraud and Corruption

The Contractor shall ensure compliance with the Kenya Government's Anti-Corruption Laws and its prevailing sanctions.

### 15.7 Corrupt gifts and payments of commission

- 15.7.1 The Contractor shall not;
  - a) Offer or give or agree to give to any person in the service of the Procuring Entity any gift or consideration of any kind as an inducement or reward for doing or for bearing to door for having done or for borne to do any act in relation to the obtaining or execution of this or any other Contract for the Procuring Entity or for showing or for bearing to show favor or disfavor to any person in relation to this or any other contract for the Procuring Entity.
  - b) Enter into this or any other contract with the Procuring Entity in connection with which commission has been paid or agreed to be paid by him or on his behalf or to his knowledge, unless before the Contract is made particulars of any such commission and of the terms and conditions of any agreement for the payment there of have been disclosed in writing to the Procuring Entity.
- 15.7.2 Any breach of this Condition by the Contractor or by anyone employed by him or acting on his behalf (whether with or without the knowledge of the Contractor) shall be an offence under the provisions of the Public Procurement and Asset Disposal Act (2015) and the Anti-Corruption and Economic Crimes Act (2003) of the Laws of Kenya.

#### 16. SUSPENSION AND TERMINATION BY CONTRACTOR

### 16.1 Contractor's Entitlement to Suspend Work

- 16.1.1 If the Architect fails to certify in accordance with Sub-Clause 14.6 [Issue of Interim Payment Certificates] or Sub-Clause 14.7 [Payment],or not receiving instructions that would enable the contractor to proceed with the works in accordance with the program, the Contractor may, after giving not less than 30 days' notice to the Procuring Entity, suspend work (or reduce the rate of work) unless and until the Contractor has received the Payment Certificate, reasonable evidence or payment, as the case may beand as described in the notice.
- 16.1.2 The Contractor's action shall not prejudice his entitlements to financing charges under Sub-Clause 14.8 [Delayed Payment] and to termination under Sub-Clause 16.2 [Terminationby Contractor].
- 16.1.3 If the Contractor subsequently receives such Payment Certificate, evidence or payment (as described in the relevant Sub-Clause and in the above notice) before giving a notice of termination, the Contractor shall resume normal working as soon as is reasonably practicable.
- 16.1.4 If the Contractor suffers delay and/ori neurs Cost as a result of suspending work (or reducing the rate of work) in accordance with this Sub-Clause, the Contractor shall give notice to the Architect and shall be entitled subject to Sub-Clause 20.1 [Contractor's Claims] to:
  - a) an extension of time for any such delay, if completion is or will be delayed, under Sub-Clause 8.4

[Extension of Time for Completion], and

- b) payment of any such Cost-plus profit, which shall be included in the Contract Price.
- After receiving this notice, the Architect shall proceed in accordance with Sub-Clause 3.5 [Determinations] to agree or determine these matters.

#### 16.3 Termination by Contractor

- 16.3.1 The Contractor shall be entitled to terminate the Contract if:
  - a) the Architect fails, within 60 days after receiving a Statement and supporting documents, to issue the relevant Payment Certificate,
  - b) the Contractor does not receive the amount due under an Interim Payment Certificate within 90 days after the expiry of the time stated in Sub-Clause1 4.7 [Payment] within which payment is to be made

(except for deductions in accordance with Sub-Clause 2.5 [Procuring Entity's Claims]),

c) the Procuring Entity substantially fails to perform his obligations under the Contract in such manner as to materially and adversely affect the economic balance of the Contract and/or the ability of the

Contractor to perform the Contract,

d) a prolonged suspension affects the whole of the Works as described in Sub-Clause 8.11 [Prolonged

Suspension], or

- e) the Procuring Entity becomes bankrupt or insolvent, goes into liquidation, has a receiving or administration order made against him, compounds with his creditors, or carries on business under a receiver, trustee or manager for the benefit of his creditors, or if any act is done or event occurs which (under applicable Laws) has a similar effect to any of these acts or events.
- f) the Contractor does not receive the Architect instruction recording the agreement of both Parties on the fulfilment of the conditions for the Commencement of Works under Sub-Clause 8.1 [Commencement of Works].
- 16.3.2 In any of these events or circumstances, the Contractor may, upon giving 14 days' notice to the Procuring Entity, terminate the Contract. However, in the case of sub-paragraph (f) or (g), the Contractor may by notice terminate the Contract immediately.
- 16.3.3 The Contractor's election to terminate the Contract shall not prejudice any other rights of the Contractor, under the Contractor otherwise.

#### 16.4 Cessation of Work and Removal of Contractor's Equipment

After a notice of termination under Sub-Clause 15.5 [Procuring Entity's Entitlement to Termination for Convenience], Sub-Clause 16.2 [Termination by Contractor] or Sub-Clause 19.6 [Optional Termination, Payment and Release] has taken effect, the Contractor shall promptly:

- a) cease all further work, except for such work as may have been instructed by the Architect for the protection of life or property or for the safety of the Works,
- b) hand over Contractor's Documents, Plant, Materials and other work, for which the Contractor has received payment, and
- c) remove all other Goods from the Site, except as necessary for safety, and leave the Site.

#### 16.5 PaymentonTermination

After a notice of termination under Sub-Clause 16.2 [Termination by Contractor] has taken effect, the Procuring Entity shall promptly:

- a) Return the Performance Security to the Contractor,
- b) pay the Contractor in accordance with Sub-Clause 19.6 [Optional Termination, Payment and Release], and
- c) pay to the Contractor the amount of any loss or damage sustained by the Contractor as a result of this termination.

### 17. RISK AND RESPONSIBILITY

#### 17.1 Indemnities

- 17.1.1 The Contractor shall indemnify and hold harmless the Procuring Entity, the Procuring Entity's Personnel, and their respective agents, against and from all claims, damages, losses and expenses (including legal fees and expenses) in respect of:
- a) Bodily injury, sickness, disease or death, of any person what so ever arising outo for in the course of or by reason of the Contractor's design (if any), the execution and completion of the Works and the remedying of any defects, unless attributable to any negligence, willful actor breach of the Contract by the Procuring Entity, the Procuring Entity's Personnel, or any of their respective agents, and
- b) damage to or loss of any property, real or personal (other than the Works), to the extent that such damage or loss arises out of or in the course of or by reason of the Contractor's design (if any), the execution and completion of the Works and the remedying of any defects, unless and to the extent that any such damage or loss is attributable to any negligence, willful act or breach of the Contract by the Procuring Entity, the Procuring Entity's Personnel, their respective agents, or anyone directly or indirectly employed by any of them.
- 17.1.2 The Procuring Entity shall indemnify and hold harmless the Contractor, the Contractor's Personnel, and their respective agents, against and from all claims, damages, losses and expenses (including legal fees and expenses) in respect of (1) bodily injury, sickness, disease or death, which is attributable to any negligence, willful act or breach of the Contract by the Procuring Entity, the Procuring Entity's Personnel, or any of their respective agents, and (2) the matters for which liability may be excluded from insurance cover, as described in sub-paragraphs (d)(i), (ii) and (iii) of Sub-Clause 18.3 [Insurance Against Injury to Persons and Damage to Property], unless and to the extent that any such damage or loss is attributable to any negligence, willful actor breach of the Contract by the contractor, the contractor's Personnel, their respective agents, or anyone directly or indirectly employed by any of them.

#### 17.2 Contractor's Care of the Works

- 17.2.1 The Contractor shall take full responsibility for the care of the Works and Goods from the Commencement Date until the Taking-Over Certificate is issued (or is deemed to be issued under Sub-Clause 10.1 [Taking Over of the Works and Sections]) for the Works, when responsibility for the care of the Works shall pass to the Procuring Entity. If a Taking-Over Certificate is issued (or is so deemed to be issued) for any Section or part of the Works, responsibility for the care of the Section or part shall then pass to the Procuring Entity.
- 17.2.2 After responsibility has accordingly passed to the Procuring Entity, the Contractor shall take responsibility for the care of any work which is outstanding on the date stated in a Taking-Over Certificate, until this outstanding work has been completed.
- 17.2.3 If any loss or damage happens to the Works, Goods or Contractor's Documents during the period when the Contractorisresponsible for their care, from any cause not listed in Sub-Clause 17.3 [Procuring Entity's Risks], the Contractor shall rectify the loss or damage at the Contractor's risk and cost, so that the Works, Goods and Contractor's Documents conform with the Contract.
- 17.2.4 The Contractor shall be liable for any loss or damage caused by any actions performed by the Contractor after a Taking-Over Certificate has been issued. The Contractor shall also be liable for any loss or damage which occurs after a Taking-Over Certificate has been issued and which arose from a previous event for which the Contractor was liable.

# 17.3 Procuring Entity's Risks

The risks referred to in Sub-Clause 17.4 [Consequences of Procuring Entity's Risks] below, in so far as they directly affect the execution of the Works in Kenya, are: a) War hostilities (whether war be declared or not).

- b) rebellion, riot, commotion or disorder, terrorism, sabotage by persons other than the Contractor's Personnel,
- c) explosive materials, ionizing gradiation or contamination by radio-activity, except as may be attributable to the Contractor's use of such explosives, radiation or radio-activity,
- d) pressure waves caused by aircraft or other aerial devices traveling at sonic or supersonic speeds,

- e) use or occupation by the Procuring Entity of any part of the Permanent Works, except as may be specified in the Contract,
- f) design of any part of the Works by the Procuring Entity's Personnel or by others for whom the Procuring Entity is responsible, and
- g) any operation of the forces of nature which is Unforeseeable or against which an experienced contractor could not reasonably have been expected to have taken adequate preventive precautions.

### 17.4 Consequences of Procuring Entity's Risks

- 17.4.1 If and to the extent that any of the risks listed in Sub-Clause 17.3 above results in loss or damage to the Works, Goods or Contractor's Documents, the Contractor shall promptly give notice to the Architect and shall rectify this loss or damage to the extent required by the Engineer.
- 17.4.2 If the Contractor suffers delay and/ or incurs Cost from rectifying this loss or damage, the Contractor shall give a further notice to the Architect and shall be entitled subject to Sub-Clause 20.1 [Contractor's Claims] to:
- (a) An extension of time for any such delay, if completion is or will be delayed, under Sub-Clause 8.4 [Extension of TimeforCompletion], and
- (b) paymentofany such Cost, which shall be included in the Contract Price. In the case of sub-paragraphs (e)and (g) of Sub-Clause 17.3 [Procuring Entity's Risks], Accrued Costs shall be payable.
- 17.4.3 After receiving this further notice, the Architect shall proceed in accordance with Sub-Clause 3.5 [Determinations] to agree or determine these matters.

### 17.5 Intellectual and Industrial Property Rights

- 17.5.1 In this Sub-Clause, "infringement" shall refer to an infringement (or alleged infringement) of any patent, registered design, copyright, trade mark, trade name, trade secret or other intellectual or industrial property right relating to the Works; and "claim" shall refer to a claim (or proceedings pursuing a claim) alleging an infringement.
- 17.5.2 Whenever a Party does not give notice to the other Party of any claim within 30 days of receiving the claim, the first Party shall be deemed to have waived any right to indemnity under this Sub-Clause.
- 17.5.3 The Procuring Entity shall indemnify and hold the Contractor harmless against and from any claim alleging an infringement which is or was:
  - a) An un avoidable result of the Contractor's compliance with the Contract, or
  - b) A result of any Works be ingused by the Procuring Entity:
    - i) for a purpose other than that indicated by, or reasonably to be inferred from, the Contract, or ii) in conjunction with anything not supplied by the Contractor, unless such use was disclosed to the Contractor prior to the Base Date or is stated in the Contract.
- 17.5.4 The Contractor shall indemnify and hold the Procuring Entity harmless again stand from any other claim which arises out of or in relation to (i) the manufacture, use, sale or import of any Goods, or (ii) any design for which the Contractor is responsible.
- 17.5.5 IfaPartyisentitledtobeindemnified under this Sub-Clause, the indemnifying Party may (at its cost) conduct negotiations for the settlement of the claim, and any litigation or arbitration which may arise from it. The other Party shall, at the request and cost of the indemnifying Party, assist in contesting the claim. This other Party (and its Personnel) shall not make any admission which might be prejudicial to the indemnifying Party, unless the indemnifying Party failed to take over the conduct of any negotiations, litigation or arbitration upon being requested to do so by such other Party.
- 17.5.6 For operation and maintenance of any plan to requipment installed, the contractor shall grant a non-exclusive and non-transferable license to the Procuring Entity under the patent, utility models ,or other intellectual rights owned by the contractor or a third party from whom the contract or has received the rights to grant sub-licenses and shall also grant to the Procuring Entity a non-exclusive and non-transferable rights (without the rights to sub-license) to use the know how and other technical information disclosed to the contract or

under the contract. Nothing contained here-in shall be construed as transferring ownership of any patent, utility model, trademark, design, copy right, know-how or other intellectual rights from the contractor or any other third party to the Procuring Entity.

### 17.6 Limitation of Liability

- 17.6.1 Neither Party shall be liable to the other Party for loss of use of anyW orks, loss of profit, loss of any contractor for any in director consequential loss or damage which may be suffered by the other Party in connection with the Contract, other than as specifically provided in Sub-Clause 8.7 [Delay Damages]; Sub-Clause 11.2 [Cost of Remedying Defects]; Sub-Clause 15.4 [Payment after Termination]; Sub-Clause 16.4 [Payment on Termination]; Sub-Clause 17.1 [Indemnities]; Sub-Clause 17.4(b) [Consequences of Procuring Entity's Risks] and Sub-Clause 17.5 [Intellectual and Industrial Property Rights].
- 17.6.2 The total liability of the Contractor to the Procuring Entity, under or in connection with the Contract other than under Sub-Clause 4.19 [Electricity, Water and Gas], Sub-Clause 4.20 [Procuring Entity's Equipment and Free- Issue Materials], Sub-Clause 17.1 [Indemnities] and Sub-Clause 17.5 [Intellectual and Industrial Property Rights], shall not exceed the sum resulting from the application of a multiplier (less or greater than one) to the Accepted Contract Amount, as stated in **the Special Conditions of Contract**, or (if such multiplier or other sum is not so stated) the Accepted Contract Amount.
- 17.6.3 This Sub-Clause shall not limit liability in any case of fraud, deliberate default or reckless misconduct by the defaulting Party.

# 17.7 Use of Procuring Entity's Accommodation/Facilities

- 17.7.1 The Contractor shall take full responsibility for the care of the Procuring Entity provided accommodation and facilities, if any, as detailed in the Specification, from the respective dates of hand-over to the Contractor until cessation of occupation (where hand-over or cessation of occupation may take place after the date stated in the Taking-Over Certificate for the Works).
- 17.7.2 If any loss or damage happens to any of the above items while the Contractor is responsible for their care arising from any cause whatsoever other than those for which the Procuring Entity is liable, the Contractor shall, at his own cost, rectify the loss or damage to the satisfaction of the Engineer.

# 18. INSURANCE

# 18.1 General Requirements for Insurances

- 18.1.1 In this Clause, "insuring Party" means, for each type of insurance, the Party responsible for effecting and maintaining the insurance specified in the relevant Sub-Clause.
- 18.1.2 Wherever the Contractor is the insuring Party, each insurance shall be effected with insurers and in terms approved by the Procuring Entity. These terms shall be consistent with any terms agreed by both Parties before the date of the Letter of Acceptance. This agreement of terms shall take precedence over the provisions of this Clause.
- 18.1.3 Wherever the Procuring Entity is the insuring Party, each insurance shall be effected with insurers and in terms acceptable to the Contractor. These terms shall be consistent with any terms agreed by both Parties before the date of the Letter of Acceptance. This agreement of terms shall take precedence over the provisions of this Clause.
- 18.1.4 If a policy is required to indemnify joint insured, the cover shall apply separately to each insured as though a separate policy had been issued for each of the joint insured. If a policy indemnifies additional joint insured, namely in addition to the insured specified in this Clause, (i) the Contractor shall act under the policy on behalf of these additional joint insured except that the Procuring Entity shall act for Procuring Entity's Personnel, (ii) additional joint insured shall not be entitled to receive payments directly from the insurer or to have any other direct dealings with the insurer, and (iii) the insuring Party shall require all additional joint insured to comply with the conditions stipulated in the policy.

18.1.5 Each policy insuring against loss or damage shall provide for payments to be made in the currencies required

to rectify the loss or damage. Payments received from insurers shall be used for the rectification of the loss or damage.

- 18.1.6 The relevant insuring Party shall, within the respective periods stated in **the Special Conditions of Contract** (calculated from the Commencement Date), submit to the other Party:
  - a) Evidence that the insurances described in this Clause have been affected, and
  - b) copies of the policies for the insurances described in Sub-Clause 18.2 [Insurance for Works and Contractor's Equipment] and Sub-Clause 18.3 [Insurance against Injury to Persons and Damage to Property].
- 18.1.7 When each premium is paid, the insuring Party shall submit evidence of payment to the other Party. Whenever evidence or policies are submitted, the insuring Party shall also give notice to the Engineer.
- 18.1.8 Each Party shall comply with the conditions stipulated in each of the insurance policies. The insuring Party shall keep the insurers informed of any relevant changes to the execution of the Works and ensure that insurance is maintained in accordance with this Clause.
- 18.1.9 Neither Party shall make any material alteration to the terms of any insurance without the prior approval of the other Party. If an insurer makes (or at tempts to make) any alteration, the Party first notified by the insurer shall promptly give notice to the other Party.
- 18.1.10 If the insuring Party fails to effect and keep in force any of the insurances it is required to effect and maintain under the Contractor fails to provide satisfactory evidence and copies of policies in accordance with this Sub- Clause, the other Party may (at its option and without prejudice to any other right or remedy) effect insurance for the relevant coverage and pay the premiums due. The insuring Party shall pay the amount of these premiums to the other Party, and the Contract Price shall be adjusted accordingly.
- 18.1.11 Nothing in this Clause limits the obligations, liabilities or responsibilities of the Contractor or the Procuring Entity, under the other terms of the Contractor otherwise. Any amounts not insured or not recovered from the insurers shall be borne by the Contractor and/or the Procuring Entity.
- 18.1.12 Procuring Entity in accordance with these obligations, liabilities or responsibilities. However, if the insuring Party fails to effect and keep in force an insurance which is available and which it is required to effect and maintain under the Contract, and the other Party neither approves the omission nor effects insurance for the coverage relevant to this default, any moneys which should have been recoverable under this insurance shall be paid by the insuring Party.
- 18.1.13 Payments by one Party to the other Party shall be subject to Sub-Clause 2.5 [Procuring Entity's Claims] or Sub- Clause 20.1 [Contractor's Claims], as applicable.
- 18.1.14 The Contractor shall be entitled to place all insurance relating to the Contract (including, but not limited to the insurance referred to Clause 18) with insurers from any eligible source country.

#### 18.2 Insurance for Works and Contractor's Equipment

- 18.2.1 The insuring Party shall insure the Works, Plant, Material sand Contractor's Documents for not less than the full reinstatement cost including the costs of demolition, removal of debris and professional fees and profit. This insurance shall be effective from the date by which the evidence is to be submitted under sub-paragraph (a) of Sub-Clause 18.1 [General Requirements for Insurances], until the date of issue of the Taking-Over Certificate for the Works.
- 18.2.2 The insuring Party shall maintain this insurance to provide cover until the date of issue of the Performance Certificate, for loss or damage for which the Contractor is liable arising from a cause occurring prior to the issue of the Taking-Over Certificate, and for loss or damage caused by the

- Contractor in the course of any other operations (including those under Clause 11 [Defects Liability]).
- 18.2.3 The insuring Party shall insure the Contractor's Equipment for not less than the full replacement value, including delivery to Site. For each item of Contractor's Equipment, the insurance shall be effective while it is being transported to the Site and until it is no longer required as Contractor's Equipment.
- 18.2.4 Unless otherwise stated in the Special Conditions, insurances under this Sub-Clause:
  - a) Shal lbe effected and maintained by the Contractor as insuring Party,
  - b) shall be in the joint names of the Parties, who shall be jointly entitled to receive payments from the insurers, payments being held or allocated to the Party actually bearing the costs of rectifying the loss or damage,
  - shall cover all loss and damage from any cause not listed in Sub-Clause 17.3 [Procuring Entity's Risks],
  - d) shall also cover, to the extent specifically required in the tendering documents of the Contract, loss or damage to a part of the Works which is attributable to the use or occupation by the Procuring Entity of another part of the Works, and loss or damage from the risks listed in subparagraphs (c), (g) and (h)of Sub-Clause 17.3 [Procuring Entity's Risks], excluding (in each case) risks which are not insurable at commercially reasonable terms, with deductibles per occurrence of not more than the amount stated **in the Special Conditions** of Contract (if an amount is not so stated,t his sub-paragraph (d) shall not apply), and
  - e) may however exclude loss of, damage to, and reinstatement of:
    - i) a part of the Works which is in a defective condition due to a defect in its design, materials or workmanship (but cover shall include any other parts which are lost or damaged as a direct result of this defective condition and not as described in subparagraph (ii) below),
    - ii) apart of the Works which is lost or damaged inorder to reinstate any other part of the Works if this other part is in a defective condition due to a defect in its design, materials or workmanship,
    - iii) apart of the Works which has been taken over by the Procuring Entity, except to the extent that the Contractor is liable for the loss or damage, and
    - iv) Goods while they are not in Kenya, subject to Sub-Clause 14.5 [Plant and Materials intended for the Works].
- 18.2.5 If, more than one year after the Base Date, the cover described in sub-paragraph (d) above ceases to be

available at commercially reasonable terms, the Contractor shall (as insuring Party) give notice to the Procuring Entity, with supporting particulars. The Procuring Entity shall then (i) be entitled subject to SubClause 2.5 [Procuring Entity's Claims] to payment of an amount equivalent to such commercially reasonable terms as the Contractor should have expected to have paid for such cover, and (ii) be deemed, unless he obtains the cover at commercially reasonable terms, to have approved the omission under SubClause 18.1 [General Requirements for Insurances].

#### 18.3 Insurance against Injury to Persons and Damage to Property

- 18.3.1 The insuring Party shall insure against each Party's liability for any loss, damage, death or bodily injury which may occur to any physical property (except things insured under Sub-Clause 18.2 [Insurance for Works and Contractor's Equipment]) or to any person (except persons insured under Sub-Clause 18.4 [Insurance for Contractor's Personnel]), which may arise out of the Contractor's performance of the Contract and occurring before the issue of the Performance Certificate.
- 18.3.2 This insurance shall be for a limit per occurrence of not less than the amount stated in **the Special**Conditions of Contract, with no limit on the number of occurrences. If an amount is not stated in the Special Conditions of Contract, this Sub-Clause shall not apply.
- 18.3.3 Unless otherwise stated in the Special Conditions, the insurances specified in this Sub-Clause:
  - a) Shall be effected and maintained by the Contractor as insuring Party,

- b) shall be in the joint names of the Parties,
- c) shall be extended to cover liability for all loss and damage to the Procuring Entity's property (except things insured under Sub-Clause 18.2) arising out of the Contractor's performance of the Contract, and
- d) may however exclude liability to the extent that it arises from:
  - i) the Procuring Entity's right to have the Permanent Works executed on, over, under, in or ii) through any land, and to occupy this land for the Permanent Works,
- iii) damage which is an unavoidable result of the Contractor's obligations to execute the iv) Works and remedy any defects, and
- v) a cause listed in Sub-Clause 17.3 [Procuring Entity's Risks], except to the extent that cover is available at commercially reasonable terms.

#### 18.4 Insurance for Contractor's Personnel

- 18.4.1 The Contractor shall effect and maintain insurance against liability for claims, damages, losses and expenses (including legal fees and expenses) arising from injury, sickness, disease or death of any person employed by the Contractor or any other of the Contractor's Personnel.
- 18.4.2 The insurance shall cover the Procuring Entity and the Architect against liability for claims, damages, losses and expenses (including legal fees and expenses) arising from injury, sickness, disease or death of any person employed by the Contractoror any other of the Contractor's Personnel, except that this insurance may exclude losses and claims to the extent that they arise from any act or neglect of the Procuring Entity or of the Procuring Entity's Personnel.
- 18.4.3 The insurance shall be maintained in full force and effect during the whole time that these personnel are assisting in the execution of the Works. For a Subcontractor's employees, the insurance may be effected by the Subcontractor, but the Contractor shall be responsible for compliance with this Clause.

#### 19. FORCE MAJEURE

#### 19.1 Definition of Force Majeure

- 19.1.1 In this Clause, "Force Majeure" means an exceptional event or circumstance:
  - a) Which is beyond a Party's control,
  - b) Which such Party could not reasonably have provided against before entering into the Contract,
  - c) which, having arisen, such Party could not reasonably have avoided or over come, and
  - d) which is not substantially attributable to the other Party.
- 19.1.2 Force Majeure may include, but is not limited to, exceptional events or circumstances of the kind listed below, s olong as conditions (a) to (d) above are satisfied:
  - a) war, hostilities (whether war be declared or not), invasion, act of foreign enemies,
  - b) rebellion, terrorism, sabotage by persons other than the Contractor's Personnel, revolution, insurrection, military or usurped power, or civil war,
  - c) riot, commotion, disorder, strike or lock out by persons other than the Contractor's Personnel,
  - d) munitions of war, explosive materials, ionizing radiation or contamination by radio-activity, except as maybeattributabletotheContractor'suseofsuchmunitions, explosives, radiation or radio-activity, and
  - e) natural catastrophes such as earthquake, hurricane, typhoon or volcanic activity.

#### 19.2 Notice of Force Majeure

19.2.1 If a Party is or will be prevented from performing its substantial obligations under the Contract by Force

Majeure, then it shall give notice to the other Party of the event or circumstances constituting the Force Majeure and shall specify the obligations, the performance of which is or will be prevented. The notice shall be given within 14 days after the Party became aware, or should have become aware, of the relevant event or circumstance constituting Force Majeure.

- 19.2.2 The Party shall, having given notice, be excused performance of its obligations for so long as such Force Majeure prevents it from performing them.
- 19.2.3 Not withstanding any other provision of this Clause, Force Majeure shall not apply to obligations of either Party to make payments to the other Party under the Contract.

# 19.3 **Duty to Minimize Delay**

Each Party shall at all times use all reasonable endeavors to minimize any delay in the performance of the Contract as a result of Force Majeure. A Party shall give notice to the other Party when it ceases to be affected

by the Force Majeure.

# 19.4 Consequences of Force Majeure

- 19.4.1 If the Contractor is prevented from performing his substantial obligations under the Contract by Force Majeure of which notice has been given under Sub-Clause 19.2 [Notice of Force Majeure], and suffers delay and/or incurs Cost by reason of such Force Majeure, the Contractor shall be entitled subject to Sub-Clause 20.1 [Contractor's Claims] to:
  - a) an extension of time for any such delay, if completion is or will be delayed, under Sub-Clause 8.4

[Extension of Time for Completion], and

- b) if the event or circumstance is of the kind described in sub-paragraphs (i) to (iv) of Sub-Clause 19.1 [Definition of Force Majeure] and, in sub-paragraphs (ii) to (iv), occurs in Kenya, payment of any such Cost, including the costs of rectifying or replacing the Works and/or Goods damaged or destroyed by Force Majeure, to the extent they are not indemnified through the insurance policy referred to in Sub- Clause 18.2 [Insurance for Works and Contractor's Equipment].
- 19.4.2 After receiving this notice, the Architect shall proceed in a ccordance with Sub-Clause 3.5 [Determinations] to agree or determine these matters.

### 19.5 Force Majeure Affecting Subcontractor

If any Subcontractor is entitled under any contract or agreement relating to the Works to relief from force majeure on terms additional to or broader than those specified in this Clause, such additional or broader force majeure events or circumstances shall not excuse the Contractor's non-performance or entitle him to relief under this Clause.

# 19.6 Optional Termination, Payment and Release

- 19.6.1 If the execution of substantially all the Works in progress is prevented for a continuous period of 84 days by reason of Force Majeure of which notice has been given under Sub-Clause 19.2 [Notice of Force Majeure], or for multiple periods which total more than 140 days due to the same notified Force Majeure, then either Party may give to the other Party a notice of termination of the Contract. In this event, the termination shall take effect 7 days after the notice is given, and the Contractor shall proceed in accordance with Sub-Clause 16.3 [Cessation of Work and Removal of Contractor's Equipment].
- 19.6.2 Upon such termination, the Architect shall determine the value of the work done and issue a Payment Certificate which shall include:
  - a) theamountspayableforanyworkcarriedoutforwhichapriceisstatedintheContract;
  - b) the Cost of Plant and Materials ordered for the Works which have been delivered to the Contractor, or of which the Contractor is liable to accept delivery: this Plant and Materials shall become the property of (and be at the risk of) the Procuring Entity when paid for by the Procuring Entity, and the Contractor shall place the same at the Procuring Entity's disposal;
  - c) other Cost or liabilities which in the circumstances were reasonably and necessarily incurred by

Contractor in the expectation of completing the Works;

- d) the Cost of removal of Temporary Works and Contractor's Equipment from the Site and the return of these items to the Contractor's works in his country (or to any other destination at no greater cost); and
- e) the Cost of repatriation of the Contractor's staff and lab or employed wholly in connection with the Works at the date of termination.

#### 19.7 Release from Performance

Not withstanding any other provision of this Clause, if any event or circumstance outside the control of the Parties (including, but not limited to, Force Majeure) arises which makes it impossible or unlawful for either or both Parties to fulfil its or their contractual obligations or which, under the law governing the Contract, entitles the Parties to be released from further performance of the Contract, then upon notice by either Party to the other Partyofsucheventorcircumstance:

- a) The Parties shall be discharged from further performance, without prejudice to the rights of either Party in respect of any previous breach of the Contract, and
- b) The sum payable by the Procuring Entity to the Contractor shall be the same as would have been payable under Sub-Clause 19.6 [Optional Termination, Payment and Release] if the Contract had been terminated under Sub-Clause 19.6.

#### 20. SETTLEMENT OF CLAIMS AND DISPUTES

#### 20.1 Contractor's Claims

- 20.1.1 If the Contractor considers itself to be entitled to any extension of the Time for Completion and/or any additional payment, under any Clause of these Conditions or otherwise in connection with the Contract, the Contractor shall give Notice to the Engineer, describing the event or circumstance giving rise to the claim. The notice shall be given as soon as practicable, and not later than 30 days after the Contractor became aware, or should have become aware, of the event or circumstance.
- 20.1.2 If the Contractor fails to give notice of a claim within such period of 30 days, the Time for Completion shall

not be extended, the Contractor shall not be entitled to additional payment, and the Procuring Entity shall be discharged from all liability in connection with the claim. Otherwise, the following provisions of this SubClause shall apply.

- 20.1.3 The Contractor shall also submit any other notices which are required by the Contract, and supporting particulars for the claim, all as relevant to such event or circumstance.
- 20.1.4 The Contractorshall keepsuch contemporary records as may be necessary to substantiate any claim, either on the Site or at an other location acceptable to the Engineer. Without admitting the Procuring Entity's liability, the Architect may, after receiving any notice under this Sub-Clause, monitor the record-keeping and/or instruct the Contractor to keep further contemporary records. The Contractor shall permit the Architect to inspect all these records and shall (if instructed) submit copies to the Engineer.
- 20.1.5 Within 42days after the Contractor became aware (or should have become aware) of the event or circumstance giving rise to the claim, or within such other period as may be proposed by the Contractor and approved by the Engineer, the Contractor shall send to the Architect fully detailed claim which includes full supporting particulars of the basis of the claim and of the extension of time and/ or additional payment claimed. If the event or circumstance giving rise to the claim has a continuing effect: a) This fully detailed claim shall be considered as interim;
- b) The Contractor shall send further interim claims at monthly intervals, giving the accumulated delay and/ or amount claimed, and such further particulars as the Architect may reasonably require; and
- The Contractor shall send a final claim within 30 days after the end of the effects resulting from the eventor circumstance, or within such other period as may be proposed by the Contractor and approved by the Engineer.

- 20.1.6 Within 42 days after receiving a Notice of a claim or any further particulars supporting a previous claim, or within such other period as may be proposed by the Architect and approved by the Contractor, the Architect shall respond with approval, or with disapproval and detailed comments. He may also request any necessary further particulars but shall nevertheless give his response on the principles of the claim within the above defined time period.
- 20.1.7 Within the above defined period of 42 days, the Architect shall proceed in accordance with Sub-Clause 3.5 [Determinations] to agree or determine (i) the extension (if any) of the Time for Completion (before or after its expiry) in accordance with Sub-Clause 8.4 [Extension of Time for Completion], and/or (ii) the additional payment (if any) to which the Contractor is entitled under the Contract.
- 20.1.8 Each Payment Certificate shall include such additional payment for any claim as has been reasonably substantiated as due under the relevant provision of the Contract. Unless and until the particulars supplied are sufficient to substantiate the whole of the claim, the Contractor shall only be entitled to payment for such part of the claim as he has been able to substantiate.
- 20.1.9 If the Architect does not respond within the time frame defined in this Clause, either Party may consider that the claim is rejected by the Architect and any of the Parties may refer the dispute for amicable settlement in accordance with Clause 20.3.
- 20.1.10 The requirements of this Sub-Clause are in addition to those of any other Sub-Clause which may apply to a claim. If the Contractor fails to comply with this or another Sub-Clause in relation to any claim, any extension of time and/ or additional payment shall take account of the extent (if any) to which the failure has prevented or prejudiced proper investigation of the claim, unless the claim is excluded under the second paragraph of this Sub-Clause 20.3.

#### **20.2** Procuring Entity's Claims

20.2.1 If the Procuring Entity considers itself to be entitled to any payment under any Clause of these Conditionsor

otherwise in connection with the Contract, and/or to any extension of the Defects Notification Period, the Procuring Entity or the Architect shall give notice and particulars to the Contractor. However, notice is not required for payments due under Sub-Clause 4.19 [Electricity, Water and Gas], under Sub-Clause 4.20 [Procuring Entity's Equipment and Free-Issue Materials], or for other services requested by the Contractor.

- 20.2.2 The notice shall be given as soon as practicable and no longer than 30 days after the Procuring Entity became aware, or should have become aware, of the event or circumstances giving rise to the claim. A notice relating to any extension of the Defects Notification Period shall be given before the expiry of such period.
- 20.2.3 The particulars shall specify the Clause or other basis of the claim and shall include substantiation of the amount and/or extension to which the Procuring Entity considers itself to be entitled in connection with the Contract. The Architect shall then proceed in accordance with Sub-Clause 3.5 [Determinations] to agree or determine (i) the amount (if any) which the Procuring Entity is entitled to be paid by the Contractor, and/or
- (ii) the extension (if any) of the Defects Notification Period in accordance with Sub-Clause 11.3 [Extension of Defects Notification Period].
- 20.2.4 This amount may be included as a deduction in the Contract Price and Payment Certificates. The Procuring Entity shall only be entitled to set off against or make any deduction from an amount certified in a Payment Certificate, or to otherwise claim against the Contractor, in accordance with this Sub-Clause.

#### 20.3 Amicable Settlement

Where a notice of a claim has been given, both Parties shall attempt to settle the dispute amicably before the commencement of arbitration. However, unless both Parties agree otherwise, the Party giving a notice of a claim in accordance with Sub-Clause 20.1 above should move to commence arbitrationa fter 60 days from the day on which a notice of a claim was given, even if no attempt at an amicable settlement has been made.

# **20.4** Matters that may be referred to arbitration

Notwithstanding anything stated herein the following matters may be referred to arbitration before the practical completion of the Works or abandonment of the Works or termination of the Contract by either party:

- a) Whether or not the issue of an instruction by the Architect is empowered by these Conditions.
- b) Whether or not a certificate has been improperly withheld or is not in accordance with these Conditions.
- c) Any dispute arising in respect risks arising from matters referred to in Clause 17.3 and Clause 19.
- e) All other matters shall only be referred to arbitration after the completion or alleged completion of the Works or termination or alleged termination of the Contract, unless the Procuring Entity and the Contractor agree otherwise in writing.

#### 20.5 Arbitration

- 20.5.1 Any claim or dispute between the Parties arising out of or in connection with the Contract not settled amicably in accordance with Sub-Clause 20.3 shall be finally settled by arbitration.
- 20.5.2 No arbitration proceedings shall be commenced on any claim or dispute where notice of a claim or dispute has not been given by the applying party within ninety days of the occurrence or discovery of the matter or issue giving rise to the dispute.
- 20.5.3 Not withstanding the issue of a notice as stated above, the arbitration of such a claim or dispute shall not commence unless an attempt has in the first instance been made by the parties to settle such claim or dispute amicably with or without the assistance of third parties. Proof of such attempt shall be required.
- 20.5.4 The Arbitrator shall, without prejudice to the generality of his powers, have powers to direct such measurements, computations, tests or valuations as may in his opinion be desirable in order to determine the rights of the parties and assess and a ward any sums which ought to have been the subject of or included in any certificate.
- 20.5.5 The Arbitrator shall, without prejudice to the generality of his powers, have powers to open up, review and

revise any certificate, opinion, decision, requirement or notice and to determine all matters in dispute which shall be submitted to him in the same manner as if no such certificate, opinion, decision require mentor notice had been given.

- 20.5.6 The arbitrators shall have full power to open up, review and revise any certificate, determination, instruction, opinion or valuation of the Engineer, relevant to the dispute. Nothing shall disqualify representatives of the Parties and the Architect from being called as a witness and giving evidence before the arbitrators on any matter whatsoever relevant to the dispute.
- 20.5.7 Neither Party shall be limited in the proceedings before the arbitrators to the evidence, or to the reasons for dissatisfaction given in its Notice of Dissatisfaction.
- 20.5.7 Arbitration may be commenced prior to or after completion of the Works. The obligations of the Parties, and the Architect shall not be altered by reason of any arbitration being conducted during the progress of the Works.
- 20.5.8 The terms of the remainder of each or all the members of Arbitration shall be mutually agreed upon by the Parties when agreeing the terms of appointment. Each Party shall be responsible for paying one-half of this remuneration.

#### **20.6** Arbitration with National Contractors

- 20.6.1 If the Contractis with national contractors, arbitration proceedings will be conducted in accordance with the Arbitration Laws of Kenya. In case of any claim or dispute, such claim or dispute shall be notified in writing by either party to the other with a request to submit it to arbitration and to concur in the appointment of an Arbitrator within thirty days of the notice. The dispute shall be referred to the arbitration and final decision of a person to be agreed between the parties. Failing agreement to concur in the appointment of an Arbitrator, the Arbitrator shall be appointed, on the request of the applying party, by the Chairman or Vice Chairman of any of the following professional institutions; i) Architectural Association of Kenya ii) Institute of Quantity Surveyors of Kenya iii) Association of Consulting Engineers of Kenya iv) Chartered Institute of Arbitrators (Kenya Branch) v) Institution of Engineers of Kenya
- 20.6.2 The institution written to first by the aggrieved party shall take precedence over all other institutions.

### **20.7** Arbitration with Foreign Contractors

20.7.1 Arbitration with foreign contractors shall be conducted in accordance with the arbitration rules of the United

Nations Commission on International Trade Law (UNCITRAL); or with proceedings administered by the International Chamber of Commerce (ICC) and conducted under the ICC Rules of Arbitration; by one or more arbitrators appointed in accordance with said arbitration rules.

20.7.2 The place of arbitration shall be a location specified in the SCC; and the arbitration shall be conducted in the language for communications defined in Sub-Clause 1.4 [Law and Language].

### **20.8** Alternative Arbitration Proceedings

Alternatively, the Parties may refer the matter to the Nairobi Centre for International Arbitration (NCIA) which offers a neutral venue for the conduct of national and international arbitration with commitment to providing institutional support to the arbitral process.

#### 20.9 Failureto Comply with Arbitrator's Decision

- 20.9.1 The award of such Arbitrator shall be final and binding up on the parties.
- 20.9.2 In the even that a Party fails to comply with a final and binding Arbitrator's decision, then the other Party may, without prejudice to any other rights it may have, refer the matter to a competent court of law.

#### 20.10 Contract operations to continue

Notwithstanding any reference to arbitration herein,

- 1.1.1 the parties shall continue to perform their respective obligations under the Contract unless they otherwise agree; and
- 1.1.2 the Procuring Entity shall pay the Contractor any monies due the Contractor.

# **Section IX - Special Conditions of Contract**

The following Special Conditions shall supplement the GCC. Whenever there is a conflict, the provisions in shall prevail over those in the GCC.

here

Conditions	Sub-	Data	
	Clause		
Part A - Contract Data			
Procuring Entity's name and	Heading	State Department for Cooperatives,	
address		Social Security Building,	
		Bishop Road,	
		P.O. Box 30547 - 00100, Nairobi.	
Name and Reference No. of the Contract	Heading and 1.1	W.P.ITEM NO. D116/CO/KWL/2001 JOB NO. 10826A	
Engineers Name and address	Heading and 3.1.1	The Works Secretary, State Department for Public Works of P.O.Box 30734-00100	
Contractor's Representative's name	4.3.1	[insert the name of the Contractor's Representative agreed by the Procuring Entity prior to Contract signature]	
Key Personnel names	16.9.1	[insert the name of each Key Personnel agreed by the Procuring Entity prior to Contract signature]	
Time for Completion	1.1.	36 weeks	
Defects Notification Period	1.1	26 weeks	
Sections	1.1	Not applicable	
Electronic transmission systems	1.3	11	
Time for the Parties entering into a	1.6	Within 30days	
Contract Agreement			
Commencement Date	8.1.1		
Time for access to the Site	2.1.1	No later than the Commencement Date, and not later	
		thandays after Commencement Date	
Architect Duties and Authority	3.1.6 (b)	Variations resulting in an increase of the Accepted	
·	(ii)	Contract Amount in excess of <u>0</u> % shall require approval of the Procuring Entity.	
Performance Security	4.2.1	The performance security will be in the form of a  [insert either one of "demand guarantee" or "performance bond"] in the amount(s) of 5 percent of the Accepted Contract Amount and in the same currency(ies) of the Accepted Contract Amount.	
Normal working hours	6.5	0800 - 1700 HOURS	
Delay damages for the Works	8.7 & 14.15(b)	0.005 % of the Contract Price per day.  If Sections are to be used, refer to Table: Summary of Sections below	
Maximum amount of delay damages	8.7.1	5_% of the final Contract Price.	
Provisional Sums	13.6. (b)(ii)	[If there are Provisional Sums, insert a percentage for adjustment of Provisional Sums]%	

Adjustments for Changes in Cost	13.9	Period "n" applicable to the adjustment multiplier "Pn": [Insert the period if different from one (1) month; if period "n" is one (1) month, insert "not applicable"]
Total advance payment	14.2.1	N/A
Conditions	Sub- Clause	Data
Repayment amortization rate of advance payment	14.2.5 (b)	N/A
Percentage of Retention	14.3.2 (c)	_10%
Limit of Retention Money	14.3.2 (c)	
Plant and Materials		If Sub-Clause 14.5 applies:
	14.5.3(b)(i)	Plant and Materials for payment Free on Board[list].
	14.5.3(c)(i)	Plant and Materials for payment when delivered to the Site [list].
Minimum Amount of Interim Payment Certificates	14.6.2	As per valuation
Publishing source of commercial interest rates for financial charges in case of delayed payment	14.8	Central Bank of Kenya
Maximum total liability of the Contractor to the Procuring Entity	17.6.2	[As per applicable laws
Periods for submission of	18.1.6	[Insert period for submission of evidence of
insurance:		insurance and policy. Period may be from 14 days to 30days.]
a. evidence of insurance.		14 days
b. relevant policies		14 days
Maximum amount of deductibles for insurance of the Procuring Entity's risks	18.2.4 (d)	As per applicable laws
Minimum amount of third-party insurance	18.3.2	As per applicable laws
The place of arbitration	20.7.2	To be agreed by the Parties

# **SECTION X - CONTRACT FORMS**

FORM No. 1 - NOTIFICATION OF INTENTION TO AWARD

FORM NO. 2 – REQUEST FOR REVIEW

FORM No. 3-LETTEROF AWARD

FORM No. 4 - CONTRACT AGREEMENT

FORM No. 5 - PERFORMANCE SECURITY [Option 1 - Unconditional Demand Bank Guarantee]

FORM No. 6- PERFORMANCE SECURITY [Option 2- Performance Bond] FORM

No. 7 - ADVANCE PAYMENT SECURITY

FORM No. 8 - RETENTION MONEY SECURITY

## FORM No 1: NOTIFICATION OF INTENTION TOAWARD OF CONTRACT

This Notification of Award shall be sent to each Tenderer that submitted a Tender and was not successful. Send this Notification to the Tenderer's Authorized Representative named in the Tender Information Form on the format below

<b>FORM</b>	AT
-------------	----

1.	For 1	the attention of Tenderer's Authorized Representative				
	i)	Name: [insert Authorized Representative's name] ii) Address:				
	[insert Authorized Representative's Address] iii) Telephone: [insert					
	Authorized Representative's telephone/fax numbers] iv) Email Address:					
	[inse	ert Authorized Representative's email address]				
	_	PORTANT: insert the date that this Notification is transmitted to Tenderers. The Notification must be sent to Tenderers simultaneously. This means on the same date and as close to the same time as possible.]				
2.	Date	e of transmission: [email] on [date] (local time)				
	This	Notification is sent by (Name and designation)				
3.	<u>Noti</u>	fication of Award				
	i)	Procuring Entity: [insert the name of the				
	Proc	curingEntity] ii) Project: [insert name ofproject] iii)				
	Co	ntract title: [insert the name of thecontract]				
	iv)	ITT No: [insert ITT reference number from ProcurementPlan]				
		Notification of Intention to Award (Notification) notifies you of our decision to award the above contract. transmission of this Notification begins the Standstill Period. During the Standstill Period, you may:				
4.		uest a debriefing in relation to the evaluation of your tender by submitting a Procurement-related Complaint in ion to the decision to award the contracts.				
	a)	The successful tenderers				
	i)	Name of successful Tender_				
	ii)	Address of the successful Tender				
	iii)	Contract price of the successful Tender Kenya Shillings  (in words)				
		b) The reasons for your tender being unsuccessful are as follows:				
		c) OtherTenderers				

Names of all Tenderers that submitted a Tender. If the Tender's price was evaluated include the evaluated price as

138

well as the Tender price as read out.

SNo	Name of Tender	Tender Price as	Tender's evaluated	One Reason Why Not Evaluated
		read out	price (Note a)	
1				
2				
3				
4				
5				

(Note a) State NE if not evaluated

#### 5. How to request a debriefing

- a) DEADLINE: The dead line to request a debriefing expires at midnight on [insert date] (local time).
- b) You may request a debriefing in relation to the results of the evaluation of your Tender. If you decide to request a debriefing your written request must be made within three (5) Business Days of receipt of this Notification of Intention to Award.
- c) Provide the contract name, reference number, name of the Tenderer, contact details; and address the request for debriefing as follows:
  - i) Attention: [insert full name of person, if applicable] ii) Title/position: [insert title/position] iii) Agency: [insert name of Procuring Entity] iv) Email address: [insert email address]
- d) If your request for a debriefing is received within the 3 Days deadline, we will provide the debriefing within five (3) Business Days of receip tof your request. If we are unable to provide the debriefing within this period, the Standstill Period shall be extended by five (3) Days after the date that the debriefing is provided. If this happens, we will notify you and confirm the date that the extended Standstill Period will end.
- e) The debriefing may be in writing, by phone, video conference call or in person. We shall promptly advise you in writing how the debriefing will take place and confirm the date and time.
- f) If the deadline to request a debriefing has expired, you may still request a debriefing. In this case, we will provide the debriefing as soon as practicable, and normally no later than fifteen (15) Days from the date of publication of the Contract Award Notice.

#### 6. How to make a complaint

- a) Period: Procurement-related Complaint challenging the decision to award shall be submitted by midnight, [insert date] (local time).
- b) Provide the contract name, reference number, name of the Tenderer, contact details; and address the Procurement-related Complaint as follows:
  - i) Attention: [insert full name of person, if applicable] ii) Title/position:
     [insert title/position] iii) Agency: [insert name of Procuring Entity]
     iv) Email address: [insert email address]
- c) At this point in the procurement process, you may submit a Procurement-related Complaint challenging the decision to award the contract. You do not need to have requested, or received, a debriefing before making this complaint. Your complaint must be submitted within the Standstill Period and received by us before the Standstill Period ends.
- d) Further information: For more information refer to the Public Procurement and Disposals Act 2015 and its Regulations a vailable from the Website <a href="https://www.ppra.go.ke">www.ppra.go.ke</a>.

You should read these documents before preparing and submitting your complaint.

- e) There are four essential requirements:
  - You must be an 'interested party'. In this case, that means a Tenderer who submitted a Tender in this tendering process and is the recipient of a Notification of Intention to Award.
  - ii) The complaint can only challenge the decision to award the contract. iii) You must submit the complaint within the period stated above. iv) You must include, in your complaint, all of the information required to support your complaint.

#### 7. Standstill Period

- i) DEADLINE: The Standstill Period is due to end at midnight on [insert date] (local time).
- ii) The Standstill Period lasts ten (14) Days after the date of transmission of this Notification of Intention to Award.
- iii) The Standstill Period may be extended as stated in paragraph Section 5(d) above.

If you have any questions regarding this Notification please do not hesitate to contact us. On behalf of the Procuring Entity:

Signature:			
Name:			
Title/position:			
Telephone:			

# FORM NO. 2- REQUEST FOR REVIEW

## FORM FOR REVIEW (r.203(1))

PUBLIC PROCUREMENT ADMINISTRATIVE REVIEW BOARD
APPLICATION NOOF20 BETWEEN
APPLICANT
AND
RESPONDENT (Procuring Entity)
Request for review of the decision of the
REQUEST FOR REVIEW
I/We
1.
2.
By this memorandum, the Applicant requests the Board for an order/orders that:
1.
2.
SIGNED(Applicant) Dated onday of/20
FOR OFFICIAL USE ONLY Lodged with the Secretary Public Procurement Administrative Review Board onday of20
SIGNED
Board Secretary

## FORM NO 4: CONTRACT AGREEMENT

	y"), of the one part, and of of (hereinafter "the Procuring of of of (hereinafter of of of of (hereinafter of
"th	e Contractor"), of the other part:
exe	IEREAS the Procuring Entity desires that the Worksknownasshould be cuted by the Contractor, and has accepted a Tender by the Contractor for the execution and completion of these rksand the remedying of any defects there in,
The	e Procuring Entity and the Contractor agree as follows:
1.	In this Agreement words and expressions shall have the same meanings as are respectively assigned to them in the Contract documents referred to.
2.	The following documents shall be deemed to form and be read and construed as part of this Agreement. This Agreement shall prevail over all other Contract documents.
	a) the Notification of Award b) the Form of Tender c) the addenda Nos(if any) d) the Special Conditions of Contract e) the General Conditions of Contract; f) the Specifications g) the Drawings; and
	h) the completed Schedules and any other documents forming part of the contract.
3.	In consideration of the payments to be made by the Procuring Entity to the Contractor as specified in this Agreement, the Contractor here by covenants with the Procuring Entity to execute the Works and to remedy defects therein in conformity in all respects with the provisions of the Contract.
4.	The Procuring Entity here by covenants to pay the Contractor in consideration of the execution and completion of the Works and the remedying of defects there in, the Contract Price or such other sum as may become payable under the provisions of the Contract at the times and in the manner prescribed by the Contract.
	INWITNESS where of the parties here to have caused this Agreement to be executed in accordance with the Laws of Kenya on the day, month and year specified above.
	Signeda nd sealed by(for the Procuring Entity)
	Signed and sealed by(for the Contractor).
FO	RM NO. 5 - PERFORMANCE SECURITY
[ <b>O</b> ]	otion 1 - Unconditional Demand Bank Guarantee]
	uarantor letterhead]
Bei	neficiary: [insert name and Address of Procuring Entity]
Date	: [Insert date of issue]

Guarantor: [Insert name a	nd address o	of place of issue,	unless indicated in the	letterhead]
---------------------------	--------------	--------------------	-------------------------	-------------

1.	We have been informedthat (hereinafter called "the Contractor") has entered into Contract No. dated
	with (name of Procuring Entity) (the Procuring Entity as the Beneficiary), for the execution of (hereinafter called "the Contract").
2.	Furthermore, we understand that, according to the conditions of the Contract, a performance guarantee is required.
3.	Atthe request of the Contractor, we as Guarantor, here by irrevocably undertake to pay the Beneficiary any sum or sums not exceeding in total an amount of (in words), such sum being payable in the types and proportions of currencies in which the Contract Price is payable, upon receipt by us of the Beneficiary's complying demand supported by the Beneficiary's statement, whether in the demand it self or in a separate signed document accompanying or identifying the demand, stating that the Applicant is in breach of its obligation(s) under the Contract, without the Beneficiary needing to prove or to show grounds for your demand or the sum specified therein.
4.	This guarantee shall expire, no later than the
5.	The Guarantor agrees to a one-time extension of this guarantee for a period not to exceed [six months] [one

[Name of Authorized Official, signature(s) and seals/stamps]

*Note:* All italicized text (including footnotes) is for use in preparing this form and shall be deleted from the final product.

year], inresponse tot he Beneficiary's written request for such extension, such request to be presented to the

Guarantor before the expiry of the guarantee."

<sup>&</sup>lt;sup>7</sup> The Guarantor shall insert an amount representing the percentage of the Accepted Contract Amount specified in the Letter of Acceptance, less provisional sums, if any, and denominated either in the currency of the Contract or a freely convertible currency acceptable to the Beneficiary.

<sup>§</sup> Insert the date twenty-eight days after the expected completion date as described in GC Clause 11.9. The Procuring Entity should note that in the event of an extension of this date for completion of the Contract, the Procuring Entity would need to request an extension of this guarantee from the Guarantor. Such request must be in writing and must be made prior to the expiration date established in the guarantee.

## FORM No. 6- PERFORMANCE SECURITY

day \_\_\_\_\_of \_\_\_\_\_\_20\_\_\_\_.

#### [Option 2- Performance Bond]

[Note: Procuring Entities a readvised to use Performance Security – Unconditiona lDemand Bank Guarantee in stead of Performance Bond due to difficulties involved in calling Bond holder to action]

J	
[G	uarantor letterhead or SWIFT identifier code]
Ben	eficiary: [insertnameandAddressofProcuringEntity]
Date	:[Insert date of issue]
PEF	FORMANCE BONDNo.:
Gı	arantor: [Insert name and address of place of issue, unless indicated in the letterhead]
1.	By this Bond as Principal (hereinafter called "the Contractor") and as Surety (hereinafter called
	"the Surety"), are held and firmly bound unto_] as Obligee (hereinafter called "the Procuring Entity") in the amount offor the payment of which sum well and truly to be made in the types and proportions of currencies in which the Contract Price is payable, the Contractor and the Surety bind themselves, their heirs, executors, administrators, successors and assigns, jointly and severally, firmly by these presents.
2.	WHEREAS the Contractor has entered into a written Agreement with the Procuring Entity dated the day of ,20, for in accordance with the documents, plans, specifications, and amendments there to, which to the extent here in provided for, are by reference made part here of and are here in after referred to as the Contract.
3.	NOW, THEREFORE, the Condition of this Obligation is such that, if the Contractor shall promptly and faithfully perform the said Contract (including any amendments thereto), then this obligation shall be null and void; otherwise, it shall remain in full force and effect. Whenever the Contractor shall be, and declared by the Procuring Entity to be, in default under the Contract, the Procuring Entity having performed the Procuring Entity's obligations there under, the Surety may promptly remedy the default, or shall promptly: a) Complete the Contract in accordance with its terms and conditions; or
	b) Obtain a tender or tenders from qualified tenderers for submission to the Procuring Entity for completing the Contract in accordance with its terms and conditions, and upon determination by the Procuring Entity and the Surety of the lowest responsive Tenderers, arrange for a Contract between such Tenderer, and Procuring Entity and make a vailable as work progresses (even though there should be a default or a succession of defaults under the Contract or Contracts of completion arranged under this paragraph) sufficient funds to pay the cost of completion less the Balance of the Contract Price; but not exceeding, including other costs and damages for which the Surety may be liable hereunder, the amount set forth in the first paragraph hereof. The term "Balance of the Contract Price," as used in this paragraph, shall mean the total amount payable by Procuring Entity to Contractor under the Contract, less the amount properly paid by Procuring Entity to Contractor; or
	c) Pay the Procuring Entity the amount required by Procuring Entity to complete the Contract in accordance with its terms and conditions upto a total not exceeding the amount of this Bond.
4.	The Surety shall not be liable for a greater sum than the specified penalty of this Bond.
5.	Any suit under this Bond must be instituted before the expiration of one year from the date of the issuing of the Taking-Over Certificate. No right of action shall accrue on this Bond to or for the use of any person or corporation other than the Procuring Entity named here in or the heirs, executors, administrators, successors, and assigns of the Procuring Entity.

6. In testimony whereof, the Contractor has here unto set his hand and affixed his seal, and the Surety has caused these presents to be sealed with his corporate seal duly at tested by the signature of his legal representative, this

SIGNED ON	on behalf of
By	in the capacity of
Inthepresenceof	
SIGNED ON	on behalf of
Ву	in the capacity of
Inthepresence of	

## FORM NO. 7 - ADVANCE PAYMENT SECURITY

-	emand Bank Guarantee] uarantor letterhead]
-	neficiary:[Insert name and Address of ProcuringEntity]
	[Insert date of issue]
	VANCE PAYMENT GUARANTEE No.: [Insert guarantee reference number]
Gu	narantor: [Insert name and address of place of issue, unless indicated in the letterhead]
1.	We have been informed that(hereinafter called "the Contractor") has entered into Contract  Nodatedwith the Beneficiary, for the execution of  (hereinafter called" the Contract").
2.	Furthermore, we understand that, according to the conditions of the Contract, an advance payment in the sum(in words) is to be made against an advance payment guarantee.
3.	At the request of the Contractor, we as Guarantor, here by irrevocably undertake to pay the Beneficiary any sum or sums not exceeding in total an amount of (in words
4.	A demand under this guarantee may be presented as from the presentation to the Guarantor of a certificate from the Beneficiary's bank stating that the advance payment referred to above has been credited to the Contractor on its account numberat
5.	The maximum amount of this guarantee shall be progressively reduced by the amount of the advance payment repaid by the Contractor as specified in copies of interim statements or payment certificates which shall be presented to us. This guarantee shall expire, at the latest, upon our receipt of a copy of the interim payment certificate indicating that ninety (90) percent of the Accepted Contract Amount, less provisional sums, has been certified for payment, oronthe_dayof_,2
6.	The Guarantor agrees to a one-time extension of this guarantee for a period not to exceed [six months] [one year], in response to the Beneficiary's written request for such extension, such request to be presented to the Guarantor before the expiry of the guarantee.
	[Name of Authorized Official, signature(s) and seals/stamps]  Note: All italicized text (including footnotes) is for use in preparing this form and shall be deleted from the final product.

<sup>&</sup>lt;sup>9</sup> The Guarantor shall insert an amount representing the amount of the advance payment and denominated either in the currency of the advance paymen tas specified in the Contract.

<sup>&</sup>lt;sup>10</sup> Insert the expected expiration date of the Time for Completion. The Procuring Entity should note that in the event of an extension of the time for completion of the Contract, the Procuring Entity would need to request an extension of this guarantee from the Guarantor. Such request must be in writing and must be made prior to the expiration date established in the guarantee.

## FORM NO. 8 – RETENTION MONEY SECURITY

•	emand Bank Guarantee] uarantor letterhead]
_	neficiary: [Insert name and Address of Procuring Entity]
Da	te:[Insert date of issue]
Ad	vance payment guarantee no. [Insert guarantee reference number]
Gı	arantor: [Insert name and address of place of issue, unless indicated in the letterhead]
1.	We have been informed that <code>_[insert name of Contractor, which in the case of a joint venture shall be the name of the joint venture]</code> (hereinafter called "the Contractor") has entered into Contract No. <code></code>
2.	Furthermore, we understand that, according to the conditions of the Contract, the Beneficiary retains moneys upto the limit set forth in the Contract ("the Retention Money"), and that when the Taking-Over Certificate has been issued under the Contract and the first half of the Retention Money has been certified for payment, and payment of [insert the second half of the Retention Money] is to be made against a Retention Money guarantee.
3.	At the request of the Contractor, we, as Guarantor, hereby irrevocably undertake to pay the Beneficiary any sum or sums not exceeding in total an amount of [insert amount in figures]
4.	A demand under this guarantee may be presented as from the presentation to the Guarantor of a certificate from the Beneficiary's bank stating that the second half of the Retention Money as referred to above has been credited to the Contractor on its account numberat [insert name and address of Applicant's bank].
5.	This guarantee shall expire no later than the
6.	The Guarantor agrees to a one-time extension of this guarantee for a period not to exceed [six months] [one year], in response to the Beneficiary's written request for such extension, such request to be presented to the Guarantor before the expiry of the guarantee.
	[Name
	of Authorized Official, signature(s) and seals/stamps]

*Note:* All italicized text (including footnotes) is for use in preparing this form and shall be deleted from the final product.

The Guarantor shall insert an amount representing the amount of the second half of the Retention Money.

<sup>2</sup>Insert a date that is twenty-eight days after the expiry of retention period after the actua lcompletion date of the contract. The Procuring Entity should note that in the event of an extension of this date for completion of the Contract, the Procuring Entity would need to request an extension of this guarantee from the Guarantor. Such request must be in writing and must be made prior to the expiration date established in the guarantee.

#### FORM NO. 9 BENEFICIAL OWNERSHIP DISCLOSURE FORM

(Amended and issued pursuant to PPRA CIRCULAR No. 02/2022)

#### INSTRUCTIONS TO TENDERERS: DELETE THIS BOX ONCE YOU HAVE COMPLETED THE FORM

This Beneficial Ownership Disclosure Form ("Form") is to be completed by the successful tenderer pursuant to Regulation 13 (2A) and 13 (6) of the Companies (Beneficial Ownership Information) Regulations, 2020. In case of joint venture, the tenderer must submit a separate Form for each member. The beneficial ownership information to be submitted in this Form shall be current as of the date of its submission.

For the purposes of this Form, a Beneficial Owner of a Tenderer is any natural person who ultimately owns or controls the legal person (tenderer) or arrangements or a natural person on whose behalf a transaction is conducted, and includes those persons who exercise ultimate effective control over a legal person (Tenderer) or arrangement.

Tender Reference No.:	[insert identification no]
Name of the Tender Title/Description:_	[insert name of the assignment] to:
	[insert complete name of Procuring Entity]

In response to the requirement in your notification of award dated\_[insert date of notification of award] to furnish additional information on beneficial ownership:\_[select one option as applicable and delete the options that are not applicable]

I)	We here by provide the follo	wing beneficial ownership	n information. Details	of Beneficial ownership
11	We here by provide the folio	will good clicite and ownership	p illioillianoll. <b>Details</b>	or Denemeral ownership

	Details of all Beneficial Owners	% of shares a person holds in the company Directly or indirectly	% of voting rights a person holds in the company	Whether a person directly or indirectly holds a right to appoint or remove a member of the board of directors of the company or an equivalent governing body of the Tenderer (Yes / No)	Whether a person directly or indirectly exercises significant influence or control over the Company (tenderer) (Yes / No)
	Full Name	Directly	Directly	1. Having the right to appoint a majority of	1. Exercises significant influence or control
1.	National identity card number or Passport number	of shares	% of voting rights	the board of the directors or an equivalent governing	over the Company body of the Company (tenderer)
	Personal Identification Number (where applicable)	Indirectly % of shares	Indirectly % of voting rights	Indirectly % of voting rights	YesNo Yes  2. Is this right held directly or indirectly?: 2. Is
	Nationality				directly or
	Date of birth [dd/mm/yyyy]			Direct	indirectly?  Direct
	Postal address			T. P. A.	
	Residential address			Indirect	Indirect
	Telephone number				
	Email address				
	Occupation or profession				

	Details of all Benefic	ial Owners	% of shares a person holds in the company Directly or indirectly	% of voting rights a person holds in the company	Whether a person directly or indirectly holds a right to appoint or remove a member of the board of directors of the company or an equivalent governing body of the Tenderer (Yes / No)	Whether a person directly or indirectly exercises significant influence or control over the Company (tenderer) (Yes / No)
2.	Full Name  National identity card number or Passport number  Personal Identification Number (where applicable)  Nationality(ies)  Date of birth [dd/mm/yyyy]  Postal address  Residential address  Telephone number  Email address  Occupation or profession		Directly of shares  Indirectly % of shares	Directly % of voting rights  Indirectly % of voting rights	1. Having the right to appoint a majority of the board of the directors or an equivalent governing body of the Tenderer: YesNo  2. Is this right held directly or indirectly?:  Direct	
3.						
e.t .c			_			

- II) Am fully aware that beneficial ownership information above shall be reported to the Public Procurement Regulatory Authority together with other details in relation to contract awards and shall be maintained in the Government Portal, published and made publicly available pursuant to Regulation 13(5) of the Companies (Beneficial Ownership Information) Regulations, 2020.(Notwithstanding this paragraph Personally Identifiable Information in line with the Data Protection Act shall not be published or made public). Note that Personally Identifiable Information (PII) is defined as any information that can be used to distinguish one person from another and can be used to deanonymize previously anonymous data. This information includes National identity card number or Passport number, Personal Identification Number, Date of birth, Residential address, email address and Telephone number.
- III) In determining who meets the threshold of who a beneficial owner is, the Tenderer must consider a natural person who in relation to the company:

- (a) holds at least ten percent of the issued shares in the company either directly or indirectly;
- (b) exercises at least ten percent of the voting rights in the company either directly or indirectly;
- (c) holds a right, directly or indirectly, to appoint or remove a director of the company; or
- (d) exercises significant influence or control, directly or indirectly, over the company.
- IV) What is stated to herein above is true to the best of my knowledge, information and belief.

Name of the Tenderer:*[insert complete name of the Tenderer]
Name of the person duly authorized to sign the Tender on behalf of the Tenderer: ** [insert complete name of
person duly authorized to sign the Tender]
Designation of the person signing the Tender: [insert complete title of the person signing the Tender]
Signature of the person named above: [insert signature of person whose name and capacity are
shown above]
Date this

Bidder Official Stamp





# PARTICULAR PRELIMINARIES

ITEM	DESCRIPTION	AMOUNT (Kshs.)
A	PARTICULAR PRELIMINARIES EMPLOYER	
	State Department For Co-operatives Ministry of Cooperatives and MSMES Development	
	The term "Employer" and "Government" wherever used in the contract document shall be synonymous	
В	LOCATION OF SITE The site of the proposed works is- Along Likoni Lunga Lunga Rd, Kinondo, Kwale County The Contractor is advised to visit the site, to familiarize with the nature and position of the site. No claims arising from the Contractor's failure to do so will be entertained.	
C	DESCRIPTION OF THE WORKS  The works to be carried out under this contract comprise  Construction of 1no. gin house of plinth area 640sm & 1no store of plinth area 560sm, comprising of substructure, reinforced concrete frame, structural steel frame &roof structure with galvanised iron sheets roof cover, timber & metal doors, steel casement windows, masonry walling and fair faced concrete floor finish, inclusive of associated mechanical, electrical and civil engineering works; all as documented in the bills of quantities.	
D	FORM OF CONTRACT The Form of Contract shall be as stipulated in the Republic of Kenya's Standard Tender Document for Procurement of Building Works(2015 Edition) included herein.Particulars of insertions to be made in the Appendix to the Contract Agreement will be found in the Particular Preliminaries part of these Bills of Quantities	
E		
	BID BOND	
	A bid bond shall be required in the amount stated here or in the invitation to tender or advertisement	
	Bid bond shall be from EITHER an insurance or bank.	

F	CLEARING AWAY	
	The Contractor shall remove all temporary works, rubbish, debris and surplus materials from the site as they accumulate and upon completion of the works, remove and clear away all plant, equipment, rubbish, unused materials and stains and leave in a clean and tidy state to the reasonable satisfaction of the Project Manager.	
	The whole of the works shall be delivered up clean, complete and in perfect condition in every respect to the satisfaction of the Project Manager.	
	Total carried to summary	
	Total carried to summary	

ITEM	DESCRIPTION	AMOUNT (Kshs.)
A		
	WORKING CONDITIONS  These are works to be undertaken in an existing building.  The contractor must allow for compliance with all County & Civic Authority laws & regulations	
В	CLAIMS	
	It shall be a condition of this contract that upon it becoming reasonably apparent to the Contractor that he has incurred losses and/or expenses due to any of the contract conditions, or by any other reason whatsoever, he shall present such claim or intent to claim notice to the PROJECT MANAGER within the contract period. No claims shall be entertained upon the expiry of the said contract period.	
C	LABOUR CAMPS The Contractor shall not be allowed to house labour on site. Allow for transporting workers to and from the site during the tenure of the contract.	
D	PRICING RATES  The tenderer shall fill in rates and prices for all items of the Works described in the Bill of Quantities.	
	Items for which no rate or price is entered by the tenderer will not be paid for when executed and shall be deemed covered by the other rates and prices in the Bill of Quantities.	
	The tenderer shall include for all costs in executing the whole of the works, including transport, replacing damaged items, fixing, all to comply with the said Conditions of Contract.	
	Prices quoted should be net inclusive of all taxes, must be in Kenya shillings Prices shall remain valid for One Hundred and twenty (120) days from the closing date of tender.	
	The rates and prices quoted by the tenderer shall only be subject to adjustment during the performance of the Contract if provided for in the Appendix to Conditions of Contract and provisions made in the Conditions of Contract.	

E	MATERIALS FROM DEMOLITIONS  Any materials arising from demolitions SHALL NOT BE re-used shall become the property of the client unless otherwise advised.	
177	URGENCY OF THE WORKS	
F	The Contractor is notified that these "works are urgent" and should be completed within the period stated in these Particular Preliminaries. The Contractor shall allow in his rates for any costs he deems that he/she may incur by having to complete the works within the stipulated contract period.	
	Total carried to summary	

ITEM	DESCRIPTION	AMOUNT (Kshs.)
A		
	PAYMENTS GENERALLY The contractor is advised to deliver & concur on his claim for payment with the PM before the following site visit to enable approval of the same by the Acceptance & Approval Committee.	
	The claim shall be prepared in the same format as these bills clearly showing quantities & rates (both work & materials).	
	Both the PM & contractor should be able to locate & identify the items claimed from the main bill.	
n	The last contractual claim/invoice for the relevant financial year should reach the PM by 30th May. Latter claims shall not be processed for payment in the current year.	
В	PAYMENT FOR MATERIALS ON SITE	
	All materials for incorporation in the works must be stored on site before payment is effected, unless specifically exempted by the Project Manager. This is to include materials of the Contractor, nominated sub-Contractors and nominated suppliers.	
C	ADVANCE PAYMENTS  The tenderer's attention if drawn to the fact that the Government does not make any advance payments.	
D	EXISTING SERVICES	
	Prior to the commencement of any work, the Contractor is to ascertain from the relevant authority the exact position, depth and level of all existing services in the area and he/she shall make whatever provisions may be required by the authorities concerned for the support, maintenance and protection of such services.	

E	TENDER DOCUMENTS  Tender documents are as listed in Clause 6 of the Instruction to Tenderer's Page 9	
F	Tender documents are as listed in Clause 6 of the Instruction to Tenderer's Page 9  DELIVERY OF TENDER  Tenders and all documents in connection therewith, as specified above must be delivered in the addressed envelope which should be properly—sealed and deposited at the offices as specified in the letter accompanying these documents or as indicated in the advertisement.  Tenders will be opened at the time specified in the letter accompanying these Tender Documents or as indicated in the advertisement. Tenders delivered/received later than the above time will not be opened.	
	Total carried to summary	

ITEM	DESCRIPTION	AMOUNT (Kshs.)
A		
	MEASUREMENTS	
	In the event of any discrepancies arising between the Bills of Quantities and the actual works, the site measurements shall generally take precedence. However, such discrepancies between any contract documents shall immediately be referred to the PROJECT MANAGER in accordance with Clause 12 of the Conditions of Contract. The discrepancies shall then be treated as a variation and be dealt with in accordance with Clause 12 of the said Conditions.	
В	VALUE ADDED TAX	
	The Contractor's attention is drawn to the Legal Notice in the Finance Act part 3 Section 21(b) operative from 1 <sup>st</sup> September, 1993 which requires payment of VAT on all In accordance with Government public notice No. 35 & 36 Dated 11th September 2003 operational from 1st October 2003, withholding VAT was to be levied against the contract sum by the Employer and remitted to the Commissioner of VAT through all interim certificates.	
C	THE CURRENT LAWS ON THIS SUBJECT SHALL APPLY The contractor should include this tax in the RATES and NOT in the Grand Summary.	

D	SUBSISTENCE ALLOWANCES, AIRTIME, STATIONERY & TRAINING	5,000,000.00
	Allow a provisional Sum of Kenya Shillings Five Million(KShs. 5,000,000) only for subsistence allowances & airtime allowance of the Projects Manager's to be expended as directed by the PM	
	Allow a percentage sum for the contractors administrative costs, profits and taxes for the above (%)	
E	STATIONERY	
	Allow a provisional Sum of Kenya Shillings Three Hundred Thousand(Kshs.300,000) only for supply and delivery of Project Managers Stationery to be expended as directed by the PM	300,000.00
	Allow a percentage sum for the contractors administrative costs, profits and taxes for the above (%)	
F	CPD TRAINING	
	Allow a provisional Sum of Kenya Shillings One Million(Kshs.1,000,000) only for officers CPD Training to be expended as directed by the PM	1,000,000.00
	Allow a percentage sum for the contractors administrative costs, profits and taxes for the above (%)	
G	CLERK OF WORKS EXPENSES	300,000.00
	Allow a sum of Kenya Shilling Three Hundred Thousand(KShs. 300,000.00) only for Clerk of Works allowances	
	Allow a percentage sum for the contractors administrative costs, profits and taxes for the above (%)	
	Total carried to summary	

ITEM	DESCRIPTION	AMOUNT (Kshs.)
	PARTICULARS OF INSERTIONS TO BE MADE IN APPENDIX TO CONTRACT AGREEMENT	
	The following are the insertions to be made in the appendix to the contract Agreement:-	
A	Period of Final Measurement 3 Months from Practical Completion	
В	Defects Liability Period 6 Months from Practical Completion	
С	Date for Possession To be agreed with the Project Manager	
D	Date for Completion Sixteen 36 WEEKS from the Date of possession	
Е	Liquidated and Ascertained Damages  At a rate of 0.005% of the contract price per day	

F	Period of Interim Certificates	Monthly	
G	Period of Honouring Certificates	30 Days	
Н	Percentage of Certified Value Retained 10%		
I	Limit of Retention Fund 5%		
		Total carried to summary	

ITEM	DESCRIPTION	AMOUNT (Kshs.)
	<u>SUMMARY</u>	
	Brought forward from page PP/1	
	Brought forward from page PP/2	
	Brought forward from page PP/3	
	Brought forward from page PP/4	

Brought forward from page PP/5	
TOTAL CARRIED TO CRAND CHARLEN	
TOTAL CARRIED TO GRAND SUMMARY	

# **GENERAL PRELIMINARIES**

ITEM	DESCRIPTION	AMOUNT (Kshs.)
Α.	GENERAL PRELIMINARIES PRICING OF ITEMS OF PRELIMINARIES AND PREAMBLES	
	Prices will be inserted against items of Preliminaries in the Contractor's priced Bills of Quantities and Specification.	
	The Contractor shall be deemed to have included in his prices or rates for the various items in the Bills of Quantities or Specification for all costs involved in complying with all the requirements for the proper execution of the whole of the works in the Contract.	
	Failure to price an item shall not exempt the contractor form carrying out works described therein.	
	Should the contractor fail to carry out works which he/she did not price and after having received a written instruction from the PM, then the value of such works shall be deducted from the very immediate certificate issued to the contractor.	
	MoPW current rates, IQSK, manufacturers or fair rates shall be used by the PM in valuation of unpriced items which the contractor shall fail to execute.	
	The contractor is advised to read and understand all preliminary items.  The Contractor is advised to visit the site, to familiarize with the nature and position of the site. No claims arising from the Contractor's failure to do so will be entertained.	
В	FIRM PRICE CONTRACT Unless otherwise specifically stated in the Contract Data and/or Particular preliminaries this is a firm price contract and the contractor must allow in his tender rates for any increase in the cost of labour and/or materials during the currency of the contract.	

C	VISIT SITE AND EXAMINE DRAWINGS.	
	The Contractor is recommended to examine the drawings and visit the site the location of which is described in the Particular Preliminaries hereof. He shall be deemed to have acquainted himself therewith as to its nature, position, means of access or any other matter which, may affect his tender. No claim arising from his failure to comply with this recommendation will be considered.	
	Total carried to summary	

ITEM	DESCRIPTION	AMOUNT (Kshs.)
A	BONDS.	
	The Contractor shall find and submit on the Form of Tender a guarantor and who will be willing to be bound the Government in the amount of the bond.	
	The amount of the bond is SPECIFIED IN THE PARTICULAR PRELIMINARIES  The guarantor shall be an approved institution as specified in the particular	
	preliminaries or invitation to tender and who will when and if called upon, sign a Bond to that effect on the relevant standard form included herein. (without the addition of any limitations) on the same day as the Contract Agreement is signed, by the Government, the	
	Contractor shall furnish within seven days another Surety to the approval of the Government.	

В	PERFORMANCE BOND  Derformance Bond against to 5% of the contract sum will be required in accordance.	
	Perfomance Bond equaivalent to 5% of the contract sum will be required in accordance with clause 48 of the Instruction to Tenderers	
	The period for supplying the bond shall be within 21 days of the receipt of the letter of award from the Procuring Entity	
	No contract shall besigned, NOR shall any payment bemade before the bidder has complied with the bond requirements	
	Failure to deliver the bond within the specified period shall automatically disqualify the bidder and the tender shall be awarded to next most reponsive bidder without reference to the defaulting bidder.  Should the bidder commence works and subsequently fail to provide the bond, he shall be	
	evicted from site without any reimbursement not withstanding the site having been handed over by the PM and client. The handing over only kickstarts the process and is not a waiver to bond conditions.	
	The bond for the due performances of the Contract shall be valid up to the date of completion as certified by the PROJECT MANAGER	
	Any bond which provides otherwise or attempts to vary the duration of validity shall be invalid	
	The bond shall comply in all respects with the PPRA copy enclosed in the instructions to tender. A bond that does not match the PPRA copy shall be treated as NO BOND	
	The contractor shall provide a bid security duly signed, sealed and stamped from an approved Bank of required amount in the particular preliminaries	
	Total carried to summary	
A	EXCEPTION TO THE STANDARD METHOD OF MEASUREMENT	

I	ГЕМ	DESCRIPTION	AMOUNT	(Kshs.)	ı
---	-----	-------------	--------	---------	---

**Attendance**; Clause B19(a) of the Standard Method of Measurement is deleted and the following clause is substituted:-

Attendance on nominated Sub-Contractors shall be given as an item in each case shall be deemed to include: allowing use of standing scaffolding, mess rooms, sanitary accommodation and welfare facilities; provision of special scaffolding where necessary; providing space for office accommodation and for storage of plant and materials; providing light and water for their work: clearing away rubbish; unloading checking and hoisting: providing electric power and removing and replacing duct covers, pipe casings and the like necessary for the execution and testing of Sub-Contractors' work and being responsible for the accuracy of the same.

### Fix Only:-

"Fix Only" shall mean take delivery at nearest railway station (Unless otherwise stated), pay all demurrage charges, load and transport to site where necessary, unload, store, unpack, assemble as necessary, distribute to position, hoist and fix only.

#### B **ABBREVIATIONS**

Throughout these Bills units of measurement and terms are abbreviated and shall be interpreted as follows:-

CM or Cm Shall mean cubic meter
SM or Sm Shall mean square meter
LM or Lm Shall mean linear meter MM

or mm Shall mean Millimeter

KG or Kg.Shall mean KilogrammeNo or NrShall mean NumberPRS or Prs.Shall mean Pairs

B.S. Shall mean the British Standard Specification

Published by the British Standards Institution,

2 Park Street, London W.I England

M.S. Shall mean measured separately
Ditto shall mean the whole of the preceding description

except as qualified in the description in which it occurs. Do

shall mean the whole of the preceding description

except as qualified in the description in which it occurs. a.b.

Shall mean as before described

a.b.d. Shall mean as before described

**Total carried to summary** 

A	EMPLOYER	

ITEM	DESCRIPTION	AMOUNT (Kshs.)
	The "Employer" is AS DEFINED UNDER PARTICULAR PRELIMINARIES	
	The term "Employer" and "Government" wherever used in the contract document shall be synonymous	
В	PROJECT MANAGER shall be -: The term "P.M." wherever used in these Bills of Quantities shall be deemed to imply the Project Manager as defined in Condition 1 of the Conditions of Contract or such person or persons as may be duly authorised to represent him on behalf of the Government.	
	In this Project, the PM shall be -: WORKS SECRETARY M.O.T.I.P.W. H.&U.D (STATE DEPARTMENT FOR PUBLIC WORKS) P.O. BOX 30743-00100 NAIROBI	
C	ARCHITECT	
	The term "Architect" shall be deemed to mean "The P.M." as defined above whose address unless otherwise notified is as above	
D	QUANTITY SURVEYOR	
	The term "Quantity Surveyor" shall be deemed to mean "The P.M." as defined above whose address unless otherwise notified is as above	
E		
	ELECTRICAL ENGINEER	
	The term "Electrical Engineer" shall be deemed to mean "The P.M." as defined above whose address unless otherwise notified is as above	
F	MECHANICAL ENGINEER	
	The term "Mechanical Engineer" shall be deemed to mean "The P.M." as defined above whose address unless otherwise notified is as above	

G	STRUCTURAL ENGINEER	
	The term "Structural Engineer" shall be deemed to mean "The P.M." as defined above whose address unless otherwise notified is as above	
	Total carried to summary	
A	PLANT, TOOLS AND VEHICLES	

ITEM	DESCRIPTION	AMOUNT (Kshs.)
	Allow for providing all scaffolding, plant, tools and vehicles required for the worksexcept in so far as may be stated otherwise herein and except for such items specifically and only required for the use of nominated Sub-Contractors as described herein. No timber used for scaffolding, formwork or temporary works of any kind shall be used afterwards in the permanent work.	
В	TRANSPORT.	
	Allow for transport of workmen, materials, etc., to and from the site at such hours and by such routes as may be permitted by the competent authorities.	
С	MATERIALS AND WORKMANSHIP.  All materials and workmanship used in the execution of the work shall be of the best quality and description unless otherwise stated. The Contractor shall order all materials to be obtained from overseas immediately after the Contract is signed and shall also order materials to be obtained from local sources as early as necessary to ensure that they are onsite when required for use in the works. The Bills of Quantities shall not be used for the purpose of ordering materials.	
D	SIGN FOR MATERIALS SUPPLIED.  The Contractor will be required to sign a receipt for all articles and materials supplied by the PROJECT MANAGER at the time of taking deliver thereof, as having received them in good order and condition, and will thereafter be responsible for any loss or damage and for replacements of any such loss or damage with articles and/or materials which will be supplied by the PROJECT MANAGER at the current market prices including Customs Duty and V.A.T., all at the Contractor's own cost and expense, to the satisfaction of the PROJECT MANAGER	

E	STORAGE OF MATERIALS  The Contractor shall provide at his own risk and cost where directed on the site weather proof lock-up sheds and make good damaged or disturbed surfaces upon completion to the satisfaction of the PROJECT MANAGER Nominated Sub-Contractors are to be made liable for the cost of any storage accommodation provided especially for their use.
	Total carried to summary
A	SAMPLES

ITEM	DESCRIPTION	AMOUNT (Kshs.)
	The Contractor shall furnish at his own cost any samples of materials or workmanship	
	including concrete test cubes required for the works that may be called for by the	
	PROJECT MANAGER for his approval until such samples are approved by the	
	PROJECT MANAGER and the PROJECT MANAGER, may reject any materials or	
	workmanship not in his opinion to be up to approved samples. The PROJECT	
	MANAGER shall arrange for the testing of such materials as he may at his discretion	
	deem desirable, but the testing shall be made at the expense of the Contractor and not at	
	the expense of the PROJECT MANAGER PROVIDED THEY PASS THE TEST. The	
	Contractor shall pay for the testing in accordance with the current scale of testing charges	
	laid down by the Ministry of Public Works.	
	The procedure for submitting samples of materials for testing and the method of marking for identification shall be as laid down by the PROJECT MANAGER The Contractor shall allow in his tender for such samples and tests except those in connection with nominated sub-contractors' work.	
	Samples of paint, carpets, curtains & covers, tiles & timber shall be required for approval by the PM together with the employer.	
	No alternte rate shall be offered on account that the employer has chosen a superior finish unless the bidder had attached the sample he priced.	

В	PUBLIC AND PRIVATE ROADS.	
	Maintain as required throughout the execution of the works and make good any damage to public or private roads arising from or consequent upon the execution of the works to the satisfaction of the local and other competent authority and the PROJECT MANAGER	
C	<b>EXISTING PROPERTY.</b> The Contractor shall take every precaution to avoid damage to all existing property including roads, cables, drains and other services and he will be held responsible for and shall make good all such damage arising from the execution of this contract at his own expense to the satisfaction of the PROJECT MANAGER	
D	ACCESS TO SITE AND TEMPORARY ROADS.  Means of access to the Site shall be agreed with the PROJECT MANAGER prior to commencement of the work and Contractor must allow for building any necessary temporary access roads for the transport of the materials, plant and workmen as may be required for the complete execution of the works including the provision of temporary culverts, crossings, bridges, or any other means of gaining access to the Site. Upon completion of the works, the Contractor shall remove such temporary access roads; temporary culverts, bridges, etc., and make good and reinstate all works and surfaces disturbed to the satisfaction of the PROJECT MANAGER	
	Total carried to summary	
A	AREA TO BE OCCUPIED BY THE CONTRACTOR	

ITEM	DESCRIPTION	AMOUNT (Kshs.)
	The area of the site which may be occupied by the Contractor for use of storage and for the purpose of erecting workshops, etc., shall be defined on site by the PROJECT MANAGER	
В	SECURITY OF WORKS ETC.  The Contractor shall be entirely responsible for the security of all the works stores, materials, plant, personnel, etc., both his own and sub-contractors' and must provide all necessary watching, lighting and other precautions as necessary to ensure security against theft, loss or damage and the protection of the public.	
C	PROGRESS CHART.  The Contractor shall provide within two weeks of Possession of Site and in agreement with the PROJECT MANAGER a Progress Chart for the whole of the works including the works of Nominated Sub-Contractors; one copy to be handed to the PROJECT MANAGER and a further copy to be retained on Site. Progress to be recorded and chart to be amended as necessary as the work proceeds.	

INSURANCE The Contractor shall insure as required in Conditions No. 18 of the Conditions of Contract. No payment on account of the work executed will be made to the Contractor until he has satisfied the PROJECT MANAGER either by production of an Insurance Policy or and Insurance Certificate that the provision of the foregoing Insurance Clauses have been complied with in all respects. Thereafter the PROJECT MANAGER shall from time to time ascertain that premiums are duly paid up by the Contractor who shall if called upon to do so, produce the receipted premium renewals for the PROJECT MANAGER's inspection.	
CONTRACTOR'S SUPERINTENDENCE/SITE AGENT  The Contractor shall constantly keep on the works a literate English speaking Agent or Representative, competent and experienced in the kind of work involved who shall give his whole experience in the kind of work involved and shall give his whole time to the superintendence of the works. Such Agent or Representative shall receive on behalf of the Contractor all directions and instructions from the Project Manager and such directions shall be deemed to have been given to the Contractor in accordance with the Conditions of Contract.	
Total carried to summary	

ITEM	DESCRIPTION	AMOUNT (Kshs.)
A	PROVISIONAL WORK	
	All work described as "Provisional" in these Bills of Quantities is subject to	
	remeasurement in order to ascertain the actual quantity executed for which payment will	
	be made. All "Provisional" and other work liable to adjustment under this Contract shall	
	left uncovered for a reasonable time to allow all measurements needed for such	
	adjustment to be taken by the PROJECT MANAGER Immediately the work is ready for	
	measuring, the Contractor shall give notice to the PROJECT MANAGER. If the	
	Contractor makes default in these respects he shall if the PROJECT MANAGER so	
	directs uncover the work to enable all measurements to be taken and afterwards reinstate	
	at his own expense.	

В		
	PROVISIONAL SUMS.  The term "Provisional Sum" wherever used in these Bills of Quantities shall have the meaning stated in Section A item A7(i) of the Standard Method of Measurement. Such sums are net and no addition shall be made to them for profit.	
C		
	ADJUSTMENT OF PROVISIONAL SUMS.  In the final account all Provisional Sums shall be deducted and the value of the work properly executed in respect of them upon the PROJECT MANAGER's order added to the Contract Sum. Such work shall be valued, but should any part of the work be executed by a Nominated Sub-Contractor, the value of such work or articles for the work to be supplied by a Nominated Supplier, the value of such work or articles shall be treated as a P.C. Sum and profit and attendance comparable to that contained in the priced Bills of Quantities for similar items added.	
D	PRIME COST (OR P.C.) SUMS.  The term "Prime Cost Sum" or "P.C. Sum" wherever used in these Bills of Quantities shall have the meaning stated in Section A item A7 (ii) of the Standard Method of Measurement. Persons or firms nominated by the PROJECT MANAGER to execute work or to provide and fix materials or goods are described herein as Nominated SubContractors. Persons or firms so nominated to supply goods or materials are described herein as Nominated Suppliers.	
	Total carried to summarys	
A	ADJUSTMENT OF P.C. SUMS.	

ITEM	DESCRIPTION	AMOUNT	(Kshs.)	
------	-------------	--------	---------	--

In the final account all P.C. Sums shall be deducted and the amount properly expended upon the PROJECT MANAGER'S order in respect of each of them added to the Contract sum. The Contractor shall produce to the PROJECT MANAGER such quotations, invoices or bills, properly receipted, as may be necessary to show the actual details of the sums paid by the Contractor. Items of profit upon P.C. Sums shall be adjusted in the final account pro-rata to the amount paid. Items of "attendance" (as previously described) following P.C. Sums shall be adjusted pro-rata to the physical extent of the work executed (not pro-rata to the amount paid) and this shall apply even though the Contractor's priced Bill shows a percentage in the rate column in respect of them. Should the Contractor be permitted to tender and his tender be accepted of any work for which a P.C. Sum is included in these Bill of Quantities profit and attendance will be allowed at the same rate as it would be if the work were executed by a Nominated Sub-Contractor.

В

#### NOMINATED SUB-CONTRACTORS

When any work is ordered by the PROJECT MANAGER to be executed by nominated sub-contractors, the Contractor shall enter into sub-contracts and shall thereafter be responsible for such sub-contractors in every respect. Unless otherwise described the Contractor is to provide for such Sub-Contractors any or all of the facilities described in these Preliminaries. The Contractor should price for these with the nominated Subcontract Contractor's work concerned in the P.C. Sums under the description "add for Attendance".

A

#### **DIRECT CONTRACTS**

Notwithstanding the foregoing conditions, the Government reserves the right to place a "Direct Contract" for any goods or services required in the works which are covered by a P.C. Sum in the Bills of Quantities and to pay for the same direct. In any such instances, profit relative to the P.C. Sum the priced Bills of Quantities will be adjusted as described for P.C. Sums and allowed.

#### B ATTENDANCE UPON OTHER TRADESMEN, ETC.

The Contractor shall allow for the attendance of trade upon trade and shall afford any tradesmen or other persons employed for the execution of any work not included in this Contract every facility for carrying out their work and also for use of his ordinary scaffolding. The Contractor, however, shall not be required to erect any special scaffolding for them. The Contractor shall perform such cutting away for and making good after the work of such tradesmen or persons as may be ordered by the PROJECT MANAGER and the work will be measured and paid for to the extent executed at rates provided in these Bills.

Total carried to summary

# A OFFICE ETC. FOR THE PROJECT MANAGER

ITEM	DESCRIPTION	AMOUNT (Kshs.)
	The Contractor shall provide, erect and maintain where directed on site and afterwards dismantle the site office of the type noted in the Particular Preliminaries, complete with Furniture. He shall also provide a strong metal trunk complete with strong hasp and staple fastening and two keys. He shall provide, erect and maintain a lock-up type water or bucket closet for the sole use of the PROJECT MANAGER including making temporary connections to the drain where applicable to the satisfaction of Government and Medical Officer of Health and shall provide services of cleaner and pay all conservancy charges and keep both office and closet in a clean and sanitary condition from commencement to the completion of the works and dismantle and make good disturbed surfaces. The office and closet shall be completed before the Contractor is permitted to commence the works. The Contractor shall make available on the Site as and when required by the "PROJECT MANAGER" a modern and accurate level together with levelling staff, ranging rods and 50 metre metallic or linen tape.	
В		
В	WATER AND ELECTRICITY SUPPLY FOR THE WORKS  The Contractor shall provide at his own risk and cost all necessary water, electric light and power required for use in the works. The Contractor must make his own arrangements for connection to the nearest suitable water main and for metering the water used. He must also provide temporary tanks and meters as required at his own cost and clear away when no longer required and make good on completion to the entire satisfaction of the PROJECT MANAGER. The Contractor shall pay all charges in connection herewith. No guarantee is given or implied that sufficient water will be available from mains and the Contractor must make his own arrangements for augmenting this supply at his own cost. Nominated Subcontractors are to be made liable for the cost of any water or electric current used and for any installation provided especially for their own use.  SANITATION OF THE WORKS  The Sanitation of the works shall be arranged and maintained by the Contractor to the satisfaction of the Government and/or Local Authorities, Labour Department and the PROJECT MANAGER	
C	SUPERVISION AND WORKING HOURS  The works shall be executed under the direction and to the entire satisfaction in all respects of the PROJECT MANAGER who shall at all times during normal working hours have access to the works and to the yards and workshops of the Contractor and subContractors or other places where work is being prepared for the contract.	

D	PROTECTION OF THE WORKS.  Provide protection of the whole of the works contained in the Bills of Quantities, including casing, casing up, covering or such other means as may be necessary to avoid damage to the satisfaction of the PROJECT MANAGER and remove such protection when no longer required and make good any damage which may nevertheless have been done at completion free of cost to the Government.	
	Total carried to summary	
A	WORKS TO BE DELIVERED UP CLEAN	

ITEM	DESCRIPTION	AMOUNT (Kshs.)
	Clean and flush all gutters, rainwater and waste pipes, manholes and drains, wash (except where such treatment might cause damage) and clean all floors, sanitary fittings, glass inside and outside and any other parts of the works and remove all marks, blemishes, stains and defects from joinery, fittings and decorated surfaces generally, polish door furniture and bright parts of metalwork and leave the whole of the buildings watertight, clean, perfect and fit for occupation to the approval of the PROJECT MANAGER	
В	GENERAL SPECIFICATION.	
	For the full description of materials and workmanship, method of execution of the work and notes for pricing, the Contractor is referred to the Ministry of Roads and Public Works and Housing General Specification dated 1976 or any subsequent revision thereof which is issued as a separate document, and which shall be allowed in all respects unless it conflicts with the General Preliminaries, Trade Preambles or other items in these Bills of Quantities.	
C	TRAINING LEVY	
	The Contractor's attention is drawn to legal notice No. 237 of October, 1971, which requires payment by the Contractor of a Training Levy at the rate of 1/4 % of the Contract sum on all contracts of more than Kshs. 50,000.00 in value.	
D	MATERIALS ON SITE	
	All materials for incorporation in the works must be stored on or adjacent to the site before payment is effected unless specifically exempted by the PROJECT MANAGER. This includes the materials of the Main Contractor, Nominated Sub-Contractors and Nominated Suppliers.	

E		
	HOARDING The Contractor shall enclose the site or part of the works under construction with a hoarding 2400 mm high consisting of iron sheets on 100 x 50 mm timber posts firmly secured at 1800 mm centres with two 75 x 50 mm timber rails for a total length of approximately three hundred meters. The Contractor is in addition required to take all precautions necessary for the safe custody of the works,materials, plant, public and Employer's property on the site.	
F	ALTERATIONS TO BILLS, PRICING, ETC.  Any unauthorised alteration or qualification made to the text of the Bills of Quantities may cause the Tender to be disqualified and will in any case be ignored. The Contractor shall be deemed to have made allowance in his prices generally to cover any items against which no price has been inserted in the priced Bills of Quantities. All items of measured work shall be priced in detail and the Tenders containing Lump Sums to cover trades or groups of work must be broken down to show the price of each item before they will be accepted.	
	Total carried to summary	
A	MATERIALS ARISING FROM EXCAVATIONS	

ITEM	DESCRIPTION	AMOUNT (Kshs.)
В	Materials of any kind obtained from the excavations shall be the property of the Government. Unless otherwise provided for in the particular preliminaries. Such materials shall only be used in the works, in substitution of materials which the Contractor would otherwise have had to supply with the written permission of the PROJECT MANAGER Should such permission be given, the Contractor shall make due allowance for the value of the materials so used at a price to be agreed.  PREVENTION OF ACCIDENT, DAMAGE OR LOSS  The Contractor is notified that these works are to be carried out on a restricted site where the client is going on with other normal activities. The Contractor is instructed to take reasonable care in the execution of the works as to prevent accidents, damage or loss and disruption of normal activities being carried out by the Client. The Contractor shall allow in his rates any expense he deems necessary by taking such care within the site.	

C		
	GOVERNMENT ACTS REGARDING WORKPEOPLE ETC.  Allow for complying with all Government Acts, Orders and Regulations in connection with the employment of Labour and other matters related to the execution of the works. In particular the Contractor's attention is drawn to the provisions of the Factory Act 1950 and his tender must include for all costs arising or resulting from compliance with any Act, Order or Regulation relating to Insurances, pensions and holidays for workpeople or so the safety, health and welfare of the workpeople. The Contractor must make himself fully acquainted with current Acts and Regulations, including Police Regulations regarding the movement, housing, security and control of labour, labour camps, passes for transport, etc. It is most important that the Contractor, before tendering, shall obtain from the relevant Authority the fullest information regarding all such regulations and/or restrictions which may affect the information regarding all such regulations and/or restrictions which may affect the organisation of the works, supply and control of labour, etc., and allow accordingly in his tender.	
D	No claim in respect of want of knowledge in this connection will be entertained.  REMOVAL OF RUBBISH ETC.  Removal of rubbish and debris from the Buildings and site as it accumulates and at the completion of the works and remove all plant, scaffolding and unused materials at completion.	
C	BLASTING OPERATIONS  Blasting will only be allowed with the express permission of the PROJECT MANAGER in writing. All blasting operations shall be carried out at the Contractor's sole risk and cost in accordance with any Government regulations in force for the time being, and any special regulations laid down by the PROJECT MANAGER governing the use and storage of explosives.	
D	SIGNBOARD Allow for providing, erecting, maintaining throughout the course of the Contract and afterwards clearing away a signboard as designed, specified and approved by the Project Manager.	
	Total carried to summary	

ITEM	DESCRIPTION	AMOUNT (Kshs.)
	<u>SUMMARY</u>	
	Brought Forward From Page GP/1	
	Brought Forward From Page GP/2	
	Brought Forward From Page GP/3	
	Brought Forward From Page GP/4	

I		
]	Brought Forward From Page GP/5	
]	Brought Forward From Page GP/6	
]	Brought Forward From Page GP/7	
]	Brought Forward From Page GP/8	
]	Brought Forward From Page GP/9	
]	Brought Forward From Page GP/10	
]	Brought Forward From Page GP/11	
]	Brought Forward From Page GP/12	
	TOTAL CARRIED TO GRAND SUMMARY	

# **MAIN WORKS**

Item	Description	Qty	Unit	Rate	Amount KSh
	ELEMENT NO. 1				
	SUBSTRUCTURES (ALL PROVISIONAL)				
	<u>Site Clearance</u>				
A	Clear site of all shrubs, bushes and small trees and grub up roots, cart away to spoil heaps away from site	640	SM		
	Oversite excavation				
В	Excavate oversite to remove top soil average 200mm deep and keep on site for later re-use for landscaping	640	SM		
	Excavation				
С	Excavation for strip foundation commencing at reduced bulk excavation levels depth not exceeding 1.5M deep				
D	Tion deep	188	CM		
D	Excavation for bases commencing at reduced bulk excavation levels depth not exceeding 1.5M deep	113	СМ		
Е	Excavation for strip foundation depth exceeding 1.50M but not exceeding 3.0M deep	188	СМ		
F	Excavation for bases depth exceeding 1.50M but not exceeding 3.0M deep	113	СМ		
G	Extra over excavation in all types of rock	512	CM		
	Disposal of excavated material				
Н	Fillings aroundfdn: backfill and compact in 150 mm layers: selected excavated materials	370	СМ		
I	Remove surplus spoil from site to an authorized dumping site				
		250	CM		
	<u>Diposal of water</u>				
J	Keeping all excavations free from all water including spring or running water		ITEM		
	Carried to Collection				

Item	Description	Qty	Unit	Rate	Amount KSh
A	Planking and strutting  Uphold the sides of all excavations		ITEM		
В	Hardcore filling 300mm thick fillings in making up levels: levelled and compacted in 150 mm layers	640	SM		
С	50mm (average) thick quarry dust blinding to surfaces of hardcore	640	SM		
D	Selected imported material  Filling in making up levels under floors, spread levelled, well rammed and consolidated in 150mm layers.	889	СМ		
E	Antitermite treatment  Premise 200 CC' or other equal and approved anti-termite insecticide treatment with ten years guarantee, applied strictly in accordance with manufacturer's instructions, to tops of fill and foundation walls	741	CM		
	50mm thick mass concrete class Q(1:3:6) in:-	741	SM		
F	Column bases	77	SM		
G	Strip foundation	125	SM		
	Reinforced concrete; class 25/(20mm) mix (1:1.5:3); vibrated				
Н	Column bases	29	CM		
I	Strip foundations	25	СМ		
J	Foundation columns	17	СМ		
K	Ground beams	17	СМ		
L	200mm thick ground slab powefloated and hardened by approved admixtures	640	SM		
	Carried to Collection				

Item	Description	Qty	Unit	Rate	Amount KSh
	<u>Reinforcement</u>				
	Bars; high yield steel; cold worked to B.S. 4461 including				
	bends, hooks, tying wire and distance blocks				
A	8 mm diameter bars	3519	KG		
В	10 mm diameter bars	4106	KG		
С	12 mm diameter bars	2346	KG		
D	16-32 mm diameter bars	1760	KG		
	Sawn formwork to insitu concrete as described to :-				
E	Sides; vertical or battering of foundation columns	176	SM		
F	Sides and soffits of ground beams	190	SM		
G	Edges of ground floor slab; 150 to 225 mm high	117	LM		
Н	Sides; vertical or battering of foundations	84	SM		
I	Sides; vertical or battering of bases	78	SM		
	<u>Insitu Finishings</u>				
J	14mm thick 2No. coatwork cement sand(1:3) render; wood floated to concrete or blockwork base to walls; external				
		54	SM		
	Painting and Decorations				
	Prepare and apply three coats bituminous paint to:				
K	Wood floated rendered plinths over 300mm girth	54	SM		
	<u>Masonry</u>				
	200mm thick approved natural stone; local; roughly squared to foundation walling; bedding and jointing in cement sand (1:3) mortar including reinforcing with hoop iron ties every alternate course.				
L	200mm thick walling	570	SM		
	Carried to Collection				

A	DPM  1000 Cause approved polythere sheeting as demanding			
D	1000 Gauge approved polythene sheeting as damp proof membrane laid on blinded hardcore(measured separetely)with welted laps(measured net-no allowance made for laps)	741	SM	
В	BRC Fabric mesh reinforcement Ref. A193 with 200 mm laps (measured net; no allowances made for laps) to basement floor bed	1280	SM	
С	Expansion joint filler  Flexcell expansion joint filler 50x150mm deep  Expansion joint	500	LM	
D	50x25 mm approved mastic expansion joint sealer  Machine platform foundation	500	LM	
E F	Excavation for bases and stub columns commencing at reduced bulk excavation levels depth not exceeding 1.5M deep  Excavation for screw conveyor trench commencing	65	СМ	
G	at reduced excavation levels depth not exceeding 1.5M deep	139	СМ	
Н	Excavation for bases and stub columns depth exceeding 1.50M but not exceeding 3.0M deep  Extra over excavation in all types of rock	65 228	CM CM	
I	Disposal of excavated material  Fillings aroundfdn: backfill and compact in 150 mm layers: selected excavated materials  Remove curplus spoil from site to an authorized	170 110	CM CM	
J	Remove surplus spoil from site to an authorized dumping site  Carried to Collection	110	CIVI	

Item	Description	Qty	Unit	Rate	Amount KSh
	<u>Hardcore filling</u>				
A	300mm thick fillings in making up levels: levelled and				
	compacted in 150 mm layers	101	SM		
В		101	OIVI		
	50mm (average) thick quarry dust blinding to surfaces of hardcore				
		101	SM		
	50mm thick mass concrete class Q(1:3:6) in:-				
C	Column bases	44	SM		
	Column bases	44	JIVI		
	Reinforced concrete; class 25/(20mm) mix (1:1.5:3);				
	vibrated				
D	Column bases	14	СМ		
	Column buses	11	Civi		
E	Foundation columns	17	CM		
F					
	200mm thick ground slab powefloated and hardened by approved admixtures				
	approved damaxtures	101	SM		
	<u>Reinforcement</u>				
	Bars; high yield steel; cold worked to B.S. 4461 including				
	bends, hooks, tying wire and distance blocks				
G	8 mm diameter bars	1247	KG		
H I	10 mm diameter bars	1455 832	KG KG		
J	12 mm diameter bars 16-32 mm diameter bars	624	KG		
	10-32 Hill diameter bars	024	KG		
K	BRC Fabric mesh reinforcement Ref. A193 with 200 mm				
	laps (measured net ; no allowances made for laps) to basement floor bed				
	Dasement noor bed	101	SM		
	450mm thick mass concrete class Q(1:3:6) in:-				
,	Pall range machine has	140	CM f		
L	Bell press machine base	140	SM		
M	Ginning machine bases	60	SM		
	Thicknessing to slab drain of 300mm width, overall thickness;				
	mickiness,				
N	150mm thick slab thicknessed	117	LM		
	Carried to Collection				
				]	

Description	Qty	Unit	Rate	Amount KSh
Sawn formwork to insitu concrete as described to :-				
Sides; vertical or battering of foundation columns	144	SM		
Edges of plinths for machine bases; 375-450mm high	88	LM		
Sides; vertical or battering of screw conveyor trench	66	SM		
Sides; vertical or battering of bases	45	SM		
Carried to Collection				
COLLECTION				
From page GH/1				
From page GH/2				
From page GH/3				
From page GH/4				
From page GH/5				
From page above				
TOTAL FOR SUBSTRUCTURES CARRIED TO				
	Sawn formwork to insitu concrete as described to :- Sides; vertical or battering of foundation columns Edges of plinths for machine bases; 375-450mm high Sides; vertical or battering of screw conveyor trench Sides; vertical or battering of bases  Carried to Collection  COLLECTION  From page GH/2  From page GH/3  From page GH/5  From page GH/5  From page above	Sawn formwork to insitu concrete as described to :- Sides; vertical or battering of foundation columns  Edges of plinths for machine bases; 375-450mm high Sides; vertical or battering of screw conveyor trench Sides; vertical or battering of bases  Carried to Collection  COLLECTION  From page GH/1  From page GH/3  From page GH/5  From page GH/5  From page above	Sawn formwork to insitu concrete as described to:  Sides; vertical or battering of foundation columns  Edges of plinths for machine bases; 375-450mm high  Sides; vertical or battering of screw conveyor trench  66 SM  45 SM  Carried to Collection  COLLECTION  From page GH/2  From page GH/3  From page GH/5  From page GH/5  From page above	Sawn formwork to insitu concrete as described to:  Sides; vertical or battering of foundation columns  Edges of plinths for machine bases; 375-450mm high  Sides; vertical or battering of screw conveyor trench  Sides; vertical or battering of bases  Carried to Collection  COLLECTION  From page GH/2  From page GH/3  From page GH/5  From page above  TOTAL FOR SUBSTRUCTURES CARRIED TO

Item	Description Proposed G	Qty	Unit	Rate	Amount KSh
	ELEMENT NO. 2				
	REINFORCED CONCRETE FRAMING				
	KEINFORCED CONCRETE FRAMING				
	Reinforced concrete; class 25/(20mm) mix (1:1.5:3);				
Α	<u>vibrated</u> Beams	39	СМ		
Λ	Deants	39	Civi		
В	Columns	40	СМ		
С	Stairs	2	CM		
D	150mm thick Landing	6	SM		
	<u>Reinforcement</u>				
	Bars; high yield steel; cold worked to B.S. 4461 including				
	bends, hooks, tying wire and distance blocks				
Е	8 mm diameter bars	3374	KG		
F	10 mm diameter bars	3936	KG		
G	12 mm diameter bars	2249	KG		
Н	16-32 mm diameter bars	1687	KG		
	Sawn formwork to insitu concrete as describedto :-				
т.		407	CM		
I	To sides and soffits of beams.	406	SM		
J	Vertical sides of columns	405	SM		
,	0.0000 0.0000 0.00000000000000000000000	100	01,1		
K	Slopping soffits of stairs	7	SM		
	Risers				
L	-150 to 225mm high	24	LM		
	Edges of stairs				
M	-150 to 225mm high	8	LM		
N		6	SM		
1 1	To soffits of landing	U	0141		
	Edges of landing				
Ο	-150 to 225mm high	10	LM		
	TOTAL FOR RC FRAME CARRIED TO SUMMARY				
			<u> </u>		

ELEMENT NO. 3  STRUCTURAL STEEL FRAME  Supply, deliver to site and erect mild steel frame steelwork to B5 449 with and including welds and bolting connections. Rates to include for all materials labour, stiffeners, welding or bolts, wastage and cutting, drilling all gusset plates fastenings and connections and all other items necessary for satisfactory incorporation into works including wire brushing surfaces free from rust, steel to be painted with one coat an epoxy primer containing zinc chromate followed by two coats of masterseal SP 120 before fabrication and one other coat after fabrication(rates inclusive of painting)  Decking, decking beares and mild steel plates and bolts  Columns and posts, size  A -150x150X6mm x 27.13kg/m SHS  Beams, size  B -125x75x4mm SB 3,472 KG  C -150x100x4mm MB RHS 990 KG  D -75x75x4mm EA RSA 396 KG  E -300x300x10mm base plate bolted to reinforced concrete stub colums 34 No. 240 No. 340 N	Item	Description	Qty	Unit	Rate	Amount KSh
STRUCTURAL STEEL FRAME  Supply, deliver to site and erect mild steel frame steelwork to BS 449 with and including welds and bolting connections. Rates to include for all materials labour, stiffeners, welding or bolts, wastage and cutting, drilling all gusset plates fastenings and connections and all other items necessary for satisfactory incorporation into works including wire brushing surfaces free from rust, steel to be painted with one coat an epoxy primer containing zinc chromate followed by two coats of masterseal SP 120 before fabrication and one other coat after fabrication(rates inclusive of painting)  Decking, decking beares and mild steel plates and bolts  Columns and posts, size  -150X150X6mm x 27.13kg/m SHS  Beams, size  B -125x75x4mm SB 3,472 KG  C -150x100x4mm MB RHS 990 KG  D -75x75x4mm EA RSA 396 KG  E -300x300x10mm base plate bolted to reinforced concrete stub colums  F -5mm thick triangular stiffiner ms plate of base 75mm and height 75mm welded to base plate and SHS columns  I6 mm Diameter holding down RAG bolts with nut and washer fixed to reinforced concrete columns, length  G -600 mm 136 No.	Item	Description	Qty	Oilit	Rate	Amount Kon
Decking, decking beares and mild steel plates and bolts  Columns and posts , size - 150X150X6mm x 27.13kg/m SHS  Beams , size  B - 125x75x4mm SB		ELEMENT NO. 3  STRUCTURAL STEEL FRAME  Supply, deliver to site and erect mild steel frame steelwork to BS 449 with and including welds and bolting connections. Rates to include for all materials, labour, stiffeners, welding or bolts, wastage and cutting, drilling all gusset plates fastenings and connections and all other items necessary for satisfactory incorporation into works including wire brushing surfaces free from rust, steel to be painted with one coat an epoxy primer containing zinc chromate followed by two coats of masterseal SP 120 before fabrication and one other coat after fabrication (rates inclusive of				
Columns and posts , size  -150X150X6mm x 27.13kg/m SHS  Beams , size  B -125x75x4mm SB 3,472 KG  C -150x100x4mm MB RHS 990 KG  D -75x75x4mm EA RSA 396 KG  E -300x300x10mm base plate bolted to reinforced concrete stub colums  F -5mm thick triangular stiffiner ms plate of base 75mm and height 75mm welded to base plate and SHS columns  16 mm Diameter holding down RAG bolts with nut and washer fixed to reinforced concrete columns, length  G -600 mm 136 No.  H 2mm thick mild sheet siding welded to framework around entire platform 83 SM		painting)				
A - 150X150X6mm x 27.13kg/m SHS  Beams , size  B - 125x75x4mm SB		Decking, decking beares and mild steel plates and bolts				
- 150X150X6mm x 27.13kg/m SHS  Beams , size  B - 125x75x4mm SB		Columns and posts , size				
B - 125x75x4mm SB 3,472 KG  C - 150x100x4mm MB RHS 990 KG  D - 75x75x4mm EA RSA 396 KG  E - 300x300x10mm base plate bolted to reinforced concrete stub colums 34 No.  F - 5mm thick triangular stiffiner ms plate of base 75mm and height 75mm welded to base plate and SHS columns  16 mm Diameter holding down RAG bolts with nut and washer fixed to reinforced concrere columns, length  G - 600 mm 136 No.  H 2mm thick mild sheet siding welded to framework around entire platform 83 SM	A	- 150X150X6mm x 27.13kg/m SHS	2,686	KG		
C - 150x100x4mm MB RHS 990 KG  D - 75x75x4mm EA RSA 396 KG  E - 300x300x10mm base plate bolted to reinforced concrete stub colums 34 No.  F - 5mm thick triangular stiffiner ms plate of base 75mm and height 75mm welded to base plate and SHS columns  16 mm Diameter holding down RAG bolts with nut and washer fixed to reinforced concrete columns, length  G - 600 mm 136 No.  H 2mm thick mild sheet siding welded to framework around entire platform 83 SM		Beams, size				
D - 75x75x4mm EA RSA  E - 300x300x10mm base plate bolted to reinforced concrete stub colums  F - 5mm thick triangular stiffiner ms plate of base 75mm and height 75mm welded to base plate and SHS columns  16 mm Diameter holding down RAG bolts with nut and washer fixed to reinforced concrere columns, length  G - 600 mm  136 No.  H 2mm thick mild sheet siding welded to framework around entire platform  83 SM	В	- 125x75x4mm SB	3,472	KG		
E - 300x300x10mm base plate bolted to reinforced concrete stub colums  F - 5mm thick triangular stiffiner ms plate of base 75mm and height 75mm welded to base plate and SHS columns  16 mm Diameter holding down RAG bolts with nut and washer fixed to reinforced concrere columns, length  G - 600 mm  136 No.  H 2mm thick mild sheet siding welded to framework around entire platform  83 SM	С	- 150x100x4mm MB RHS	990	KG		
- 300x300x10mm base plate bolted to reinforced concrete stub colums  F - 5mm thick triangular stiffiner ms plate of base 75mm and height 75mm welded to base plate and SHS columns  16 mm Diameter holding down RAG bolts with nut and washer fixed to reinforced concrete columns, length  G - 600 mm  136 No.  H 2mm thick mild sheet siding welded to framework around entire platform  83 SM	D	- 75x75x4mm EA RSA	396	KG		
Washer fixed to reinforced concrere columns, length  G - 600 mm 136 No.  H 2mm thick mild sheet siding welded to framework around entire platform 83 SM		stub colums  - 5mm thick triangular stiffiner ms plate of base 75mm	34			
		washer fixed to reinforced concrere columns, length - 600 mm  2mm thick mild sheet siding welded to framework around				
Carried to Collection		entire platform	83	SM		
		Carried to Collection				

Item Description	Qty	Unit	Rate	Amount KSh

Platform balustrading and railings comprising of mild steel circular hollow section handrail 50mm diameter welded to 50x50x5mm RHS balusters at 1000mm spacing and 40x40x 3mm RH5 mid rail welded to balusters balusters welded to beams and platform, including preparing and applying one undercoat and two finishing coats of gloss paint available from approved manufacturero, balustrading overal height  A -950mm 70 LM  B -Purpose made 3000x1500x 4mm thick chequred plate welded to beams  Staircase members , size  C -200X50X6mm CFC stringer beams 339 KG  D -Purpose made 1500x245x4mm thick chequred plate welded to stringer beams  Staircase balustrading and railings comprising of mild steel circular hollow section handrail 50mm diameter welded to 50x50x3mm RHS mid rail welded to balusters balusters welded to beams and platforme, overal height  E -950mm 20 LM		11000000 0				
C - 200X50X6mm CFC stringer beams  D -Purpose made 1500x245x4mm thick chequred plate welded to stringer beams  Staircase balustrading and railings comprising of mild steel circular hollow section handrail 50mm diameter welded to 50x50x3mm RHS balusters at 1000mm spacing and 40x40x 3mm RHS mid rail welded to balusters balusters welded to beams and platformc, overal height		steel circular hollow section handrail 50mm diameter welded to 50x50x3mm RHS balusters at 1000mm spacing and 40x40x 3mm RHS mid rail welded to balusters balusters welded to beams and platform, including preparing and applying one undercoat and two finishing coats of gloss paint available from approved manufacturero, balustrading overal height - 950mm  -Purpose made 3000x1500x 4mm thick chequred plate				
Purpose made 1500x245x4mm thick chequred plate welded to stringer beams  Staircase balustrading and railings comprising of mild steel circular hollow section handrail 50mm diameter welded to 50x50x3mm RHS balusters at 1000mm spacing and 40x40x 3mm RHS mid rail welded to balusters balusters welded to beams and platformc, overal height		Staircase members , size				
-Purpose made 1500x245x4mm thick chequred plate welded to stringer beams  Staircase balustrading and railings comprising of mild steel circular hollow section handrail 50mm diameter welded to 50x50x3mm RHS balusters at 1000mm spacing and 40x40x 3mm RHS mid rail welded to balusters balusters welded to beams and platformc, overal height	С	- 200X50X6mm CFC stringer beams	339	KG		
steel circular hollow section handrail 50mm diameter welded to 50x50x3mm RHS balusters at 1000mm spacing and 40x40x 3mm RHS mid rail welded to balusters balusters welded to beams and platformc, overal height	D	= = =	24	No.		
E - 950mm 20 LM		steel circular hollow section handrail 50mm diameter welded to 50x50x3mm RHS balusters at 1000mm spacing and 40x40x 3mm RHS mid rail welded to balusters				
	Е	- 950mm	20	LM		
Carried to Collection		Carried to Collection				

Item	Description	Qty	Unit	Rate	Amount KSh
------	-------------	-----	------	------	------------

	Proposed G	11110450			
A	Prepare and apply one undercoat and two finishing coats of gloss paint available from approved manufacturer as described on; Prepare surfaces, apply primer, one undercoat and two finishing coats of premium quality gloss oil paint on all steel work after erection (measured net overall)	2,400	SM		
	Carried to Collection				
	COLLECTION From page GH/8 From page GH/9 From Above				
	TOTAL FOR STRUCTURAL STEEL FRAME CARRIED TO SUMMARY				

Item Description	Qty	Unit Rate	Amount KSh
------------------	-----	-----------	------------

	Troposed O	11110400		ı	
	ELEMENT NO. 4				
	WALLING				
	Hessian based bituminous felt damp proof course laid on cement and sand (1:4) mortar under:-				
A	200mm wide; B.S. 743 Type A bitumen hessian base 150 mm laps (make allowance for laps); horizontal, 1 no. layer, bedded in cement sand (1:3) mortar	190	LM		
	Precast concrete grade 20(12mm aggregate) including formwork, finishing fair on all exposed surfaces and hoisting and placing in position, bedding, jointing and pointing in cement and sand (1:3) mortar				
В	200 x 200 mm Lintel reinforced with and including two 12mm diameter mild steel rods hooked at ends (in 38No.)	25	LM		
	EXTERNAL WALLING				
	Approved machine cut coral block wall; squared; hand dressed one side to key joint; bedding, jointing in cement and sand mortar (1:4); including reinforcing with hoop iron in every alternative course				
C	Walls 200 mm thick	700	SM		
	Precast concrete grade 20(12mm aggregate) finishing fair on all exposed surfaces and hoisting and placing in position, bedding, jointing and pointing in cement and sand (1:3) mortar				
D	Precast concrete vents	360	SM		
	INTERNAL WALLING				
	Approved machine cut coral block wall; squared; hand dressed one side to key joint; bedding, jointing in cement and sand mortar (1:4);including reinforcing with hoop iron in every alternative course				
Е	Walls 200 mm thick	215	SM		
	TOTAL FOR WALLING CARRIED TO SUMMARY				

Item Desc	cription	Qty	Unit	Rate	Amount KSh
-----------	----------	-----	------	------	------------

	Proposed G	11110400		I	
	ELEMENT NO. 5				
	<u>DOORS</u>				
	50mm thick mahogany pannelled single door in , comprising 150 x 50mm top and bottom rails infilled with 50mm thick solid moulded 1no. timber panels per leaf with moulded beading around panels; edges bevelled and grooved into 100x50mm frames; all framed, clamped and grooved together to Architects details				
A	Door overall size 900x2400mm	1	NO.		
В	Ditto but double door overall size 1500x 2550mm	1	NO.		
	Supply and install powder coated heavy duty steel sliding door comprising of frames and all necessary iron mongery, door panels supported at the top and bottom with galvanisesd wheels running in galvanised steel trucks, all to Architects details				
С	Door overall size 3000 x 3000mm	2	NO.		
	Heavy duty metal casement powder coated steel door in 50x45mm RHS bottom, middle and top rails and stiles infilled with steel panels welded to door and framed, including cutting and pinning lugs to concrete or concrete blockwork surround and bedding frame in cement and sand mortar				
D	Door overall size 900 x 2400mm	2	NO.		
E	Door overall size 1500 x 2400mm	6	NO.		
E	<u>Iron mongery</u>	U	INO.		
	Supply and fix the following to UNION catalogue or other equal and approved				
	To softwood, hardwood or the like fixing with screws				
F	Three lever mortice lock complete with set lever aluminium handle furniture	2	NO.		
	Carried to Collection				
	1		ı	ı	

Item	Description	Qty	Unit	Rate	Amount KSh

A	100x76x3mm Stainless steel hinges To concrete or blockwork; fixing with bolts; plugging	5	PRS		
В	Rubber door stop complete with 38 mm rawl bolt	2	NO.		
	Wrot Hardwood framed frames and framings				
С	150 x 50 mm; 2 No. labours; plugged door frame	15	LM		
D	40 x 35 mm moulded architrave	30	LM		
Е	25 x 25mm moulded quadrants	30	LM		
	Painting and Decorations				
	<u>On wood</u>				
	Aluminium primer or other equal and approved wood primer before fixing: -				
F	Backs of frame, board, etc over 100mm but not exceeding 200mm girth	15	LM		
	Knot, prime and stop; prepare and apply three coats polyurethane clear varnish on woodwork				
G	General surfaces of timber doors over 300mm girth; external				
		15	SM		
H	Frames; over 200mm but not exceeding 300mm girth; internal	15	LM		
I	Frames; not exceeding 100mm girth,	60	LM		
	<u>On Metal work</u>				
	Prepare and apply three coats of premium qualitity super gloss oil paint as approved to: -				
J	General door surfaces	170	SM		
	Carried to Collection				

COLLECTION From page GH/12 From page GH/13  TOTAL FOR DOORS CARRIED TO SUMMARY	Item	Description	Qty	Unit	Rate	Amount KSh
From page GH/13  From page GH/13						
From page GH/13						
		From page GH/12				
TOTAL FOR DOORS CARRIED TO SUMMARY		From page GH/13				
TOTAL FOR DOORS CARRIED TO SUMMARY						
TOTAL FOR DOORS CARRIED TO SUMMARY						
TOTAL FOR DOORS CARRIED TO SUMMARY						
TOTAL FOR DOORS CARRIED TO SUMMARY						
TOTAL FOR DOORS CARRIED TO SUMMARY						
TOTAL FOR DOORS CARRIED TO SUMMARY						
TOTAL FOR DOORS CARRIED TO SUMMARY						
TOTAL FOR DOORS CARRIED TO SUMMARY						
TOTAL FOR DOORS CARRIED TO SUMMARY						
TOTAL FOR DOORS CARRIED TO SUMMARY						
TOTAL FOR DOORS CARRIED TO SUMMARY						
TOTAL FOR DOORS CARRIED TO SUMMARY						
TOTAL FOR DOORS CARRIED TO SUMMARY						
TOTAL FOR DOORS CARRIED TO SUMMARY						
TOTAL FOR DOORS CARRIED TO SUMMARY						
TOTAL FOR DOORS CARRIED TO SUMMARY						
TOTAL FOR DOORS CARRIED TO SUMMARY						
TOTAL FOR DOORS CARRIED TO SUMMARY						
TOTAL FOR DOORS CARRIED TO SUMMARY						
TOTAL FOR DOORS CARRIED TO SUMMARY						
TOTAL FOR DOORS CARRIED TO SUMMARY						
TOTAL FOR DOORS CARRIED TO SUMMARY						
TOTAL FOR DOORS CARRIED TO SUMMARY						
TOTAL FOR DOORS CARRIED TO SUMMARY						
TOTAL FOR DOORS CARRIED TO SUMMARY						
TOTAL FOR DOORS CARRIED TO SUMMARY						
TOTAL FOR DOORS CARRIED TO SUMMARY						
TOTAL FOR DOORS CARRIED TO SUMMARY						
TOTAL FOR DOORS CARRIED TO SUMMARY						
TOTAL FOR DOORS CARRIED TO SUMMARY						
TOTAL FOR DOORS CARRIED TO SUMMARY						
TOTAL FOR DOORS CARRIED TO SUMMARY						
TOTAL FOR DOORS CARRIED TO SUMMARY						
TOTAL FOR DOORS CARRIED TO SUMMARY		TOTAL FOR DOODS CARRIED TO SUMMARY				
		TOTAL FOR DOOKS CARRIED TO SUMMARY				

		1	1	1	
Item	Description	Qty	Unit	Rate	Amount KSh

	Proposed G	11110400		1	
	ELEMENT NO. 6 WINDOWS				
	ALUMINIUM WINDOWS PURPOSE - MADE UNITS				
	Supply, assemble and fix the following purpose-made natural powder coated aluminium framed windows to B.S. 3987, 1984 to Booth Standard extruded profiles, or equal and approved complete with 6mm thick laminated sheet glass & all necessary ironmongery and fixtures. All windows to have permanent vents.  Aluminium; for glazing with putty, lugs to two jambs, cutting and pinning to concrete or blockwork, fixing to				
A	head and sill with screws; plugging  Window, overall size 2000x1200mm high	3	NO		
В	Window, overall size 2000 X 1500mm high	6	NO		
	<u>Grills</u>				
С	High tensile steel burglar proof bars at 300mm cross centres horizontal and vertical; ends lugged in masonry.  12mm diameter bars welded and ground smooth to approval.	20	SM		
	Carried to Collection				

Item	Description	Qty	Unit	Rate	Amount KSh

	Proposed G	11110450	1	
	Painting and Decorations			
	<u>On Metal work</u>			
	Prepare and apply three coats of premium qualitity super gloss oil paint as approved to: -			
A	Backs of frame, board, etc over 200mm but not exceeding 300mm girth	20	LM	
В	Surfaces of metal over 300mm girth (burglar proofing grills)	50	SM	
	Carried to Collection			
	COLLECTION			
	From page GH/15 From Above			
	TOTAL FOR WINDOWS CARRIED TO SUMMARY			

I trans   December 19 and	01	TI-1 Data	A IZC1-
Item   Description	Otv	Unit   Rate	Amount KSh

ELEMENT NO. 7  FINISHES  Wall finishes  Insitu finishes  A Extra over horizontal and vertical pointing in 10mm thick rod in cement and sand (1:3) mortar; one coat of bituminous paint.  Plaster; 18mm thick, 2 No. coatwork, 15mm first coat of cement sand (1:3); 3mm second coat of cement and lime putty (1:9); steel trowelled to concrete or blockwork base  B Walls, beams and columns; internal  Painting & Decoration
Wall finishes  Insitu finishes  A Extra over horizontal and vertical pointing in 10mm thick rod in cement and sand (1:3) mortar; one coat of bituminous paint.  Plaster; 18mm thick, 2 No. coatwork, 15mm first coat of cement sand (1:3); 3mm second coat of cement and lime putty (1:9); steel trowelled to concrete or blockwork base  B Walls, beams and columns; internal  Painting & Decoration  Insitu finishes  700  SM  Painting & Decoration
Insitu finishes  A Extra over horizontal and vertical pointing in 10mm thick rod in cement and sand (1:3) mortar; one coat of bituminous paint.  Plaster; 18mm thick, 2 No. coatwork, 15mm first coat of cement sand (1:3); 3mm second coat of cement and lime putty (1:9); steel trowelled to concrete or blockwork base  B Walls, beams and columns; internal  1129 SM  Painting & Decoration
A Extra over horizontal and vertical pointing in 10mm thick rod in cement and sand (1:3) mortar; one coat of bituminous paint.  Plaster; 18mm thick, 2 No. coatwork, 15mm first coat of cement sand (1:3); 3mm second coat of cement and lime putty (1:9); steel trowelled to concrete or blockwork base  B Walls, beams and columns; internal  1129 SM  Painting & Decoration
rod in cement and sand (1:3) mortar; one coat of bituminous paint.  Plaster; 18mm thick, 2 No. coatwork, 15mm first coat of cement sand (1:3); 3mm second coat of cement and lime putty (1:9); steel trowelled to concrete or blockwork base  B Walls, beams and columns; internal  1129 SM  Painting & Decoration
Painting & Decoration
Prepare and apply three coats of premium quality weather guard paint as approved to:-
C Walls; external 360 SM
Prepare and apply three coats of premium quality silk vinyl emulsion paint as approved to:-
D Walls; internal 1,129 SM
Floor finishes
Power float floor finish to concrete floor finish
200mm thick class 25 concrete top later laid to falls to warehouse to Engineers details with power float finish; including non-mettalic floor hardener or any other equally
E Oil and dusted proofed power floated hardened screed finish laid in bays not exceeding 10 square metre including black plastic approved durable dividing strips 741 SM
Carried to collection

Item	Description	Qty	Unit	Rate	Amount KSh

	1 Toposcu G			1
	Staircase finishes			
	Cement and sand (1:3) in:			
A	30mm thick screed finished to receive terrazo	40	SM	
В	Ditto to 300mm wide treads	48	LM	
С	Ditto to 150mm high risers	48	LM	
D	Ditto to 200-300mm wide edge of sloping staircase	96	LM	
Е	Ditto slopping soffites	16	SM	
F	20mm thick terrazo finish to floor screed	77	SM	
	Carried to collection			
	COLLECTION  From page GH/17 From above			
	TOTAL FOR FINISHES CARRIED TO SUMMARY			

Item	Description	Otv	Unit	Rate	Amount KSh

	110posea d	III I I I U U SC			
A	ELEMENT NO. 8  Balustrading and railings comprising of mild steel handrail 100mm SH5 fixed to 50mm balusters at 1000mm spacing, balusters bolted to concrete plinths or beds and 25mm mid-rails fixed to balusters at 200mm, overal height - 900mm		LM		
	TOTAL FOR BALUSTRADING & RAILINGS CARRIED TO SUMMARY				

Item	Description	Qty	Unit	Rate	Amount KSh

	Proposed G	11110450	1	
АВ	ELEMENT NO. 09  ROOFING  Supply, deliver to site and erect mild steel frame steelwork to BS 449 with and including welds and bolting connections. Rates to include for all materials, labour, stiffeners, welding or bolts, wastage and cutting, drilling all gusset plates fastenings and connections and all other items necessary for satisfactory incorporation into works including wire brushing surfaces free from rust, steel to be painted with one coat an epoxy primer containing zinc chromate followed by two coats of masterseal SP 120 before fabrication and one other coat after fabrication  All structural steelworks in roofing shall be in accordance with ASTM A500 KS02-104 Grade 250, all welding in accordance with BS5135 and bolts and nuts, grade 4.6 to BS4360.All steelwork shall be primed withn red oxide before delivery to site.  Truss 1  The following in 4 no.steel trusses compring 100x100x4mm SHS top and bottom chords, 50x50x3mm SHS struts and ties spanning at 12.20m and hoisted at 12.25m above ground level, top, bottom and struts and ties connected with a 6mm continous fillet weld  Top and Bottom Chords  - 100x100x4mm SHS  Struts and ties  - 50x50x3mm SHS  Z Purlin, size  - 165.1x 50.8 x 20x2.0mm	1,848 583	KG KG	
С		1,270	KG	
	Carried to Collection			

Item	Description	Qty	Unit	Rate	Amount KSh

	1 toposed di	111110000			
	Truss 2				
	The following in 7no. steel trusses compring 100x100x4mm SHS top and bottom chords, 50x50x3mm SHS struts and ties spanning at 10.20m and hoisted at 7.25m above ground level, top, bottom and struts and ties				
	connected with a 6mm continous fillet weld  Top and Bottom Chords				
A	- 100x100x4mm SHS	2,402	KG		
	Struts and ties				
В	- 50x50x3mm SHS	1,014	KG		
	Z Purlin, size	0.504	140		
С	- 165.1x 50.8 x 20x2.0mm	2,534	KG		
	Truss 3				
	The following in 7no. steel trusses compring 100x100x4mm SHS top and bottom chords, 50x50x3mm SHS struts and ties spanning at 4.60m and hoisted at 3.40m above ground level, top, bottom and struts and ties connected with a 6mm continous fillet weld				
D	Top and Bottom Chords - 100x100x4mm SHS	1,201	KG		
	Struts and ties				
Е	- 50x50x3mm SHS	374	KG		
	Z Purlin, size				
F	- 165.1x 50.8 x 20x2.0mm	1,183	KG		
	Carried to Collection				

Item	Description	Qty	Unit	Rate	Amount KSh
		~-3			

	Proposed G	11110460		T.	1	
	Truss 4  The following in 4no. steel trusses compring 100x100x4mm SHS top and bottom chords, 50x50x3mm SHS struts and ties spanning at 3.60m and hoisted at 3.40m above ground level, top, bottom and struts and ties connected with a 6mm continous fillet weld					
A	<u>Top and Bottom Chords</u> - 100x100x4mm SHS	634	KG			
В	Struts and ties - 50x50x3mm SHS	194	KG			
С	<u>Z Purlin, size</u> - 165.1x 50.8 x 20x2.0mm <u>Braces, size</u>	411	KG			
D E	- 50 x 50 x 6mm SHS  16mm diameter antisag rods	2,464 300	KG LM			
F	Mild steel plates and bolts  Triangular apex haunch 300mm long, size - 475x191x8mm ms plate welded on rafters  Base Plate, size	33	No.			
G H	- 250x200x10mm plate with 4 number 18mm diameter holes for 16mm bolts to reinforced concrete beam - 350x100x6mm gusset plate welded to mild steel plate including 6mm thick fillet weld	44 88	No.			
I J	<ul> <li>- 125x100x6mm angle cleat to Z purlins rafter connection including 6mm continous fillet weld</li> <li>- 250x200x10mm plate to angle cleat connection</li> </ul>	242 242	No. No.			
	Carried to Collection					

Item Description	Qty	Unit	Rate	Amount KSh
------------------	-----	------	------	------------

A -1100x150x12mm mild steel plate with 18mm diameter holes drilled at 200mm c/c vertical for 16mm diameter boltsat apex connection 20 No.  B -400x150x3mm thick fish plates to with 4 number 14mm diameter holes drilled for 12mm diameter bolts at Z purlins connection  16 mm Diameter bolts with nut and washer fixed to rafters and apex haunches, lenghth  C -150 mm 264 No.  16 mm Diameter grade 8.8 holding down bolts with nut and washer fixed to rafter beam connection  D -300 mm 176 No.  12mm Diameter bolts with nut and washer fixed to Z purlins' connection, lenghth  E -150 mm 800 No.  1.5mm thick galvanised gutter overall girth.  F -1000mm 168 LM  G Roof covering in aluminium roofing sheets; 150mm laps both sides; and fixing to purlins (m.s.) on steel trusses (m.s.) with zinc nails at 5000mmc/c all laid to fall  Av. 300mm dia alluminium ridge sheet with stiffeners 41 LM		11000000				
holes drilled at 200mm c/c vertical for 16mm diameter boltsat apex connection  - 400x150x3mm thick fish plates to with 4 number 14mm diameter holes drilled for 12mm diameter bolts at Z purlins connection  16 mm Diameter bolts with nut and washer fixed to rafters and apex haunches, lenghth  - 150 mm  16 mm Diameter grade 8.8 holding down bolts with nut and washer fixed to rafter beam connection  D - 300 mm  176 No.  12mm Diameter bolts with nut and washer fixed to Z purlins' connection, lenghth  E - 150 mm  800 No.  1.5mm thick galvanised gutter overall girth.  F - 1000mm  Roof covering in aluminium roofing sheets; 150mm laps both sides; and fixing to purlins (m.s.) on steel trusses (m.s.) with zinc nails at 5000mmc/c all laid to fall  Av. 300mm dia alluminium ridge sheet with stiffeners  No.  220 No. No. No. 16 mm Diameter bolts with nut and washer fixed to Z purlins' connection.  176 No. 177 No. 188 LM  800 No. 188 LM  800 No. 188 LM  801 No. 188 LM  802 No. 188 LM  803 No. 188 LM  804 No. 188 LM  805 SM  806 AV. 300mm dia alluminium ridge sheet with stiffeners						
and apex haunches, lenghth  C - 150 mm  16 mm Diameter grade 8.8 holding down bolts with nut and washer fixed to rafter beam connection  D - 300 mm  12mm Diameter bolts with nut and washer fixed to Z purlins' connection, lenghth  E - 150 mm  1.5mm thick galvanised gutter overall girth,  F - 1000mm  G Roof covering in aluminium roofing sheets; 150mm laps both sides; and fixing to purlins (m.s.) on steel trusses (m.s.) with zinc nails at 5000mmc/c all laid to fall  H Av. 300mm dia alluminium ridge sheet with stiffeners  850 SM  41 LM		holes drilled at 200mm c/c vertical for 16mm diameter boltsat apex connection  - 400x150x3mm thick fish plates to with 4 number 14mm diameter holes drilled for 12mm diameter bolts at Z				
C -150 mm  16 mm Diameter grade 8.8 holding down bolts with nut and washer fixed to rafter beam connection  D -300 mm  12mm Diameter bolts with nut and washer fixed to Z purlins' connection, lenghth  E -150 mm  1.5mm thick galvanised gutter overall girth,  F -1000mm  G Roof covering in aluminium roofing sheets; 150mm laps both sides; and fixing to purlins (m.s.) on steel trusses (m.s.) with zinc nails at 5000mmc/c all laid to fall  850 SM  H Av. 300mm dia alluminium ridge sheet with stiffeners  168 LM						
and washer fixed to rafter beam connection  1 - 300 mm  1 - 150 mm  1 - 150 mm  1 - 150 mm  1 - 1000mm  1 - 1000mm	С		264	No.		
12mm Diameter bolts with nut and washer fixed to Z purlins' connection, lenghth  E -150 mm						
purlins' connection, lenghth E -150 mm  1.5mm thick galvanised gutter overall girth,  F -1000mm  G Roof covering in aluminium roofing sheets; 150mm laps both sides; and fixing to purlins (m.s.) on steel trusses (m.s.) with zinc nails at 5000mmc/c all laid to fall  H Av. 300mm dia alluminium ridge sheet with stiffeners  850 SM  41 LM	D	- 300 mm	176	No.		
F -1000mm  G Roof covering in aluminium roofing sheets; 150mm laps both sides; and fixing to purlins (m.s.) on steel trusses (m.s.) with zinc nails at 5000mmc/c all laid to fall  H Av. 300mm dia alluminium ridge sheet with stiffeners  168 LM  850 SM  LM  LM  168 LM  850 SM  LM  168 LM	E	purlins' connection, lenghth	800	No.		
G Roof covering in aluminium roofing sheets; 150mm laps both sides; and fixing to purlins (m.s.) on steel trusses (m.s.) with zinc nails at 5000mmc/c all laid to fall  H Av. 300mm dia alluminium ridge sheet with stiffeners  850 SM LM		1.5mm thick galvanised gutter overall girth,				
both sides ; and fixing to purlins (m.s.) on steel trusses (m.s.) with zinc nails at 5000mmc/c all laid to fall  H Av. 300mm dia alluminium ridge sheet with stiffeners  850 SM  LM	F	- 1000mm	168	LM		
H Av. 300mm dia alluminium ridge sheet with stiffeners 41 LM	G	both sides; and fixing to purlins (m.s.) on steel trusses				
Carried to Collection	H	Av. 300mm dia alluminium ridge sheet with stiffeners	41	LM		
Carried to Collection						
Carried to Collection						
Carried to Collection						
Carried to Collection						
Carried to Collection						
Carried to Collection						
Carried to Collection						
Carried to Concentral		Carried to Collection				

Item Description	Qty	Unit	Rate	Amount KSh
------------------	-----	------	------	------------

	Troposed G				
A	Prepare and apply one undercoat and two finishing coats of gloss paint available from approved manufacturer as described on;  Prepare surfaces, apply primer, one undercoat and two finishing coats of premium quality gloss oil paint on all steel work after erection (measured net overall)  RAINWATER DISPOSAL	2,000	SM		
	24g Galvanised mild steel sheeting; all welds ground smooth				
В	150 x 100mm box gutter including soldered joints in the running length fixed to fascia board with and including brackets at approved centers  Extra; for 900 corners.	168 15	LM No		
D	Extra; 100mm dia.outlet 100mm long	15	No		
Е	100mm dia. rainwater downpipe fixed with and including mild steel straps at 900mm centres, plugged and screwed to wall				
F	Extra; swanneck bend with 1135mm projection	200 15	LM No		
G	Extra; horse shoe bend	15	No		
	Wrought cypress treated as described and with a moisture content not exceeding 12% to				
Н	Fascia and verge board, size 200x25mm	180	LM		
	Carried to Collection				

Item	Description	Qty	Unit	Rate	Amount KSh
	Painting and Decorations				
	<u>On Woodwork</u>				
	Prepare and apply one zinc plumbate primer and three coats of approved super gloss oil paint to:-				
A	Fascias; 200 to 300mm girth; external	180	LM		
	<u>On Metal work</u>				
В	General surfaces; over 300mm girth external	134	SM		
С	Small pipes of girth 100mm diameter	200	LM		
	Carried to Collection				
	COLLECTION				
	From page GH/20				
	From page GH/21				
	From page GH/22				
	From page GH/23				
	From page GH/24				
	From above				
	TOTAL FOR STRUCTURAL STEELWORK CARRIED TO SUMMARY				

Item	Description	Qty	Unit	Rate	Amount KSh
	ELEMENT NO. 10				
	BUILDERS WORK IN CONNECTION WITH				
	SPECIALIST SERVICES(Provisional)				
	Builder's work in connection with Plumbing and drainage				
	<u>installations</u>				
	<u>Labour and Materials</u>				
١.					
A	Form or leave hole in 200mm thick natural stone wall for				
	large pipe and later make good	10	No		
В	Ditto for small pipe and ditto	10	No		
С	Form or leave hole in 100mm thick natural stone wall for				
	small pipe and later make good	48	No		
D	Cut horizontal or vertical chase in natural stone walling				
	for small pipes and later make good	300	LM		
Е	Ditto for large pipes	300	LM		
	Builder's work in connection with electrical installations				
	Cut away for and make good after Electricain installing				
	<u>aconcealed conduit system to the following points</u> including cutting or leaving all holes, mortices, sinkings in				
	the structure and its finishes and for all making good				
	therewith:-				
F	Lighting points	50	No		
G	Power points	20	No		
Н	Switch points	15	No		
I	Data outlet points	5	No		
J	Consumer unit	1	No		
K	Meter board	1	No		
		400	LM		
L	25x25mm deep chase in stone walling for conduits				
	Carried to Collection				

т.	Proposed G		T7 *-	ln (	A
Item	Description	Qty	Unit	Kate	Amount KSh
A	50x50mm deep chase in stone walling for conduits	400	LM		
	Carried to Collection				
	COLLECTION				
	From page GH/26 From above				
	TOTAL FOR BUILDERS WORKS CARRIED TO				
	SUMMARY				

Them Beschiption 20, One late 1 mount is	Item	Description	Qty	Unit	Rate	Amount KSl
--	------	-------------	-----	------	------	------------

Proposed Gin House

	Proposed G			
ELEM	SUMMARY ENT NO. TITLE		NO. OF UNITS	AMOUNT KSh
1 2	SUBSTRUCTURE (ALL PROVISIONAL) R.C FRAME	GH/6 GH/7	1	
4	STRUCTURAL STEEL FRAME WALLING	GH/10 GH/11	1	
6	DOORS WINDOWS	GH/14 GH/16	1	
8	FINISHES  BALUSTRADING & RAILINGS	GH/18 GH/19	1	
9 10	ROOFING BUILDERS WORK IN SPECIALISTS WORKS	GH/25 GH/27		
	TOTAL FOR 1 N0. GIN HOUSE			

Item	Description	Qty	Unit	Rate	Amount KSh
	ELEMENT NO. 1				
	SUBSTRUCTURES (ALL PROVISIONAL)				
	Site Clearance				
Α	Clear site of all shrubs, bushes and small trees and grub				
	up roots, cart away to spoil heaps away from site	560	SM		
	Oversite excavation				
В		560	SM		
	Excavate oversite to remove top soil average 200mm deep and keep on site for later re-use for landscaping				
	<u>Excavation</u>				
С	Excavation for strip foundation commencing at				
	reduced bulk excavation levels depth not exceeding				
	1.5M deep	176	CM		
D	Excavation for bases commencing at reduced bulk				
	excavation levels depth not exceeding 1.5M deep	<b>5</b> 0	C) I		
 	O	79	CM		
Е	Excavation for strip foundation depth exceeding				
	1.50M but not exceeding 3.0M deep	176	CM		
F	Excavation for bases depth exceeding 1.50M but not				
	exceeding 3.0M deep	79	СМ		
G		79 434	CM		
	Extra over excavation in all types of rock	101	Civi		
	Disposal of excavated material				
Н	Fillings aroundfdn: backfill and compact in 150 mm				
	layers: selected excavated materials	904	CM		
I	Remove surplus spoil from site to an authorized	90 <del>4</del>	Civi		
1	dumping site				
		603	CM		
	Diposal of water				
т	-		ITEM		
J	Keeping all excavations free from all water including spring or running water		HEM		
	Carried to Collection				
	Curried to Concention				

Item	Description	Qty	Unit	Rate	Amount KSh
A	Planking and strutting Uphold the sides of all excavations		ITEM		
В	Hardcore filling 300mm thick fillings in making up levels: levelled and compacted in 150 mm layers	560	SM		
С	50mm (average) thick quarry dust blinding to surfaces of hardcore	560	SM		
D	Selected imported material  Filling in making up levels under floors, spread levelled, well rammed and consolidated in 150mm layers.	672	СМ		
E	Antitermite treatment  Premise 200 CC' or other equal and approved anti-termite insecticide treatment with ten years guarantee, applied strictly in accordance with manufacturer's instructions, to tops of fill and foundation walls	570	SM		
	50mm thick mass concrete class Q(1:3:6) in:-	560	SIVI		
F	Column bases	48	SM		
G	Strip foundation  Reinforced concrete; class 25/(20mm) mix (1:1.5:3);  vibrated	107	SM		
Н	Column bases	20	СМ		
I	Strip foundations	24	СМ		
J	Foundation columns	12	СМ		
K	Ground beams	17	СМ		
L	200mm thick ground slab powefloated and hardened by approved admixtures	560	SM		
	Carried to Collection				

Item	Description	Qty	Unit	Rate	Amount KSh
	<u>Reinforcement</u>				
	Bars; high yield steel; cold worked to B.S. 4461 including				
	bends, hooks, tying wire and distance blocks				
A	8 mm diameter bars	2940	KG		
В	10 mm diameter bars	3430	KG		
C	12 mm diameter bars	1960	KG		
D	16-32 mm diameter bars	1470	KG		
	Sawn formwork to insitu concrete as described to :-				
	Sawii Toliitwolk to hista concrete as aescribea to .				
Е	Sides; vertical or battering of foundation columns	120	SM		
	,				
F	Sides and soffits of ground beams	178	SM		
G	Edges of ground floor slab; 150 to 225 mm high	105	LM		
	anges of ground from the property of the prope	100	22,1		
Н	Sides; vertical or battering of foundations	71	SM		
I	Sides; vertical or battering of bases	57	SM		
	_	37	Sivi		
	<u>Insitu Finishings</u>				
Т т	14mm thick 2No. coatwork cement sand(1:3) render; wood				
J	floated to concrete or blockwork base to walls; external				
		- 4	G) f		
	Painting and Decorations	54	SM		
	1 anting and Decorations				
	Prepare and apply three coats bituminous paint to:				
			0) (		
K	Wood floated rendered plinths over 300mm girth	54	SM		
	<u>Masonry</u>				
	200mm thick approved natural stone; local; roughly				
	squared to foundation walling; bedding and jointing in				
	cement sand (1:3) mortar including reinforcing with hoop				
	<u>iron ties every alternate course.</u>				
L	200mm thick walling	534	SM		
	Carried to Collection				

Item	Description	Qty	Unit	Rate	Amount KSh
A					
	BRC Fabric mesh reinforcement Ref. A193 with 200 mm laps (measured net; no allowances made for laps) to basement floor bed	1120	SM		
	<u>DPM</u>				
В	1000 Gauge approved polythene sheeting as damp proof membrane laid on blinded hardcore(measured separetely)with welted laps(measured net-no allowance made for laps)				
	Expansion joint filler	560	SM		
С	Flexcell expansion joint filler 50x150mm deep	500	LM		
	Expansion joint				
D	50x25 mm approved mastic expansion joint sealer	500	LM		
	Carried to Collection				
	COLLECTION				
	From page CS/1				
	From page CS/2				
	From page CS/3				
	From page above				
	TOTAL FOR CURCUPLICATIBLE CARRIED TO				
	TOTAL FOR SUBSTRUCTURES CARRIED TO SUMMARY				

I I,				
-	ELEMENT NO. 2			
	REINFORCED CONCRETE FRAMING			
	Reinforced concrete; class 25/(20mm) mix (1:1.5:3);			
1	vibrated			
A	Beams	22	CM	
В	Columns	22	СМ	
	Columns	22	CIVI	
C	Stairs	2	CM	
]	Reinforcement			
	Bars; high yield steel; cold worked to B.S. 4461 including bends, hooks, tying wire and distance blocks			
$\mid D \mid$	8 mm diameter bars	1863	KG	
	10 mm diameter bars	2174	KG	
	12 mm diameter bars	1242	KG	
G	16-32 mm diameter bars	932	KG	
	Sawn formwork to insitu concrete as describedto :-			
Н	To sides and soffits of beams.	243	SM	
I	Vertical sides of columns	196	SM	
J	Slopping soffits of stairs	17	SM	
	<u>Risers</u>			
K	-150 to 225mm high	48	LM	
	Edges of stairs			
L -	-150 to 225mm high	22	LM	
,	TOTAL FOR RC FRAME CARRIED TO SUMMARY			

Item	Description	Qty	Unit	Rate	Amount KSh
	ELEMENT NO. 3				
	WALLING				
	Hessian based bituminous felt damp proof course laid on cement and sand (1:4) mortar under:-				
A	200mm wide; B.S. 743 Type A bitumen hessian base 150 mm laps (make allowance for laps); horizontal, 1 no. layer, bedded in cement sand (1:3) mortar	81	LM		
	Precast concrete grade 20(12mm aggregate) including formwork, finishing fair on all exposed surfaces and hoisting and placing in position, bedding, jointing and pointing in cement and sand (1:3) mortar				
В	200 x 200 mm Lintel reinforced with and including two 12mm diameter mild steel rods hooked at ends (in 38No.)	12	LM		
	EXTERNAL WALLING				
	Approved machine cut coral block wall; squared; hand dressed one side to key joint; bedding, jointing in cement and sand mortar (1:4); including reinforcing with hoop iron in every alternative course				
С	Walls 200 mm thick	313	SM		
	Precast concrete grade 20(12mm aggregate) finishing fair on all exposed surfaces and hoisting and placing in position, bedding, jointing and pointing in cement and sand (1:3) mortar				
D	Precast concrete vents	46	SM		
	TOTAL FOR WALLING CARRIED TO SUMMARY				

Item [	Description	Qty	Unit	Rate	Amount KSh

	ELEMENT NO. 4				
	<u>DOORS</u>				
	Supply and install powder coated heavy duty steel sliding door comprising of frames and all necessary iron mongery, door panels supported at the top and bottom with galvanisesd wheels running in galvanised steel trucks, all to Architects details				
A	Door overall size 1500 x 3100mm	2	NO.		
В	Door overall size 3000 x 3000mm	3	NO.		
	On Metal work  Prepare and apply three coats of premium qualitity super gloss oil paint as approved to: -				
С	General door surfaces	73	SM		
	TOTAL FOR POORS SARVED TO SARVED				
	TOTAL FOR DOORS CARRIED TO SUMMARY				

Item Description	Qty	Unit	Rate	Amount KSh
------------------	-----	------	------	------------

	3101				
	ELEMENT NO. 5				
	WINDOWS				
	ALUMINIUM WINDOWS				
	<u>PURPOSE - MADE UNITS</u>				
	Supply, assemble and fix the following purpose-made natural powder coated aluminium framed windows to B.S. 3987, 1984 to Booth Standard extruded profiles, or equal and approved complete with 6mm thick laminated sheet glass & all necessary ironmongery and fixtures. All windows to have permanent vents.  Aluminium; for glazing with putty, lugs to two jambs, cutting and pinning to concrete or blockwork, fixing to head and sill with screws; plugging				
A	Window, overall size 4600 X 1000mm high  Painting and Decorations	16	NO		
	<u>Grills</u>				
	High tensile steel burglar proof bars at 300mm cross centres horizontal and vertical; ends lugged in masonry.				
В	12mm diameter bars welded and ground smooth to approval.				
	Painting and Decorations	74	SM		
	On Metal work				
С	Surfaces of metal over 300mm girth (burglar proofing grills)	148	SM		
	TOTAL FOR WINDOWS CARRIED TO SUMMARY				

Item Description	Qty	Unit Ra	ate	Amount KSh
------------------	-----	---------	-----	------------

	ELEMENT NO. 6				
	ELEMENTING				
	FINISHES				
	Wall finishes				
	<u>Insitu finishes</u>				
Α	Extra over horizontal and vertical pointing in 10mm thick				
	rod in cement and sand (1:3) mortar; one coat of bituminous paint.				
	-	313	SM		
	Plaster; 18mm thick, 2 No. coatwork, 15mm first coat of				
	cement sand (1:3); 3mm second coat of cement and lime putty (1:9); steel trowelled to concrete or blockwork base				
	the first transfer to concrete or processing the page				
В	Walls, beams and columns; internal	313	SM		
	wans, beams and columns, memai	313	JIVI		
	Painting & Decoration				
	=				
	Prepare and apply three coats of premium quality				
	weather guard paint as approved to:-				
		4.6	C) I		
С	Walls; external	46	SM		
	Prepare and apply three coats of premium quality silk				
	vinyl emulsion paint as approved to:-				
D	Walls; internal	313	SM		
	vvans, memai	313	JIVI		
	Floor finishes				
	Power float floor finish to concrete floor finish				
	1 OWEL HOUR HINSH to CONCICLE HOUR HINSH				
	200mm thick class 25 concrete top later laid to falls to warehouse to Engineers details with power float finish;				
	including non-mettalic floor hardener or any other equally				
	approved hardener to Architects detail and satisfaction				
E	Oil and dusted proofed power floated hardened screed				
	finish laid in bays not exceeding 10 square metre including black plastic approved durable dividing strips	540	SM		
		560	JIVI		
	Carried to collection				

Item Description	Qty	Unit	Rate	Amount KSh
------------------	-----	------	------	------------

	Staircase finishes			
	Cement and sand (1:3) in:			
A	30mm thick screed finished to receive terrazo	40	SM	
В	Ditto to 300mm wide treads	48	LM	
С	Ditto to 150mm high risers	48	LM	
D	Ditto to 200-300mm wide edge of sloping staircase	96	LM	
Е	Ditto slopping soffites	16	SM	
F	20mm thick terrazo finish to floor screed	77	SM	
	Carried to collection			
	<u>COLLECTION</u>			
	From page CS/09 From above			
	From above			
	TOTAL FOR FINISHES CARRIED TO SUMMARY			

Item Description	Qty	Unit Rate	Amount KSh
------------------	-----	-----------	------------

ELEMENT NO. 8  BALUSTRADING & RAILINGS  Balustrading and railings comprising of mild steel handrail 100mm SHS fixed to 50mm balusters at 1000mm spacing, balusters bolted to concrete plinths or beds and 25mm mid-rails fixed to balusters at 200mm, overal height  A -900mm  40 LM					
	A	BALUSTRADING & RAILINGS  Balustrading and railings comprising of mild steel handrail 100mm SHS fixed to 50mm balusters at 1000mm spacing, balusters bolted to concrete plinths or beds and 25mm mid-rails fixed to balusters at 200mm, overal height	LM		
TOTAL FOR BALUSTRADING & RAILINGS CARRIED TO SUMMARY					

Item	Description	Qty	Unit	Rate	Amount KSh

	SION			
	ELEMENT NO. 10			
	STRUCTURAL STEELWORK & ROOFING			
	Supply, deliver to site and erect mild steel frame			
	steelwork to BS 449 with and including welds and			
	bolting connections. Rates to include for all materials, labour , stiffeners, welding or bolts , wastage			
	and cutting, drilling all gusset plates fastenings and			
	connections and all other items necessary for satisfactory			
	incorporation into works including wire brushing			
	surfaces free from rust, steel to be painted with one coat			
	an epoxy primer containing zinc chromate followed by two coats of masterseal SP 120 before fabrication and			
	one other coat after fabrication			
	All structural steelworks in roofing shall be in			
	accordance with ASTM A500 KS02-104 Grade 250,all			
	welding in accordance with BS5135 and bolts and nuts, grade 4.6 to BS4360. All steelwork shall be primed			
	withn red oxide before delivery to site.			
	The following in steel trusses compring 100x100x4mm			
	SHS top and bottom chords, 50x50x3mm SHS struts and			
	ties spanning at 15.20m and hoisted at 6.2m above ground level, top, bottom and struts and ties connected with a			
	6mm continous fillet weld			
	<u>Top chords</u>			
A	100 100 1 6776	1,742	KG	
	- 100x100x4mm SHS	_,		
	Bottom chords			
D		1.640	T/C	
В	- 100x100x4mm SHS	1,642	KG	
	Struts and ties			
С	- 50x50x3mm SHS	948	KG	
	SONO ON OHILL OF LO			
	Z Purlin, size			
D		3,604	KG	
	- 165.1x 50.8 x 20x2.0mm	5,50 <del>1</del>	1.0	
	Braces, size			
			***	
E	- 50 x 50 x 6mm SHS	2,189	KG	
	Carried to Collection			

Item Descr	iption	Qty	Unit	Rate	Amount KSh

				1	
A	16mm diameter antisag rods	132	LM		
	Mild steel plates and bolts				
В	Triangular apex haunch 300mm long, size - 475x191x8mm ms plate welded on rafters	12	No.		
	Base Plate, size				
С	- 250x200x10mm plate with 4 number 18mm diameter holes for 16mm bolts to reinforced concrete beam	16	No.		
D	- 350x100x6mm gusset plate welded to mild steel plate including 6mm thick fillet weld	32	No.		
Е	- 125x100x6mm angle cleat to Z purlins rafter connection including 6mm continous fillet weld	120	No.		
F	- 250x200x10mm plate to angle cleat connection	120	No.		
G H	<ul> <li>- 1100x150x12mm mild steel plate with 18mm diameter holes drilled at 200mm c/c vertical for 16mm diameter boltsat apex connection</li> <li>- 400x150x3mm thick fish plates to with 4 number 14mm diameter holes drilled for 12mm diameter bolts at Z purlins connection</li> </ul>	6 200	No. No.		
I	16 mm Diameter bolts with nut and washer fixed to rafters  and apex haunches, lenghth  - 150 mm  16 mm Diameter grade 8.8 holding down bolts with nut	72	No.		
J	and washer fixed to rafter beam connection - 300 mm	64	No.		
K	12mm Diameter bolts with nut and washer fixed to Z purlins' connection, lenghth - 150 mm	800	No.		
	1.5mm thick galvanised gutter overall girth,				
L	- 1000mm	51	LM		
M	Roof covering in aluminium roofing sheets; 150mm laps both sides; and fixing to purlins (m.s.) on steel trusses (m.s.) with zinc nails at 5000mmc/c all laid to fall	630	SM		
	Carried to Collection				
	•			-	

Item D	Description	Qty	Unit	Rate	Amount KSh
--------	-------------	-----	------	------	------------

A	Av. 300mm dia aluminium ridge sheet with stiffeners Painting and decoration	30	LM		
	Prepare and apply one undercoat and two finishing coats of gloss paint available from approved manufacturer as described on;				
В	Prepare surfaces, apply primer, one undercoat and two finishing coats of premium quality gloss oil paint on all steel work after erection (measured net overall)  RAINWATER DISPOSAL	2,173	SM		
	24g Galvanised mild steel sheeting; all welds ground smooth				
С	150 x 100mm box gutter including soldered joints in the running length fixed to fascia board with and including brackets at approved centers	51	LM		
D	Extra; for 900 corners.	10	No		
E	Extra; 100mm dia.outlet 100mm long	10	No		
F	100mm dia. rainwater downpipe fixed with and including mild steel straps at 900mm centres, plugged and screwed to wall	100	LM		
	Carried to Collection				

Item Description	Qty	Unit Rate	Amount KSh
------------------	-----	-----------	------------

				I	$\neg$
A	Extra; swanneck bend with 1135mm projection	10	No		
В	Extra; horse shoe bend	10	No		
	Wrought cypress treated as described and with a moisture content not exceeding 12% to				
С	Fascia and verge board, size 200x25mm  Painting and Decorations	100	LM		
	<u>On Woodwork</u>				
	Prepare and apply one zinc plumbate primer and three coats of approved super gloss oil paint to:-				
D	Fascias; 200 to 300mm girth; external	100	LM		
	On Metal work				
Е	General surfaces; over 300mm girth external	50	SM		
F	Small pipes of girth 100mm diameter	100	LM		
	Carried to Collection				
	COLLECTION				
	From page CS/12				
	From page CS/13				
	From page CS/14				
	From above				
	TOTAL FOR STRUCTURAL STEELWORK CARRIED TO SUMMARY				

Item	Description	Qty	Unit	Rate	Amount KSh
------	-------------	-----	------	------	------------

				_	
Item	Description	Qty	Unit	Rate	Amount KSh

Carried to Collection		
COLLECTION From page CS/16 From above		
TOTAL FOR BUILDERS WORKS CARRIED TO SUMMARY		

Item	Description	Otv	Unit	Rate	Amount KSh
100111	Description	2.7	CILL	Tute	miount Ron

	5.01			
ELEM	SUMMARY ENT NO. TITLE		NO. OF UNITS	AMOUNT KSh
1	SUBSTRUCTURE (ALL PROVISIONAL)	CS/4	1	
2	R.C FRAME	CS/5	1	
3	WALLING	CS/6	1	
4	DOORS	CS/7	1	
5	WINDOWS	CS/8	1	
6	FINISHES	CS/10	1	
7	BALUSTRADING & RAILINGS	CS/11	1	
8	STRUCTURAL STEELWORK & ROOFING	CS/15	1	
9	BUILDERS WORK IN SPECIALISTS WORKS	CS/17	1	
	TOTAL FOR 1N0. STORE		x1	

Item	Description	Qty	Unit	Rate	Amount KSh
	ELEMENT NO. 1				
	PAVING & DRAINAGE AROUND BUILDINGS				
A	Excavate and Level the area around the building including carting away of any surplus material.	317	SM		

	Stor	e		•	
В	Provide, place and compact 100mm thick murram to make up levels round the building.	317	SM		
С	Provide and place 50mm thick quary dust as blinding for laying paving slabs.	317	SM		
D E	Provide, lay and joint 600x600x50mm pcc paving slabs.  Lay 150x100mm conc. class 15 as edgings to the paving slabs	317 300	SM LM		
	Storm Drain around the buildings  Excavate a trench for 150x750 mm shallow IBD depth				
F	not exceeding 300mm, back fill and cart away the surplus excavated material.	300	LM		
G	Ditto; for 125x390, ditto;. 20		LM		
Н	Provide, place and compact 100mm thick murram as and to make up the necessary levels for 175x750mm IBD.	base 300	LM		
J	Ditto; for 125x390, ditto;. 20		LM		
K	Provide, lay and joint 150x750x600mm pcc Shallow IBD. 300 all to detail (50) 5330.		LM		
L	Ditto; for 125x390, ditto;. 20		LM		
M	Provide and install 150mm Diameter UPVC service ducts with 100mm concrete surround	100	LM		
	TOTAL FOR PAVING & DRAINAGE AROUND BUILDINGS				

Item	Description	Amoun
	MAIN WORKS SUMMARY	
A	Gin House	
В	Store	
С	Paving & Drainage Around Building	
	TOTAL FOR MAIN WORKS CARRIED TO MAIN	
	SUMMARY	

# **PROVISIONAL SUMS**

Item	Description		Amount
	PROVISIONAL SUMS		
A	Allow a provisional sum of Kenya Shillings Eight Million ( <b>Ksh 8,000,000</b> /=) only to cover contingencies		8,000,000.00
	TOTAL FOR PROVISIONAL SUMS CARRIED TO		0 000 000 00
	GRAND SUMMARY		8,000,000.00


# **GRAND SUMMARY**

# PROPOSED CONSTRUCTION OF PAVI KWALE CO-OPERATIVE UNION GINNERY AT KINONDO, KWALE COUNTY

# W.P. ITEM NO. D116/CO/KWL/2001 JOB NO. 10826A

BILL NO.	DESCRIPTION	FOR TENDERER USE ONLY	FOR OFFICIAL USE ONLY
	GRAND SUMMARY	KSHS	KSHS
1	PARTICULAR PRELIMINARIES		
2	GENERAL PRELIMINARIES		
3	VOLUME 1 OF 3: MAIN WORKS		
4	<b>VOLUME 2 OF 3</b> : ELECTRICAL INSTALLATION WORKS	'	
5	<b>VOLUME 3 OF 3:</b> FIRE PROTECTION WORKS & VENTILATION		
6	PROVISIONAL SUMS		
_	TOTAL AMOUNT CARRIED TO FORM OF TENDER(INCLUSIVE OF V.A.T)		

Amount in Words:	
Official Stamp	
Signed:	
Designation:	
Date:	
WITNESSED BY	
Name	
Adress	
Date	



# PROPOSED CONSTRUCTION OF PAVI KWALE CO-OPERATIVE UNION GINNERY AT KINONDO, KWALE COUNTY PHASE 1 (ONE)

# TENDER SPECIFICATIONS AND BILLS OF QUANTITIES FOR ELECTRICAL INSTALLATION WORKS

## WP ITEM NO. D116/CO/KWL/2001 - JOB NO. 10826A

# **VOLUME 2 OF 3**

### **CLIENT**

# STATE DEPARTMENT FOR CO-OPERATIVES P.O.BOX 30547-00800 NAIROBI

PROJECT MANAGER ARCHITECT

WORKS SECRETARY CHIEF ARCHITECT

S.D.P.W S.D.P.W

P.O.BOX 30743-00100 P.O.BOX 30743-00100

NAIROBI NAIROBI

<u>QUANTITY SURVEYOR</u> <u>ELECTRICAL ENGINEER</u>

CHIEF QUANTITY SURVEYOR CHIEF ENGINEER (ELECTRICAL)

S.D.P.W S.D.P.W

P.O.BOX 30743-00100 P.O.BOX 30743-00100

NAIROBI NAIROBI

STRUCTURAL ENGINEER	MECHANICAL ENGINEER
CHIEF ENGINEER (STRUCTURAL)	<b>CHIEF ENGINEER (MECHANICAL-B.S)</b>
S.D.P.W	S.D.P.W
P.O.BOX 30743-00100	P.O.BOX 30743-00100
NAIROBI	NAIROBI
O	OCT. 2023

MINISTRY OF AGRICULTURE, LIVESTOCK, FISHERIES AND



TENDER SPECIFICATIONS AND BILLS OF QUANTITIES FOR ELECTRICAL INSTALLATION WORKS

# CO-OPERATIVES

# STATE DEPARTMENT FOR CO-OPERATIVES

# PROPOSED CONSTRUCTION OF PAVI KWALE CO-OPERATIVE UNION GINNERY AT KINONDO, KWALE COUNTY PHASE 1 (ONE)

W.P. ITEM NO. D116 CO/KWL/2001 JOB NO. 10826A

# **VOLUME 2**

#### CLIENT

PRINCIPAL SECRETARY, STATE DEPRTMENT FOR COOPERATIVES P.O. BOX 30547 - 00100, NAIROBI

### PROJECT MANAGER

WORKS SECRETARY STATE DEPARTMENT OF PUBLIC WORKS P.O BOX 30743-00100 NAIROBI

### **ARCHITECT**

CHIEF ARCHITECT
STATE DEPARTMENT OF PUBLIC WORKS
P. O. BOX 30743 – 00100
NAIROBI

## **QUANTITY SURVEYOR**

CHIEF QUANTITY SURVEYOR STATE DEPARTMENT OF PUBLIC WORKS P. O. BOX 30743 – 00100 NAIROBI **ELECTRICAL ENGINEER** 

CHIEF ENGINEER (ELECTRICAL) STATE DEPARTMENT OF PUBLIC WORKS P. O. BOX 41191 – 00100 NAIROBI

MECHANICAL ENGINEER
CHIEF ENGINEER (MECHANICAL (BS))
STATE DEPARTMENT OF PUBLIC WORKS
P. O. BOX 41191 – 00100

NAIROBI

STRUCTURAL ENGINEER
CHIEF ENGINEER (STRUCTURAL)
STATE DEPARTMENT OF PUBLIC WORKS
P. O. BOX 30743 – 00100
NAIROBI

# **TABLE OF CONTENTS**

TITLE	<u>PAGE</u>
Contents	i)

Definitions	. ii)
SECTION A: Instructions to Tenderers	. EIW-A/1 - A/4
SECTION B: General Specifications of Materials and Works	EIW-B/1 - B/17
SECTION C: Schedule of Contract Drawings	EIW-C/1
SECTION D: Particular Specifications of Materials and Works	EIW-D/1 - D/3
SECTION E: Schedule of Unit Rates.	. EIW-E/1 - E/3
SECTION F: Bills of Quantities	. EIW-F/1 - F/10
SECTION G: Technical Schedule	EIW-G/1 – G/2
SECTION H: Standard Forms	EIW-H/1 – H/13

The following terms and expressions used in the contract document shall have the following meanings:

The Employer Principal Secretary

State Department for Cooperatives

P.O Box 30547-00100,

Nairobi

Project Manager The Works Secretary

State Department of Public Works

P.O. Box 30743 - 00100

Nairobi

Architect Chief Architect

State Department of Public Works

P. O. Box 30743 - 00100

Nairobi

Electrical Engineer Chief Engineer (Electrical)

State Department of Public Works

P. O. Box 41191 – 00100

Nairobi

Mechanical Engineer Chief Engineer (Mechanical [Bs])

State Department of Public Works

P. O. Box 41191 - 00100

Nairobi

Quantity Surveyor Chief Quantity Surveyor

State Department of Public Works

P. O. Box 30743 - 00100

Nairobi

Structural Engineer Chief Engineer (Structural)

State Department of Public Works


P. O. Box 30743 - 00100

Nairobi

Contractor The firm appointed to carry out Builders Works.

Sub-contractor The firm appointed to carry out Electrical Installation Works

The Site The Site is Located at Kinondo – Kwale County



## **INSTRUCTIONS TO TENDERERS**

## CONTENTS

## **DESCRIPTION**

Contents		EIW/A-1
Tender Evaluation	Criteria	FI\\\/\\\ _2 _ FI\\\/\\\\ _4

## Note.

This criterion shall be used to evaluate the bidders proposed to carry out the specialized works who shall be domestic subcontractors to the main bidder on award of the contract.

## TENDER EVALUATION CRITERIA

After tender opening, the tenders will be evaluated in 2 stages, namely:

- 1. Preliminary Evaluation;
- 2. Technical Evaluation;

Note: This criterion shall be used to evaluate sub contracts

## STAGE 1: PRELIMINARY EVALUATION

This stage of evaluation shall involve examination of the mandatory requirements as set out in the Tender Advertisement Notice or Letter of Invitation to Tender and any other conditions stated in the bid document. These conditions shall include the following:

S/No	PRELIMINARY EVALUATION CRITERIA / MANDATORY REQUIREMENTS
Electrica	l Installation Works
MR1	Company Certificate of incorporation/registration;
MR2	Valid Tax Compliance Certificate;
MR3	Current certificate of Registration with National Construction Authority (NCA 6 and
	above) in Electrical Installations;
MR4	Valid Current Annual NCA contractor's Practicing license;
MR5	Current Class of License with Energy and Petroleum Regulatory Authority (EPRA Class B
	and above)
MR7	Compliance with Technical Specifications

#### Note

On compliance with Technical Specifications, bidders shall supply equipment/items which comply with the technical specifications set out in the bid document. In this regard, the bidders will be required to submit relevant technical brochures/catalogues with the tender document, highlighting (using a mark-pen or highlighter) the Catalogue Number/model of the proposed items. Such brochures/catalogues should indicate comprehensive relevant data of the proposed equipment/items which should include but not limited to the following:

- (i) Standards of manufacture;
- (ii) Performance ratings/characteristics;
- (iii) Material of manufacture;
- (iv) Electrical power ratings; and
- (v) All other requirements as indicated in the technical specifications of the bid.

The bid will then be analyzed, using the information in the technical brochures, to determine compliance with <u>technical specifications</u> for the works/items as indicated in the tender document. Bidders not complying with any of the <u>technical specifications</u> shall be adjudged to be technically

non-responsive while those meeting all the technical specifications shall be adjudged to be technically responsive.

The tenderer shall also fill in the Technical Schedule as specified in the tender document for Equipment and Items indicating the Country of Origin, Model/Make/Manufacturer and catalogue numbers of the Items/Equipment they propose to supply.

The tenderers who do not satisfy any of the above mandatory requirements shall be considered NonResponsive and their tenders will not be evaluated further.


#### **STAGE 2: TECHNICAL EVALUATION**

The following table shall be used to determine the bidder's responsiveness to the technical specifications.

## Compliance to Technical Specifications (Electrical Works)

	DESCRIPTION (as described in	Contractor Proposed ( Attach Brochures and catalogue)		Compliant/ Non- Compliant	
ITEM	particular specification)	TYPE/MAKE	MODEL NO.	COUNTRY OF ORIGIN	Compilant
1.0	Light Fittings				
1.0	-High bay LED				
	-600 x600 LED panel				
	-LED Floodlight				
	-Recessed Circular				
	LED				
	-Exit Signs				
	-LED Batten fittings				
2.0	Distribution Boards				
3.0	Consumer Unit				
4.0	MCBs				
5.0	Power Cables				
6.0	Sockets				
7.0	Switches				
8.0	DP Switches				
9.0	SP Isolators				
10.0	TPN Isolators				
11.0	Industrial Sockets				

11.0	Fire Alarm Panel		
12.0	Smoke Detectors		
13.0	Fire Alarm Sounders		



# PART 1. GENERAL SPECIFICATIONS OF WORKS

	1.1	General
	1.2	Standard of Materials
	1.3	Workmanship
	1.4	Procurement of Materials
	1.5	Shop Drawings
	1.6	Record Drawings
	1.7	Regulations and Standards
	1.8	Setting out Works
PA	.RT 2. <u>G</u> E	ENERAL SPECIFICATIONS OF ELECTRICAL WORKS
	2.1	Position of Electrical Plant and Apparatus
	2.2	M.C.B Distribution Panels and Consumer Units
	2.3	Fused Switchgear and Isolators
	2.4	Conduits and Conduit Runs
	2.5	Conduit Boxes and Accessories
	2.6	Labels
	2.7	Earthing
	2.8	Cables and Flexible Cords
	2.9	Armoured PVC Insulated and Sheathed Cables
	2.10	Cable Supports; Markers and Tiles

PVC Insulated Cables

Heat Resisting Cables

Flexible Cords

2.11

2.12

2.13

2.14	Cable Ends and phase Colours
2.15	Cable Insulation Colours
2.16	Sub-circuit Wiring
2.17	Space Factor
2.18	Insulation
2.19	Lighting Switches
2.20	Sockets and Switched sockets
2.21	Fused Spur Boxes
2.22	Cooker Outlets
2.23	Connectors
2.24	Lamp holders
2.25	LED Lamps
2.26	lighting Fittings Street lighting Lanterns
2.27	Position of Points and Switches
2.28	Street/Security Lighting Columns
2.29	Timing Control Switch
2.30	Wiring System for Street Lighting
2.31	Metal control Pillar
2.32	Current Operated Earth leakage circuit breaker
2.33	MV Switchboard
2.34	Steel Conduits and Steel Trunking
2.35	Testing on Site

## PART 1. GENERAL SPECIFICATIONS OF WORKS

#### 1.1 GENERAL

This specification is to be read in conjunction with the drawings which are issued with it. Bills of quantities shall be the basis of all additions and omissions during the progress of the works.

#### 1.2 STANDARD OF MATERIALS

Where the material and equipment are specifically described and named in the Specification followed by approved equal, they are so named or described for the purpose of establishing a standard to which the sub-contractor shall adhere.

Should the Sub-contractor install any material not specified herein before receiving approval from the proper authorities, the Engineer shall direct the Sub-contractor to remove the material in question immediately. The fact that this material has been installed shall have no bearing or influence on the decision by the Engineer.

All materials condemned by the Engineer as not approved for use, are to be removed from the premises and suitable materials delivered and installed in their place at the expense of the Subcontractor. All materials required for the works shall be new and the best of the respective kind and shall be of a uniform pattern.

#### 1.3 WORKMANSHIP

The workmanship and method of installation shall conform to the best standard practice. All work shall be performed by a skilled tradesman and to the satisfaction of the Engineer. Helpers shall have qualified supervision.

Any work that does not in the opinion of the Engineer conform to the best standard practice will be removed and reinstated at the Sub-contractors expense.

Permits, Certificates or Licenses must be held by all tradesmen for the type of work; in which they are involved where such permits, certificates or licenses exist under Government legislation.

#### 1.4 PROCUREMENT OF MATERIALS

The sub-contractor is advised that no assistance can be given in the procurement or allotment of any materials or products to be used in and necessary for the construction and completion of the work.

Sub-contractors are warned that they must make their own arrangements for the supply of materials and/or products specified or required.

#### 1.5 SHOP DRAWINGS

Before manufacture or Fabrication is commenced the sub-contractor shall submit Two copies of detailed drawings of all control pillars, meter cubicles, medium voltage switchboards including their components showing all pertinent information including sizes, capacities, construction details, etc, as may be required to determine the suitability of the equipment for the approval of the Engineer.

Approval of the detailed drawings shall not relieve the sub-contractor of the full responsibility of errors or the necessity of checking the drawings himself or of furnishing the materials and equipment and performing the work required by the plans and specifications.

#### 1.6 RECORD DRAWINGS

These diagrams and drawings shall show the completed installation including sizes, runs and arrangements of the installation. The drawings shall be to scale not less than 1:50 and shall include plan views and section.

The drawings shall include all the details which may be useful in the operation, maintenance or subsequent modifications or extensions to the installation.

Three sets of diagrams and drawings shall be provided, all to the approval of the Engineer.

One coloured set of line diagrams relating to operating and maintenance instructions shall be framed and, mounted in a suitable location.

#### 1.7 REGULATIONS AND STANDARDS

All work executed by the Sub-contractor shall comply with the current edition of the "Regulations" for the Electrical Equipment of Buildings, issued by the Institution of Electrical Engineers, and with the Regulations of the Local Electricity Authority.

Where the two sets of regulations appear to conflict, they shall be clarified with the Engineers. All materials used shall comply with relevant Kenya Bureau of Standards Specification.

## 1.8 SETTING OUT WORK

The sub-contractor at his own expenses; is to set out works and take all measurements and dimensions required for the erection of his materials on site; making any modifications in details as may be found necessary during the progress of the works, submitting any such modifications or alterations in detail to the Engineer before proceeding and must allow in his Tender for all such modifications and for the provision of any such sketches or drawings related thereto.

## PART 2. GENERAL SPECIFICATIONS OF ELECTRICAL WORKS

#### 2.1 POSITIONS OF ELECTRICAL PLANT AND APPARATUS

The routes of cables and approximate positions of switchboards etc, as shown on the drawings shall be assumed to be correct for purpose of Tendering, but exact positions of all electrical Equipment and routes of cables must be agreed on site with the Engineer before any work is carried out.

#### 2.2 MCB DISTRIBUTION PANELS AND CONSUMER UNITS

All cases of MCB Panels and consumer units shall be constructed in heavy gauge sheet with hinged covers.

Removable undrilled gland plates shall be provided on the top and bottom of the cases. Miniature circuit breakers shall be enclosed in moulded plastic with the tripping mechanism and arc chambers separated and sealed from the cable terminals.

The operating dolly shall be trip free with a positive movement in both make and break position. Clear indication of the position of the handle shall be incorporated.

The tripping mechanism shall be on inverse characteristic to prevent tripping in temporary overloads and shall not be affected by normal variation in ambient temperature.

A locking plate shall be provided for each size of breaker; A complete list of circuit details on typed cartridge paper glued to stiff cardboards and covered with a sheet of perspex, and held in position with four suitable fixings, shall be fitted to the inner face of the lids of each distribution panel. The appropriate MCB ratings shall be stated on the circuit chart against each circuit in use: Ivorine labels shall be secured to the insulation barriers in such a manner as to indicate the number of the circuits shown on the circuit chart.

Insulated barriers shall be fitted between phases, and neutrals in all boards, and to shroud live parts.

Neutral cables shall be connected to the neutral bar in the same sequence as the phase cables are connected to the MCB's. This shall also apply to earth bars when installed.

#### 2.3 FUSED SWITCHGEAR AND ISOLATORS

All fused switchgear and isolators whether mounted on machinery, walls or industrial panels shall conform to the requirements of KS 04 – 226 PART: 1: 1985.

All contacts are to be fully shrouded and are to have a breaking capacity on manual operations as required by KS 04 - 182: 1980.

Fuse links for fused switches are to be of high rupturing capacity cartridge type, conforming to KS 04 – 183: 1978.

Isolators shall be load breaking/fault making isolators.

Fused switches and isolators are to have separate metal enclosures. Mechanical interlocks are to be provided between the door and main switch operating mechanism so arranged that the door may not be opened with the switch in the 'ON' position. Similarly; it shall not be possible to close the switch with the door open except that provision to defeat the mechanical interlock and close the switch with the door in the open position for test purposes. The 'ON' and 'OFF' positions of all switches and isolators shall be clearly indicated by a mechanical flag indicator or similar device. In T.P & N fused switch units, bolted neutral links are to be fitted.

#### 2.4 CONDUITS AND CONDUIT RUNS

Conduit systems are to be installed so as to allow the loop-in system of wiring:

All conduits shall be black rigid super high impact heavy gauge class 'A' PVC in accordance with KS 04 – 179: 1988 and IEE Regulations. No conduit less than 20mm in diameter shall be used anywhere in this installation.

Conduit shall be installed buried in plaster work and floor screed except when run on wooden or metal surface when they will be installed surface supported with saddles every 600mm. Conduit run in chases shall be firmly held in position by means of substantial pipe hooks driven into wooden plugs.

The Sub-contractor's attention is drawn to the necessity of keeping all conduits entirely separate from other piping services such as water and no circuit connections will be permitted between conduits and such pipes.

All conduits systems shall be arranged wherever possible to be self-draining to switch boxes and conduit outlet points for fittings:

The systems, when installed and before wiring shall be kept plugged with well fitting plugs and when short conduit pieces are used as plugs, they shall be doubled over and tied firmly together with steel wire; before wiring all conduit systems shall be carried out until the particular section of the conduit installation is complete in every respect.

The sets and bends in conduit runs are to be formed on site using appropriate size bending springs and all radii of bends must not be less than 2.5 times the outside diameter of the conduit. No solid or inspection bends, tees or elbows will be used.

Conduit connections shall either be by a demountable (screwed up) assembly or adhesive fixed and water tight by solution. The tube and fittings must be clean and free of all grease before applying the adhesive. When connections are made between the conduit and switch boxes, circular or nonscrewed boxes, care shall be taken that no rough edges of conduit stick out into the boxes.

Runs between draw in boxes are not to have more than two right angle bends or their equivalent. The sub-contractor may be required to demonstrate to the Engineers that wiring in any particular run is easily withdrawable and the sub-contractor may, at no extra cost to the contract; be required to install additional draw-in boxes required. If conduit is installed in straight runs in excess of 6000mm, expansion couplings as manufactured by Egatube shall be used at intervals of 6000mm.

Where conduit runs are to be concealed in pillars and beams, the approval of the Structural Engineer, shall be obtained. The sub-contractor shall be responsible for marking the accurate position of all holes chases etc., on site, or if the Engineer so directs, shall provide the Main Contractor with dimensional drawings to enable him to mark out and form all holes and chases. Should the subcontractor fail to

inform the main contractor of any inaccuracies in this respect they shall be rectified at the sub-contractors expense.

It will be the Sub-contractors responsibility to ascertain from site, the details of reinforced concrete or structural steelwork and check from the builder's drawings the positions of walls, structural concrete and finishes. No reinforced concrete or steelwork may be drilled without first obtaining the written permission of the Structural Engineer.

The drawings provided with these specifications indicate the appropriate positions only of points and switches, and it shall be the Sub-Contractors responsibility to mark out and centre on site the accurate positions where necessary in consultation with the Architect and the Engineer. The sub-contractor alone shall be responsible for the accuracy of the final position.

#### 2.5 CONDUIT BOXES AND ACCESSORIES

All conduit outlets and junction boxes are to be either malleable iron and of standard circular pattern of the appropriate type to suit saddles being used or super high impact PVC manufactured to KS 04 – 179: 1983.

Small circular pattern boxes are to be used with conduits up to and including 25mm outside diameter. Rectangular pattern adaptable boxes are to be used for conduits of 32mm outside diameter and larger. For drawing in of cables in exposed runs of conduit, standard pattern through boxes are to be used:

Boxes are to be not less than 50mm deep and of such dimensions as will enable the largest appropriate number of cables for the conduit sizes to be drawn in without excessive bending.

Outlet boxes for lighting fittings are to be of the loop-in type where conduit installation is concealed and the sub-contractor shall allow one such box per fitting, except where fluorescent fittings are specified when two such boxes per fitting shall be fitted flush with ceiling and if necessary fitted with break joint rings. Pattresses shall be fitted where required to outlets on surface conduit runs.

Adaptable boxes are to of PVC or mild steel (of not less than 12swg) and black enamelled or galvanised finish according to location. They shall be of square or oblong shape location. They shall be of square or oblong shape complete with lids secured by four 2 BA brass roundhead screws; No adaptable box shall be less than 75mm x 75mm x 50mm or larger than 300mm x 300mm x 75mm and shall be adequate in depth in relation to the size of conduit entering it. Conduits shall only enter boxes by means of conduit bushes.

#### 2.6 LABELS

Labels fitted to switches and fuse boards; -

- (i) Shall be Ivorine engraved black on white.
- (ii) Shall be secured by R.H brass screws of same manufacturing throughout.
- (iii) Shall be indicated on switches:
  - a) Reference number of switches
  - b) Special current rating
  - c) Item of equipment controlled
- (iv) Shall indicate on MCB panels

- d) Reference number
- e) Type of board, i.e;, lighting, sockets, etc,.
- f) Size of cable supplying panel
- g) where to isolate feeder cable
- (v) Shall be generally not less than 75mm x 50mm.

#### 2.7 EARTHING

The earthing of the installation shall comply with the following requirements;-

- (i) It shall be carried out in accordance with the appropriate sections of the current edition of the Regulations, for the Electrical Equipment of Buildings issued by Institute of Electrical Engineers of Great Britain.
- (ii) At all main distribution panels and main service positions a 25mm x 3mm minimum cross-sectional area Copper tape shall be provided and all equipment including the lead sheath and armouring of cables, distribution boards and metal frames shall be bonded thereto.
- (iii) The earth tape in Sub-clause (ii) shall be connected by means of a copper tape or cable of suitable cross-sectional area to an earth electrode which shall be a copper earth rod (see later sub-clause).
- (iv) All tapes to be soft high conductivity copper, untinned except where otherwise specified and where run underground on or through walls, floors, etc., it shall be served with corrosion resisting tape or coated with corrosion compound and braided
- (v) Where the earth electrode is located outside the building a removable test link shall be provided inside the building as near as possible to the point of entry to the tape, for isolating the earth electrode for testing purposes.
- (vi) Earthing of sub-main equipment shall be deemed to be satisfactory where the submain cables are M.I.C.S. or conduit with separate earth wire, and installation is carried out in accordance with the figures stated in the current edition of the I.E.E Regulations.
- (vii) Where an earth rod is specified (see Sub-clause (iii) it shall be proprietary manufacture, solid hand drawn copper of 15mm diameter driven into the ground to a minimum depth of 3.6M. It shall be made up to 1.2m sections with internal screw and socket joints and fitted with hardened steel tip and driving cap.
- (viii) Earth plates will not be permitted
- (ix) Where an earth rod is used the earth resistance shall be tested in the manner described in the current edition of the IEE Regulations, by the Sub-Contractor in the presence of the Engineer and the Sub-Contractor shall be responsible for the supply of all test equipment.
- (x) Where copper tape is fixed to the building structure it shall be by means of purpose made non-ferrous saddles which space the conductor away from the structure a minimum distance of 20mm. Fixings, shall be made using purpose made plugs; No fixings requiring holes to be drilled through the tape will be accepted.

- (xi) Joints in copper tape shall be tinned before assembly riveted with a minimum of two copper rivets and seated solid.
- (xii) Where holes are drilled in the earth tape for connection to items of equipment the effective cross sectional area must not be less than required to comply with the IEE regulations.
- (xiii) Bolts, nuts and washers for any fixing to the earth tape must be of non-ferrous material.
- (xiv) Attention is drawn to the need for the earthing metal parts of lighting fittings and for bonding ball joint suspension in lighting fittings.

#### 2.8 CABLES AND FLEXIBLE CORDS

All cables used in this Sub-Contract shall be manufactured in accordance with the current appropriate Kenya standard Specification which are as follows: -

P.V.C. Insulated Cables and Flexible Cords --- Ks 04-192:1988

P.V.C Insulated Armoured Cables --- Ks 04-194:1990

Armouring of Electric cables --- Ks 04-290:1987

The successful Sub-Contractor will, at the Engineers discretion be required to submit samples of cables for the Engineers approval; the Engineer reserves the right to call for the cables of an alternative manufacture without any extra cost being incurred.

P.V.C. insulated cables shall be 500/1000 volt grade. No cables smaller than 1.5mm<sup>2</sup> shall be used unless otherwise specified. The installation and the finish of cables shall be as detailed in later clauses. The colour of cables shall conform to the details stated in the "Cable Braid and insulation Colours" Clause.

#### 2.9 ARMOURED P.V.C. INSULATED AND SHEATHED CABLES:

Shall be 600/1000-volt grade manufactured to Ks 04-194:1988 and Ks 04-187/188 with copper stranded conductors.

The wire armour of the cable shall be used wholly as an earth continuity conductor and the resistance of the wire armour shall have a resistance not more than twice of the largest current carrying conductor of the cable.

P.V.C./S.W.A./P.V.C. cables shall be terminated using "Telecom" "B" type or approved equal or approved equal glands and a P.V.C. tapered sleeve shall be provided to shroud each gland.

#### 2.10 CABLE SUPPORTS, MARKERS AND TILES

All PVC/SWA/PVC cables run inside the building shall be fixed in rising ducts or on ceilings by means of die cast cable hooks or clamps, of appropriate size to suit cables, fixed by studs and back nuts to their channel sections.

Alternatively, fixing shall be by BICC claw type cleating system with die-cast cleats and galvanized mild steel back straps or similar approved equal method. For one or two cables run together the cleats shall be fixed a special channel section supports or backstraps described above which shall in turn be secured to walls or ceilings of ducts by rawbolts.

In excessively damp or corrosive atmospheric conditions special finishes may be required and the Subcontractor shall apply to the Engineer for further instructions before ordering cleats and channels for such areas.

The above type of hooks and clamps and channels or cleats and blackstraps shall also be used for securing cables in vertical ducts.

Cables supports shall be fixed at 600mm maximum intervals, the supports being supplied and erected under this Sub-contract. Saddles shall not be used for supporting cables nor any other type of fixing other than one of the two methods described above or other system which has received prior approval of the Engineer;

Cables are to be kept clear of all pipe work and the Sub-contractor shall work in close liaison with other services Sub-contractors.

The Sub-Contractor shall include for the provision of fixing of approved type coloured slip on cables end markers to indicate permanently the correct phase and neutral colours on all ends.

Provision shall be made for supplying and fixing approved non-corrosive metal cable markers to be attached to the outside of all PVC/SWA/PVC cables at 15mm intervals indicating cable size and distinction.

Where PVC/SWA/PVC cables are outside the building they shall be laid underground 750mm deep with protecting concrete interlocking cover tiles laid over which shall be provided and laid under this Subcontract.

All necessary excavations and reinstatement of ground including sanding or trenches will be carried out by the Sub-Contractor, unless otherwise stated.

#### 2.11 PVC INSULATED CABLES

Shall be of non-braided type as CMA reference 6491  $\times$  600/1000/1000 volt grade cables, or equal approved.

PVC cables shall conform to the details of the "Cables and Flexible cords" and "Cable Braid and Insulation Colours" clauses.

#### 2.12 HEAT RESISTING CABLES

Final connections to cookers, water heaters, etc., shall be made using butyl rubber insulated cable as CMA reference 610 butyl (Single core 600/1000 Volt).

This type of cable shall be used in all instances where a temperature exceeding 100°F, but not exceeding 150°F is likely to be experienced. Final connections to all lighting fittings (and other equipment where

a temperature in excess of 150°c likely to be experienced) shall be made using silicon rubber insulated cable or equal and approved.

#### 2.13 FLEXIBLE CORDS

Shall be in accordance with the "Cable and Flexible Cords" clause. No cord shall be less than 24/0.2mm in size unless otherwise specified.

Circular white twin TRS flex shall be used for plain pendant fittings up to 100 watts. For all other types of lighting fittings the flexible cable shall be silicone rubber insulated.

No polythene insulated flexible cable shall be used in any lighting fitting or other appliance (see "Heat Resisting Cables" Clause 30).

#### 2.14 CABLE ENDS AND PHASE COLOURS

All cable ends connected up in switchgear, MCB panels etc;, shall have the insulation carefully cut back and the ends sealed with Hellerman rubber slip on cable end markers.

The markers shall be of appropriate phase colour for switch and all other live feeds to the details of the "Cable Insulation Colours" clause. Black cable with black end markers shall only be used for neutral cables.

#### 2.15 CABLE INSULATION COLOURS

Unless otherwise stated in later clauses the insulation colours shall be in accordance with the following table.

Where other systems are installed the cable colours shall be in accordance with the details stated in the appropriate clause.

SYSTEM	INSULATION COLOUR	<u>CABLE END</u> MARKER
1) Main and Sub-Main		THE WINDER
a) Phase	Red	Red
b) Neutral	Black	Black
2) Sub-Circuits Single Phase		
a) Phase	Red	Red
b) Neutral	Black	Black

#### 2.16 SUB-CIRCUIT WIRING

For all lighting and sockets wiring shall be carried out in the "looping in" system and there shall be no joints whatsoever. No lighting circuits shall comprise more than 20 points when protected by 10A MCB. Cables with different cross-section area of copper shall not be used in combination.

Lighting circuits P.V.C. cable.

(i) 1.5mm<sup>2</sup> for all lighting circuits indicated on the drawing.

Power circuits P.V.C cable (minimum sizes).

- (i) 2.5mm<sup>2</sup> for one, two or three 5Amp sockets wired in parallel.
- (ii) 2.5mm<sup>2</sup> for one 15Amp socket.
- (iii) 2.5mm² for maximum of ten switched 13 Amp sockets wired from 30 Amp MCB.

The wiring sizes for lighting circuits and sockets are shown on the drawings. In such cases, the sizes shown on the drawings shall prevail over the sizes specified.

Wiring sizes for other appliances shall be shown on the drawing or specified in later clauses of this specification.

## 2.17 SPACE FACTOR

The maximum number of cables that may be accommodated in a given size of conduit or trunking or duct is not to exceed the number in Tables B.5 and B.6 or as stated in Regulation B.91, B.117 and B.118 of the I.E.E Regulations whichever is appropriate.

#### 2.18 INSULATION

The insulation resistance to earth and between poles of the whole wiring system, fittings and lumps, shall not be less than the requirements of the latest edition of the I.E.E Regulations. Complete tests shall be made on all circuits by the Sub-contractor before the installations are handed over.

A report of all tests shall be furnished by the Sub-Contractor to the Engineer. The Engineer will then check test with his own instruments if necessary.

#### 2.19 LIGHTING SWITCHES

These shall be mounted flush with the walls, shall be contained in steel or alloy boxes and shall be of the gangs' ratings and type shown in the drawings. They shall be as manufactured by M.K. Electrical Ltd., or other equal and approved to KS 04 – 247: 1988

#### 2.20 SOCKETS AND SWITCHED SOCKETS

These shall be flush pattern in steel/pvc box and shall be of the gangs and type specified in the drawings.

They shall be 13- Amp, 3-pin, shuttered, switched and as manufactured by "M.K. Electrical Co. Ltd.", or other approved equal to KS 04 – 246: 1987

#### 2.21 FUSED SPUR BOXES

These shall be flush, D.P switched as in steel/pvc box and of type and make specified in the drawings complete with pilot light and as manufactured by "M. K. Electrical Company Ltd", or other approved equal. KS 04 – 247: 1988

#### 2.22 COOKER OUTLETS

These shall be flush mounted with 13-A switched socket outlet and neon indicator Lamps.

The cooker control units shall be as manufactured by "M.K. Electrical Company Ltd", or other approved equal KS 04 - 247: 1988

#### 2.23 CONNECTORS

Shall be specified in the drawings and appropriate rating. These shall be fitted at all conduit box lighting point outlets for jointing of looped P.V.C cables with flexible cables of specified quality.

#### 2.24 LAMPHOLDERS

Shall be of extra heavy H.O skirted and shall be provided for every specified lighting fitting and shall be B.C;, E.S;, or G.E.S as required. All E.S. and G.E.S. holders shall be heavy brass type (except for plain pendants where the reinforced bakelite type shall be used). The screwed cap of the E.S and G.E.S. holders shall be connected to the neutral.

Where lampholders are supported by flexible cable, the holders shall have "cord grip" arrangements and in the case of metal shades earthing screws shall be provided on each of the holders.

The Sub-Contractor must order the appropriate type of holder when ordering lighting fittings, to ensure that the correct types of holders are provided irrespective of the type normally supplied by the manufacturers.

#### 2.25 LAMPS

All lamps shall be suitable for normal stated supply voltage and the number and sizes of lamps detailed on the drawings shall be supplied and fixed. The Sub-Contractor must verify the actual supply voltage with the supply authority before ordering the lamps.

Tungsten filament lamps shall be manufactured in accordance with KS 04 - 112:1978 for general service lamps and KS 04 - 307:1985 for lamps other than general services. Tubular fluorescent lamps shall comply with KS 04 - 464:1982

LED lamps shall be used in all fittings unless otherwise specified. The minimum luminous flux allowed is 95 lumens per Watt, minimum life time of 50,000hrs, minimum power factor of 0.9, voltage range of 100-240V, THD <15% amongst others.

#### 2.26 LIGHTING FITTINGS AND STREET LIGHTING LANTERNS

This Sub-Contract shall include for the provision, handling charges, taking the delivery, safe storage, wiring (including internal wiring) assembling and erecting of all lighting fittings shown on the drawings.

All fittings and pendants shall be fixed to the conduit boxes with brass R/H screws. These to be in line with metal finish of fittings. The lighting fittings are detailed for the purpose of establishing a high standard of finish and under no circumstances will substitute fittings be permitted.

In case of rectangular shaped ceiling fittings, the extreme ends of the fittings shall be secured to suitable support in addition to the central conduit box fittings. Supports shall be provided and fixed by the Sub-Contractor.

The whole of the metal work of each lighting fittings shall be effectively bonded to earth. In the case of ball and/or knuckle joints short lengths of flexible cable shall be provided, bonded to the metal work on either side of the joints. If the above provisions are not made by the manufacturers -, the Subcontractor shall include cost of additional work necessary in his tender. See "Flexible Cords" clause for details of internal wiring of lighting fittings.

Minimum size of internal wiring shall be 20/0.20mm (23/0067). Each lighting fitting shall be provided with number type and size of lamps as detailed on the drawings. It is to be noted that some fittings are suspended as shown on the drawings.

Where two or more points are shown adjacent to each other on the drawings, e.g socket outlet and telephone outlet, they shall be lined up vertically or horizontally on the centre lines of the units concerned.

Normally, the units shall be lined up on vertical centre lines, but where it is necessary to mount units at low level they shall be lined up horizontally.

#### 2.27 POSITIONS OF POINTS AND SWITCHES

Although the approximate positions of all points are shown on the drawings, enquiry shall be made as to the exact positions of all M.C.B panels, lighting points, socket outlets etc, before work is actually commenced. The Sub-contractor must approach the Architect with regard to the final layout of all lights on the ceiling and walls.

The Sub-contractor must consult with the Engineer in liaison with the Clerk of Works, or the General Foreman on site regarding the positions of all points before fixing any conduit etc. The SubContractor shall be responsible for all alterations made necessary by the non-compliance with the clause.

#### 2.28 CURRENT OPERATED EARTH LEAKAGE CIRCUIT BREAKER

Current operated earth leakage circuit breaker shall conform to B.S.S. 4293:68 rated at 240 volts D.P. 50 cycles A.C. Mains.

The breaker shall be provided with test switch and fitted in weather proof enclosure for surface mounting. The rated load current and earth fault operating current shall be as specified in the drawings. These shall be as manufactured by Crabtree, Siemens or other equal and approved. When switches are arranged in their formation all necessary horizontal and vertical barriers shall be provided to ensure segregation from adjacent units. Means of locking the switch in the "OFF" position shall be provided.

#### 2.29 STEEL CONDUITS AND STEEL TRUNKING

Conduits shall be of heavy gauge class "B" welded to Standard specification KS 04-180:1985. In no case will conduit smaller than 20mm diameter be used on the works. Conduits installed within buildings shall be black enamelled finish except where specified otherwise. Where installed externally or in damp conditions they shall be galvanised. Conduit fittings, accessories or equipment used in conjunction with galvanised conduits shall also be galvanised or otherwise as approved by the service engineer.

Metal trunking shall be fabricated from mild steel of not less than 18 swg. All sections of trunking shall be rigidly fixed together and attached to the framework or fabric or the building at intervals of not less than 1.2m. Joint trunking shall not overhang fixing points by more than 0.5m.

All trunking shall be made electrically continuous by means of 25 x 3mm copper links across each joint and where the trunking is galvanised, the links shall be made by galvanised flat iron strips.

All trunking fittings (i.e. Bends, tees, etc) shall leave the main through completely clear of obstructions and continuously open except through walls and floors at which points suitable fire resisting barriers shall be provided as may be necessary. The inner edge of bends and tees shall be chamfered where cables larger than 35mm<sup>2</sup> are employed.

Where trunking passes through ceilings and walls the cover shall be solidly fixed to 150mm either side of ceilings and floors and 50mm either side of walls.

Screws and bolts securing covers to trunking or sections of covers together shall be arranged so that damage to cables cannot occur either when fixing covers or when installing cables in the trough.

Where trunking is used to connect switchgear of fuseboards, such connections shall be made by trunking fittings manufactured for this purpose and not by multiple conduit couplings.

Where vertical sections of trunking are used which exceed 4.5m in length, staggered tie off points shall be provided at 4.5m intervals to support the weight of cables.

Unless otherwise stated, all trunking systems shall be painted as for conduit.

Where a wiring system incorporates galvanised conduit and trunking, the trunking shall be deemed to be galvanised unless specified otherwise.

The number of cables to be installed in trunking shall be such as to permit easy drawing in without damage to the cables, and shall in no circumstances be such that a space factor of 45% is exceeded.

Conduit and trunking shall be mechanically and electrically continuous. Conduit shall be tightly screwed between the various lengths so that they butt at the socketed joints. The internal edges of conduit and all fittings shall be smooth, free from burrs and other defects.

Oil and any other insulating substance shall be removed from the screw threads; where conduits terminate in fuse-gear, distribution boards, adaptable boxes, non-spouted switchboxes, etc., they shall, unless otherwise stated, be connected thereto by means of smooth bore male brass bushes, compression washers and sockets. All exposed threads and abrasions shall be painted using an oil paint for black enameled tubing and galvanizing paint for galvanised tubing immediately after the conduits are erected. All bends and sets shall be made cold without altering the section of the conduit.

The inner radius of the bed shall not be less than four (4) times the outside diameter of the conduit. Not more than two right angle bends will be permitted without the inter-position of a draw-in-box. Where straight runs of conduit are installed, draw-in-boxes shall be provided at distances not exceeding 15mm. No tees, elbows, sleeves, either of inspection or solid type, will be permitted.

Conduit shall be swabbed out prior to drawing in cables, and they shall be laid so as to drain of all condensed moisture without injury to end connections.

Conduits and trunking shall be run at least 150mm clear of hot water and steam pipes, and at least 75mm clear of cold water and other services unless otherwise approved by the services engineer.

All boxes shall conform to KS 04 - 668: 1986, to be of malleable iron, and black enamelled or galvanised according to the type of conduit specified. All accessory boxes shall have threaded brass inserts.

Box lids where required shall be heavy gauge metal, secured by means of zinc plated or cadmium plated steel screws.

All adaptable boxes and lids of the same size shall be interchangeable.

Boxes used on surface work are to be tapped or drilled to line up with the conduit fixed in distance type saddles allowing clearance between the conduit and wall without the need for setting the conduit.

Where used in conjunction with mineral insulated copper sheathed cable, galvanized boxes shall be used and painted after erection.

Draw-in boxes in the floors are generally to be avoided but where they are essential they must be grouped in positions approved by the services engineer and covered and by the suitable floor traps, with non-ferrous trays and covers.

The floor trap covers are to be recessed and filled in with a material to match the floor surface.

The Sub-contractor must take full responsibility for the filling in of all covers, but the filling in material will be supplied and the filling carried out by the main building contractor.

Where buried in the ground outside the building the whole of the buried conduit is to be painted with two coats of approved bitumastic composition before covering up.

Where run on the surface, unpainted fittings and joints shall be painted with two coats of oil bound enamel applied to rust and grease free metalwork.

#### 2.30 TESTING ON SITE

The Sub-contractor shall conduct during and at the completion of the installation and, if required, again at the expiration of the maintenance period, tests in accordance with the relevant section of the current edition of the Regulations for the electrical equipment of buildings issued by the I.E.E of Great Britain, the Government Electrical Specification and the Electric Supply Company's By-Laws.


- (b) Tests shall be carried out to prove that all single pole switches are installed in the 'live' conductor.
- (c) Tests shall be carried out to prove that all socket outlets and switched socket outlets are connected to the 'live' conductor in the terminal marked as such, and that each earth pin is effectively bonded to the earth continuity system. Tests shall be carried out to verify the continuity of all conductors of each 'ring' circuit.

- (d) Phase tests shall be carried out on completion of the installation to ensure that correct phase sequence is maintained throughout the installation. Triplicate copies of the results of the above tests shall be provided within 14 days of the witnessed tests and the Sub-contractor will be required to issue to the service engineer the requisite certificate upon completion as required by the regulations referred to above.
- (e) Any faults, defects or omissions or faulty workmanship, incorrectly positioned or installed parts of the installation made apparently by such inspections or tests shall be rectified by the Subcontractor at his own expense.
- (f) The Sub-contractor shall provide accurate instruments and apparatus and all labour required to carry out the above tests. The instruments and apparatus shall be made available to the services engineer to enable him to carry out such tests as he may require.
- (g) The Sub-contractor shall generally attend on other contractors employed on the project and carry out such electrical tests as may be necessary.
- (h) The Sub-contractor shall test to the services engineer's approval and as specified elsewhere in this specification or in standards and regulations already referred to, all equipment, plant and apparatus forming part of the works and before connecting to any power or other supply and setting to work.
- (i) Where such equipment, etc., forms part of or is connected to a system whether primarily or of an electrical nature or otherwise (e.g. air conditioning system) the Sub-contractor shall attend on and assist in balancing, regulating testing and commissioning, or if primarily an electrical or other system forming part of works, shall balance, regulate, test and commission the system to the service engineer's approval.

#### APPENDIX TO GENERAL SPECIFICATIONS OF MATERIALS AND WORKS

The electrical sub-contractor shall comply with the following:-

- 1. Government Electrical Specifications No. 1 and No. 2.
- 2. All requirements of Kenya Power Company Limited, and Communications Authority of Kenya (CA).



## **SCHEDULE OF CONTRACT DRAWINGS**

1.0 There are currently no drawings in this contract.

The drawings shall however be availed, on award of the tender, to the sub-contractor.

# SECTION D PARTICULAR & TECHNICAL SPECIFICATIONS OF MATERIALS AND WORKS

## PARTICULAR SPECIFICATIONS OF MATERIALS AND WORKS

#### 1.0 SITE LOCATION

The location of the proposed works is at Kinondo – Kwale County.

#### 2.0 SCOPE OF WORKS

The works to be carried out under this sub-contract comprise of but not limited to the supply, installation, testing and commissioning of:

- Wiring and Installation of electrical fittings and accessories
- Installation of power distribution cables and control switchgear
- Installation of fire detection & alarm system
- Installation of power distribution board
- Trunking and conduiting works

#### 3.0 MATERIALS FOR THE WORKS

Materials shall be as specified in Section D and in the Bills of Quantities of this document which shall be read in conjunction with contract drawings. Alternative materials shall be accepted only after approval by the Project Manager.


#### 4.0 BROCHURES FOR ALL ELECTRICAL EQUIPMENT AND FITTINGS

For consideration and qualification tenderers shall, at their own cost, provide coloured manufacturer's brochures detailing technical literature and specifications of all the required Electrical equipment and fittings where applicable.

#### 5.0 TECHNICAL SPECIFICATIONS FOR LED LIGHT FITTINGS/LAMPS

LED PANEL LIGHT	FITTING		
IEC Compliant			
ltem	Minimum Specifications		
Brand	State the brand, model and attach Technical Brochure (Mandatory)		
Operating	O voltage range: 130-300 V ac		
	• frequency range: 45-55 Hz		
	O Power factor ≥ 0.9 lagging		
	O THD <15%		
	• Ambient temperature range -10 to +35 °Operating		
	<ul><li>Colour Consistency ≤ 5SDCM</li></ul>		

Performance	O luminous flux - 3600 lm
	• System efficacy > 90lm/W
	O Lamp colour temperature (NW)4000K / (CW)6500K
	O Colour Rendering Index >80
	<ul> <li>Median useful life ≥ 50,000 hrs</li> </ul>
	O Luminaire light beam spread - 120°
Standards Compliance	CB/EMC/CE
	O Driver/power unit/transformer - PSU-E
General	O Optical cover/lens type - Polystyrene bowl/cover prismatic
	O Protection class IEC - Safety class II (II)




#### SCHEDULE OF UNIT RATES

- 1. The tenderer shall insert unit rates against the items in the following schedules and may add such other items as he considers appropriate.
- 2. The unit rates shall include for supply, transport, insurance, delivery to site, storage as necessary, assembling, cleaning, installing, connecting, profit and maintenance in defects liability and any other obligation under this contract.
- 3. The unit rates will be used to assess the value of additions or omissions arising from authorised variations to the contract works.
- 4. Where trade names or manufacturer's catalogue numbers are mentioned in the specification, the reference is intended as a guide to the type of article or quality of material required. Alternative brands of equal and approved quality will be accepted.
- 5. The prices quoted shall be deemed to include for all obligations under the sub-contract including but not limited to supply of materials, labour, delivery to site, storage on site, installation, testing, commissioning and all taxes (including V.A.T, Withholding tax and all other taxes applicable at the time of tender).
- 6. Any bid returned with unfilled Schedule of Unit Rates shall be considered technically non- responsive, and the bidder shall automatically be disqualified.

# (MUST be completed by the Tenderer)

m	Description	Unit	044	Rate (KShs)
	The rates entered in the schedule unless otherwise stated	Unit	Qty	
	shall be the complete cost of supply, transportation,			
	Insurance, Installation etc, to be added or deducted from			
	the sub-contract Price in respect to variations ordered			
	during the course of the work.			
	Switchgear			
	Distribution Boards of the following types and ratings, as			
	EATON:			
	10 way TP&N with integral 125ampere isolating switch	No	1	
	12 way TP&N with integral 125 ampere isolating switch	No	1	
	12 way 17 & 10 with integral 123 ampere isolating switch	INO	1	
	PVC copper cables with conductors of the following			
	sizes:			
	6.0 sq. mm 2 core	m m	1	
	16.0 sq. mm 2 core	m	1	
			1	
	PVC/SWA/PVC insulated copper cables with conductors			
	of the following sizes: 10 sq. mm 4 core		1	
	16 ag mm 4 agm	m	1	
	16 sq. mm 4 core	m	1	
	<u>Conduit</u>			
	Supply and Installation per linear metre including fixing			
	of all accessories of PVC conduit of the following sizes:		_	
	25mm	m	1	
	32mm	m	1	
	As above but PVC sheathed flexible steel conduit:			
	20mm	m	1	
	25mm	m	1	
	32mm	m	1	
	Cable trunking and Tray			
	Supply & install sheet steel cable trunking complete with	44-	1	
	all necessary supports, fixings and dividing 50 x 25mm	m	l 1	
	75 x 50mm	m	1	

	100 x 50mm 250 x 50mm	m m	1 1	
Item	Description			Rate (KShs)
		Unit	Qty	
	Miniature circuit breakers Supply and installation into distribution board of <b>triple pole</b> MCB of the following ratings:			
	50 amperes	No	1	
	80 amperes	No	1	
	100 amperes	No	1	
	Earthing Equipment Supply, install and connect up complete, Per linear metre complete, 25x3.2 mm hard Drawn copper tape. As above but with PVC sleeve	m	1	
	Earth bonding wires of equivalent current Carrying capacity to the above copper tape	No.	1	
	Copper earth rod 20 mm diameter x 1.10 Metres length.	No.	1	
	As above but welding earthing stud as specified	No	1	
	Luminares Slim circular luminaire in brass finish with 13W LED	No	1	
	recessed			
	Recessed 8W LED downlight with 100mm diameter c/w Opal glass cover.	No	1	



#### **BILLS OF QUANTITIES**

#### A) PRICING OF PRELIMINARIES ITEMS.

Prices will be inserted against item of preliminaries in the sub-contractor's Bills of Quantities and specification. These Bills are designated as Bill No.1 in this Section. Where the sub-contractor fails to insert his price in any item he shall be deemed to have made adequate provision for this on various items in the Bills of Quantities. The preliminaries form part of this contract and together with other Bills of Quantities covers for the costs involved in complying with all the requirements for the proper execution of the whole of the works in the contract.

The Bills of Quantities are divided generally into three sections:-

#### a) Preliminaries – Bill 1

Sub-contractors preliminaries are as per those described in section C – sub-contractor preliminaries and conditions of contract. The sub-contractor shall study the conditions and make provision to cover their cost in this Bill. The number of preliminary items to be priced by the Tenderer has been limited to tangible items such as site office, temporary works and others. However the Tenderer is free to include and price any other items he deems necessary taking into consideration conditions he is likely to encounter on site.

#### b) Installation Items and Other Bills

The brief description of the items in these Bills of Quantities should in no way modify or supersede the detailed descriptions in the contract Drawings, conditions of contract and specifications.

The unit of measurements and observations are as per those described in clause 1.05 of the section C.

#### c) Summary

The summary contains tabulation of the separate parts of the Bills of Quantities carried forward with provisional sum, contingencies and any prime cost sums included. The sub-contractor shall insert his totals and enter his grand total tender sum in the space provided below the summary.

This grand total tender sum shall be entered in the Form of Tender provided elsewhere in this document

#### B) NOTES FOR BILLS OF QUANTITIES

- 1. The Bills of Quantities form part of the contract documents and are to be read in conjunction with the contract drawings and general specifications of materials and works.
- 2. The prices quoted shall be deemed to include for all obligations under the sub-contract including but not limited to supply of materials, labour, delivery to site, storage on site, installation, testing, commissioning and all taxes (including 16% V.A.T and all taxes applicable at the time of tender.
- 3 All prices omitted from any item, section or part of the Bills of Quantities shall be deemed to have been included to another item, section or part.
- 4. The brief description of the items given in the Bills of Quantities are for the purpose of establishing a standard to which the sub-contractor shall adhere to. Otherwise alternative brands of **equal** and **approved** quality will be accepted.

Should the sub-contractor install any material not specified here in before receiving **approval** from the Project Manager, the sub-contractor shall remove the material in question and, **at his own cost**, install the proper material.

- 5. The grand total of prices in the price summary page must be carried forward to the **Form of Tender**.
- 6. Tenderers must enclose, together with their submitted tenders, **detailed manufacturer's Brochures** detailing Technical Literature and specifications on the items they intend to offer.

This shall be used in the tender evaluation to determine the first line aesthetics and quality of fittings offered.

### PROPOSED CONSTRUCTION OF PAVI KWALE CO-OPERATIVE UNION GINNERY AT KINONDO, KWALE COUNTY

#### W.P. ITEM NO. D116 CO/KWL/2001 JOB NO. 10826A

#### **ELECTRICAL INSTALLATION WORKS**

#### **BILL NO.1: SUB-CONTRACT PRELIMINARIES**

ITEM	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
1	Discrepancies clause 1.02				
2	Conditions of sub-contract Agreement clause 1.03				
3	Payments clause 1.04				
4	Site location clause 1.06				
5	Scope of contract works clause 1.08				
6	Extent of contractors duties clause 1.09				
7	Firm price contract clause 1.12				
8	Variation clause 1.13				
9	Prime cost and provisional sum clause 3.14 (insert profit and attendance which is a percentage of expended PC or provisional sum				
10	Bond clause 1.15	1	item		
11	Government legislation and regulations clause 1.16				
12	Import duty and VAT clause 1.17 (Note this clause applies for materials supplied only VAT will also be paid by the subcontractors as allowed in the summary page)				
13	Insurance company fees clause 1.18				
14	Provision of services by the Main contractor clause 1.19				
15	Samples and materials generally clause 1.21				
16	Supplies clause 1.20				
17	Bills of quantities clause 1.23				
18	Contractors office in Kenya clause 1.24				
19	Builders work clause 1.25				
20	Setting to work and regulating system clause 1.29				
21	Identification of plant components clause 1.30				
22	Working drawings clause 1.32				
23	Records Drawings (As Installed) and instructions clause 1.33				
24	Maintenance Manual clause 1.34				

Sub Total carried to Page H4	

ITEM	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
25	Hand over clause 1.35				
26	Painting clause 1.36				
27	Testing and inspection - manufactured plant clause 1.38				
28	Testing and inspection - installation clause 1.39				
29	Storage of materials clause 1.41				
30	Initial Maintenance Clause 1.42				
31	Attendance Upon Tradesmen etc (Insert percentage only) clause 1.58				
32	Local and other authorities notice clause 1.60				
33	Temporary Works clause 1.63				
34	Patent Rights clause 1.64				
35	Mobilization and Demobilization clause 1.65				
36	Extended preliminaries clause 1.66 (see Appendix - clause 1.70)				
37	Supervision by Engineer and site meetings clause 1.67	1	item	200,000	200,000.00
38	Allow for profit and attendance for the above				
39	Amendment to Scope of subcontract works clause 1.68				
40	Contract obligation and employers obligation clause 1.69				
41	Any other preliminaries				
	Sub-total above				
	Subtotal brought forward from page H/3				
	Total for Bill No 1-Preliminaries carried forward to price summar	y	•	-	
	page				

BILL NO. 2 : SCHEDULE 1: BALE STORE

Item	Description	Qty	Unit	Rate (Kshs)	Cost (Kshs)
	SUPPLY, DELIVER, INSTALL, TEST AND COMMISSION THE FOLLOWING:-				
1.01	LIGHTING POINTS AND SWITCHES  Lighting points wired in 3 x 1.5mm <sup>2</sup> PVC/SC CU cables drawn in 20mmØ surface/concealed HG/PVC conduits complete with all necessary accessories but excluding switches for:ii)  Two way switching	22	No.		
1.02	10A, moulded plastic ivory Switch Plates as MK or approved equivalent as follows:  i) One gang two way ii) Intermediate switch	3	No.		
1.03	Lighting fittings complete with lamps of appropriate wattage and colour rendering and fixing materials as follows:-	1	NO.		
	a)50W IP66 6500K Daylight LED Floodlight, Wide-angle beam C/W electronic gear as Ledvance or equal and approved equivalent	6	No.		
	b) 125W, 15000lm IP65 single point suspension LED high bay luminaire with rack beam optic. >80CRI Electronic, fixed output control gear, for 100-240V, 50/60Hz supply. Class I electrical. IK08. Housing/Fins: die-cast aluminium fins,Polycarbonate diffuser complete with 6500k Daylight LED as Thorn Hipak LED or equal and approved equivalent	12	No.		
	1.04Self-contained double sided EXIT sign with 3W LED for nonmaintained emergency lighting for 3 hour duration as Thorn Voyager Blade 2 or approved equivalent.	4	No.		
1.05	A photocell to fit 70-75lux switch on level and 1.5 maximum differential complete with the mounting post and as THORN QPK or approved equivalent		No.		
1.06	30A SP 300mA residual circuit breaker with overload and short circuit protection (RCBO).	1	No.		
1.07	30A, 240V 3-pole contactor as manufactured by Telemecanique or approved equivalent.	1	No.		
1.08	POWER POINTS Socket outlet power points comprising wiring in 3x2.5mm <sup>2</sup> PVC/SC CU cables drawn in 25mmØ concealed HG PVC conduits including all conduit accessories but excluding plates	4	No.		
1.09	13A moulded switched socket outlet plates as MK or approved equivalent as follows:  i) Twin switched	4	No.		
	Sub-Total carried forward to next page				

Item	Description	Qty	Unit	Rate (Kshs)	Cost (Kshs)			
	Sub-Total b/f from previous page							
1.10	Fire alarm control panel power points comprising wiring in 3 x 2.5mm <sup>2</sup> PVC/SC CU cables drawn in 25mmØ concealed HG PVC conduits including all conduit accessories but excluding plates	1	No.					
1.11	20A, unswitched fused spur DP control switch with neon light and cord outlet for item above as MK or approved equivalent	1	No.					
1.12	POWER SUPPLY AND DISTRIBUTION 6 Ways SPN+E, flush mounted Consumer Unit as Schneider or an approved equivalent	1	No.					
1.13	SP Miniature circuit breakers for the distribution board above i) 10A SP MCB ii) 20A SP MCB	1 1	No.					
	ii) 32A SP MCB	1	No.					
	v) TP blanking plates	3	No.					
1.14	SUB-MAINS CABLES  10 mm2 2-C PVC/SWA/PVC copper cable from workshop DB1 to CU above drawn in PVC HG duct concealed c/w appropriate cable lugs (Provisional length, actual length to be determined on site)	50	Lm					
	i) Cable glands for above cable	2	No.					
1.15	Allow for labelling of the above DB including all the incoming and outgoing circuits as per the specifications	1	Item					
	FIRE DETECTION AND ALARM SYSTEM Supply, deliver, install, test and commission the following;							
1.16	Fire Alarm points comprising wiring in 1.5mm2 heat resistant cables drawn in 20mmØ concealed HG PVC conduits	8	No.					
1.17	Addressable Resettable call point incorportating integral short circuit isolator and reset key as Menvier or Approved Equivalent	3	No.					
1.18	Addressable Electronic Fire Alarm sounder complete with Red Flashing beacon as MENVIER or approved equivalent.	1	No.					
1.19	Addressable optical- Photoelectric smoke detector as Menvier MENVIER or equal and approved.	4	No.					
1.20	Microprocessor based 1 Loop Addressable Fire Alarm Panel as Menvier or Approved Equivalent	1	No.					
1.21	Allow for testing and commissioning of the complete the installation	1	Item					
	Total for Bale Store C/F to Summary Page							
	Total for Bare Store of to Summary Lage							

**BILL NO. 2 : SCHEDULE 2: GINNERY** 

Item	Description	Qty	Unit	Rate (Kshs)	Cost (Kshs)
	SUPPLY, DELIVER, INSTALL, TEST AND COMMISSION THE FOLLOWING:-				
2.01	LIGHTING POINTS AND SWITCHES Lighting points wired in 3 x 1.5mm <sup>2</sup> PVC/SC CU cables drawn in 20mmØ surface/concealed HG/PVC conduits complete with all necessary accessories but excluding switches for:-				
	i) One way switching ii) Two way switching	28 66	No. No.		
2.02	10A, moulded plastic ivory Switch Plates as MK or approved equivalent as follows:  i) One gang one way	2	No.		
	ii) One gang two way	2	No.		
2.03	10A metal clad Switch plates wall mounted as MK or approved equivalent.  i) One gang one way	2	No.		
	ii) One gang two way	2	No.		
	iii) Two gang two way	4	No.		
	iv) Intermediate Switch	1	No.		
2.04	Lighting fittings complete with lamps of appropriate wattage and colour rendering and fixing materials as follows:-				
	a) 34W, 4300lm IP65 dust and moisture resistant LED luminaire. Electronic, fixed output control gear. Diffuser: polycarbonate with linear prisms. Toggles: stainless steel with mounting brackets for vertical surface mounting, complete with 6500k Daylight LED as THORN AquaForce LED or approved equivalent	20	<b>.</b>		
		30	No.		
	b) 125W, 15000lm IP65 single point suspension LED high bay luminaire with rack beam optic. >80CRI Electronic, fixed output control gear, for 100-240V, 50/60Hz supply. Class I electrical. IK08. Housing/Fins: die-cast aluminium fins, polycarbonate diffuser complete with 6500k Daylight LED as Thorn Hipak LED or equal and approved equivalent	6	No.		
	c) 50W, IP66 LED floodlight with symmetric distribution for creating lighting effects. Electronic, Class I electrical. Body: diecast aluminium, powder coated silver-grey with clear polycarbonate enclosure complete with surface mounting brackets,				
	6500K LED as Thorn Olsys 1 ilum/ Ledvance or approved equivalent	16	Nτα		
	Sub-Total carried forward to next page	16	No.		

Item	Description	Qty	Unit	Rate (Kshs)	Cost (Kshs)			
	Sub-Total b/f from previous page							
	d) 36W,4500lm 6500k Daylight LED batten Luminaire, 1200mm with a detachable LED engine. Switchable or DALI ballast As Thorn PopPack LED or approved equivalent	14	No					
	e) Standard Recessed 600mmX600mm,40W,3600lm, 6500k Daylight LED Panel Light, Office Compliant, IP44 ,as PHILLIPS Coreline or approved equivalent.	3	No.					
	f) 16W,1692 lm, 6500K Daylight LED Recessed circular edge lit panel as Thorn OMEGA C LED/ Philips or equal and approved equivalent.	4	No.					
2.05	Self-contained double sided EXIT sign with 3W LED for nonmaintained emergency lighting for 3 hour duration as Thorn Voyager Blade 2 or approved equivalent.	3	No.					
2.06	A photocell to fit 70-75lux switch on level and 1.5 maximum differential complete with the mounting post and as THORN QPK or approved equivalent	2	No.					
2.07	30A SP 300mA residual circuit breaker with overload and short circuit protection (RCBO).	1	No.					
2.08	30A, 240V 3-pole contactor as manufactured by Telemecanique or approved equivalent.	1	No.					
2.09	SOCKET OUTLETS & POWER POINTS  Socket outlet power points comprising wiring in 3x2.5mm <sup>2</sup> PVC/SC  CU cables drawn in 25mmØ concealed HG PVC conduits including all conduit accessories but excluding the plates	20	No.					
2.10	13A moulded switched socket outlet plates as MK or approved equivalent as follows:  i) Twin switched	6	No.					
2.11	13A metal clad twin switched socket outlet plates as MK Electric or equal and approved equivalent.	12	No.					
2.12	Fire alarm control panel power points comprising wiring in 3 x 2.5mm <sup>2</sup> PVC/SC CU cables drawn in 25mmØ concealed HG PVC conduits including all conduit accessories but excluding plates	1	No.					
2.13	20A, unswitched fused spur DP control switch with neon light and cord outlet for item above as MK or approved equivalent	1	No.					
	Cub Total							
	Sub-Total carried forward to next page							

Item	Description	Qty	Unit	Rate (Kshs)	Cost (Kshs)	
	Sub-Total b/f from previous page					
2.14	<b>Data/Telephon</b> e outlet points comprising 25mmØ concealed HG PVC conduits complete with draw wire.	4	No			
2.15	Single phase Industrial Socket Outlet Points comprising wiring in 3 x 4mm2 PVC/SC/CU cables drawn in 25mmØ HG/PVC conduits complete with all necessary accessories but excluding the outlet plates	4	No.			
2.16	16-32A - 2P + E watertight wonder plug industrial socket outlet as schneider electric Pratika or equal and approved equivalent	4	No.			
2.17	25A, surface mount 2P isolator Switch IP66 for item 5.11 above as Schneider Electric or approved equivalent	2	No.			
2.18						
	32A, surface mount 2P isolator Switch IP66 for item 5.11 above as Schneider Electric or approved equivalent	2	No.			
2.19	Three phase Industrial Socket Outlet Points comprising wiring in 5 x 4.0mm2 PVC/SC/CU cables drawn in 25mmØ HG/PVC conduits complete with all necessary accessories but excluding the outlet plates	2	No.			
2.20	Three phase Industrial Socket Outlet Points comprising wiring in 5 x 6.0mm2 PVC/SC/CU cables drawn in 25mmØ HG/PVC conduits complete with all necessary accessories but excluding the outlet plates	2	No.			
2.21	25-45A watertight industrial socket outlet (3P-N-E) as Schneider Electric Pratika or equal and approved equivalent. (workshop)					
2.22		4	No.			
2.23	25A, surface mount TPN isolator Switch IP66 for item 5.15 above as Schneider Electric or approved equivalent 45A, surface mount TPN isolator Switch IP66 for item 5.16 above as Schneider Electric or approved equivalent	2 2	No. No.			
	Sub-Total carried forward to next page					
	The state of the s					

Item	Description	Qty	Unit	Rate (Kshs)	Cost (Kshs)
	Sub-Total b/f from previous page				
	POWER SUPPLY AND DISTRIBUTION DB 1 - WORKSHOP				

2.24	8Ways 100A TPN distribution board surface mounted complete with 100A TP integral isolator and <b>lockable cover</b> and all accessories excluding MCBs as Schneider Electric or approved equivalent		No.		
2.25	Miniature circuit breakers for the distribution board above i) 10A SP MCB ii) 20A SP MCB	2	No.		
	iii) 25A SP MCB	2	No.		
	iv) 32A SP MCB	4	No.		
	v) 25A TP MCB	2	No.		
	vi) 45A TP MCB	2	No.		
	vii) 63A TP MCB	1	No.		
	viii) TP blanking plates	4	No.		
2.26	SUB-MAINS CABLES  4x25Sq.mm armoured PVC/SWA/PVC CU cable from existing meterboard to DB 1 - WORKSHOP c/w appropriate cable lugs (Provisional length, actual length to be determined on site)	90	LM		
	i) Cable glands for above cable	2	No.		
2.27	Allow for labelling of the above DB including all the incoming and outgoing circuits as per the specifications	1	Item		
	FIRE DETECTION AND ALARM SYSTEM Supply, deliver, install, test and commission the following;				
2.28	Fire Alarm points comprising wiring in 1.5mm2 heat resistant cables drawn in 20mmØ concealed HG PVC conduits	15	No.		
2.29	Addressable Resettable call point incorportating integral short circuit isolator and reset key as Menvier or Approved Equivalent	3	No.		
2.30	Addressable Electronic Fire Alarm sounder complete with Red Flashing beacon as MENVIER or approved equivalent.	2	No.		
2.31	Addressable optical- Photoelectric smoke detector as Menvier MENVIER or equal and approved.	10	No.		
2.32	Microprocessor based 1 Loop Addressable Fire Alarm Panel as Menvier or Approved Equivalent	1	No.		
2.33	Allow for testing and commissioning of the complete the installation	1	Item		
	Total for Ginnery C/F to Summary Page				

BILL NO.2:SCHEDULE 3: LIGHTNING PROTECTION SYSTEM

Item	Description	Qty	Unit	Rate (Kshs)	Amount (Kshs)
3.01	LIGHTNING PROTECTION	70	Lm	( 12 12)	( 12 12)
	i)25x3mm pure copper tape including copper saddles fixed at 1500mm intervals and bonding to metal work in the roof, complete with tape jointing clamps, all as FURSE.	4	No		
	ii)15mm diameter multiple point Copper air terminal (lightning arrestors) iii)Copper air terminal	4	No		
	base clamp as FURSE iv)Copper Saddle	34	No		
	Clips	6	No		
	v)Oblong test/junction clamp as FURSE	2	No		
	vi)Earthing with 15mm diameter 1800mm long copper earth rods, complete with driving head and clamp vii)Earth	2	No		
	rod-to-tape clamp type A viii)Concrete inspection earth pit	2	No		
	ix)1500mm x 1500mm copper earth mat made from 25mm x 3mm copper tape at 300mm spacing, buried at permanent moisture level and complete with all clamps, welding joints and 6m long 25mm x 3mm insulated copper tape clamped to the down conductors.	2	No		
	Total for Lightning Protection C/F to Summary Page				

#### **ELECTRICAL ENGINEER'S STATIONERY**

Item	Description	Qty	Unit	Rate	Amount	
				(Kshs)	(Kshs)	

	Supply and deliver to the Project Engineer the following stationery to be used in running the project:			
4.01	Photocopier Papers size A4 80g/cm2 white	20	Ream	
4.02	HP Laserjet Printer Toner/cartridge CE278A	4	No.	
4.03	Laptop Core i7 11th Generation, 16GB RAM, 1TB SSD storage as HP Spectre x360 convertible or approved equivalent	1	No.	
4.04	A4 size translucent PVC covers as KATKO or approved equivalent, 100 sheets blue in colour and 0.2mm thick	5	Pkts	
4.05	A4 size Embossed covers as KATKO or approved equivalent, 100 sheets blue in colour	4	Pkts	
4.06	22mm diameter spiral binders black in colour	4	Roll	
4.07	2-Terabyte portable external hard disc as Hp/ Transcend/ Toshiba	1	No.	
	Total for Electrical Engineer's Stationery C/F to Sur	nma	ry Page	


#### PROVISIONAL SUMS

Item	Description	Cost Kshs
<b>A.</b>	A. CONTINGENCY  Allow a Provisional Sum of Kshs. Three Hundred Thousand (300,000.00) only contingency to be used at the discretion of the Project Engineer	
В	Allow a Provisional Sum of Kshs. One Hundred and Fity Thousand (150,000.00) only for CPD Training of SDPW Electrical Engineer	150,000.00
	Sub total for PROVISIONAL Sums C/F to Summary page	

#### **BILLS SUMMARY PAGE**

Item	Description	Amount(KShs)
No.		
1.00	PRELIMINARIES AND GENERAL CONDITIONS B/F FROM PAGE EIW-F/4	
2.00	SUB-TOTAL FOR BALE STORE B/F FROM PAGE EIW-F/6	
3.00	SUB-TOTAL FOR GINNERY B/F FROM PAGE EIW-F/10	
4.00	SUB-TOTAL FOR LIGHTNING PROTECTION B/F FROM PAGE EIW-F/11	
5.00	SUB-TOTAL FOR ENGINEER'S STATIONERY B/F FROM PAGE EIW-F/12	
6.00	SUB-TOTAL FOR PROVISIONAL SUMS B/F FROM PAGE EIW-F/13	
	GRAND TOTAL C/F TO MAIN SUMMARY PAGE	
TOTA	LAMOUNT IN WORDS	
		•••••
•••••	•	
•••••	•••••••••••••••••••••••••••••••	•••••
•••••	••••	
	••••	•••••
		•••••
TEND	ERER'S NAME & STAMP	
•••••	•••••••••••••••••••••••••••••••••••••••	•••••
	•	
•••••	••••	
		•••••
•••••	••••	
SIGNA	ATURE	

P.I.N No	V.A.T CERTIFICATE No
WITNESS	
ADDRESS	•••••
SIGNATURE OF WITNESS	•••••
<b>DATE</b>	•••••



#### **TECHNICAL SCHEDULE**

- 1.0 The technical schedule shall be submitted by tenderers to facilitate and enable the Project Manager to evaluate the tenders
- 2.0 The filling of this schedule forms part of Technical Evaluation of the tenders, and bidders shall therefore be required to indicate the type/make and country of origin of all the materials and equipment they intend to offer to the employer as listed in the technical schedule.
- 3.0 Any bid returned with unfilled Technical Schedule shall be considered technically nonresponsive, and the bidder shall automatically be disqualified.


#### EIW-G/1

#### TECHNICAL SCHEDULE OF ITEMS TO BE SUPPLIED

(To be Completed by the Tenderer as a Mandatory Requirement)

ITEM	DESCRIPTION	TYPE/MAKE	COUNTRY OF ORIGIN
1	Lighting fittings		
2	Lighting Switches		
3	DP Switches		
4	Power Cables		
5	Cable Trunking & Conduits		
7	Socket Outlets (13 Ampere)		
8	Distribution Boards		
9	Miniature Circuit breakers		
10	Fire alarm sounder		
11	Smoke Detector		
12	Fire Alarm Panel		
13	Consumer Unit		
14	SP Isolators		
15	TP Isolators		
16	Industrial socket outlets		

**Detailed manufacturer's Brochure**s detailing Technical Literature and specifications on the above items MUST be attached and Items to be supplied highlighted (Model and Make).



#### **CONTENTS OF SECTION H**

	<u>TITLE</u>	<u>PAGE</u>
1.	Contents	EIW- H/1
2.	Key Personnel	EIW- H/2
3.	Schedule of Contracts completed in the last five (5) years	EIW- H/3
4.	Schedule of on-going projects	EIW- H/4
5.	Schedule of major items of Contractor's Equipment	EIW- H/5
6.	Details of Litigation or Arbitration Proceedings	EIW- H/6
7.	Commissioning Guide for Electrical Installation works	EIW-H/7 – EIW-H/13

#### NOTE:

Tenderers must duly fill these Standard Forms as a mandatory requirement as they will form part the evaluation criteria.

#### KEY PERSONNEL

Qualifications and experience of key personnel proposed for administration and execution of the Contract.

POSITION	NAME	HIGHEST QUALIFICATION (Attach proof)	YEARS OF EXPERIENCE (GENERAL)	YEARS OF EXPERIENCE IN PROPOSED POSITION

I certify that the above information is correct.								
Title	Signature	 Date						
	EIW-H/2							

#### CONTRACTS COMPLETED IN THE LAST FIVE (5) YEARS

Work performed on works of a similar nature, complexity and volume over the last 5 years.

PROJECT NAME	NAME CLIENT	OF	TYPE OF WORK AND YEAR OF COMPLETION	VALUE CONTRACT (Kshs.)	OF

I certify that the above work	ss were successfully carried ou	it and completed by ourse	lves.
Title	Signature	Date	
	EIW-H/3		

#### **SCHEDULE OF ON-GOING PROJECTS**

Details of on-going or committed projects, including expected completion date.

PROJECT NAME	NAME OF CLIENT	CONTRACT SUM	% COMPLETE	COMPLETION DATE

I certify that the above works a	re currently being carried o	out by ourselves.
Title	Signature	Date
	EIW-H/4	

# SCHEDULE OF MAJOR ITEMS OF CONTRACTOR'S EQUIPMENT PROPOSED FOR CARRYING OUT THE WORKS (Attach proof of ownership)

ITEM OF	DESCRIPTION, MAKE	CONDITION (New,	OWNED, LEASED
EQUIPMENT	AND AGE (Years)	good, poor) and	(From whom?), or
		number available	to be purchased
			(From whom?)

		n or arbitration pro ne of the parties in th		<u>ie tenderer has</u>	
1.					
	EIW-H/6				

_		
-	 	
-	 	
-		
-		
-		

Code: E/CG/01



# MINISTRY OF TRANSPORT, INFRASTRUCTUTRE, HOUSING, URBAN DEVELOPMENT & PUBLIC WORKS

#### STATE DEPARTMENT FOR PUBLIC WORKS

(ELECTRICAL DEPARTMENT)

# PROPOSED CONSTRUCTION OF PAVI KWALE CO-OPERATIVE UNION GINNERY AT KINONDO, KWALE COUNTY

W.P. ITEM NO. D116 CO/KWL/2001 JOB NO. 10826A

**TESTING & COMMISSIONING GUIDE** 

FOR

ELECTRICAL INSTALLATION WORKS ON SITE

Issued by:

The Chief Engineer (Electrical), State Department for Public Works, P.O. BOX 41191 – 00100 GPO, NAIROBI.

## MINISTRY OF TRANSPORT, INFRASTRUCTURE, HOUSING, URBAN DEVELOPMENT & PUBLIC WORKS

## STATE DEPARTMENT FOR PUBLIC WORKS ELECTRICAL DEPARTMENT

#### TESTING AND COMMISSIONING OF ELECTRICAL INSTALLATION WORKS ON SITE.

JOB NO

The Sub contractor shall test in accordance with the relevant section of IEE regulations, Rule 3 of the Electrical Power Act for additional tests not covered by the regulations, Government Electrical specifications I & II and the Kenya Power & Lighting Co. Ltd by-laws.

#### A PRELIMINARY CHECKS

The Engineer shall check to establish the following data:-

ITEM	DESCRIPTION			REMARKS
(i)	Type of installation (New/Renovation/Addition/ to existing installation)			
	a) Power sup	oply 240V/4	115V/11KV	
(ii)	b) Frequency of the mains supply			
	c) Installatio			
(iii)	Method of Metering (New /Monitoring/Existing meter)			
(iv)	Are Testing/Measuring instruments available			
(v)	Are there maintenance/operational manuals for specialized systems (if any)			
(vi)	List of 'as installed drawings'	Drg No.	Description	

ITEM	TEST DESCRPTION	OBSERVATIONS/ RESULTS	REMARKS
1	Tests shall be carried out to ensure:		
	a) All fuses and single pole switches are installed in live conductor		
	b) All outlets and switched socket outlets are connected to 'LIVE' conductor in the Terminal marked so and each earth pin effectively bonded to earth continuity system		
	c) Verify continuity of all final conductors of each 'Ring' circuit. (0.05 to $0.8\Omega$ )	Ohms	
	d) All radial circuits emanate from respective distribution boards/consumer units and that they do not supply any other Equipment		
	e) The correct phase sequence is maintained throughout the installation		
	f) Effective 'Discrimination' in the arrangement of protective devices. i.e. a fault in the furthest power point/Lighting point should not blow or trip Fuses/MCBs respective in the Meter board.		
2	Inspect to ensure:		
	a) No terminal in the Ceiling Rose is 'LIVE' when the corresponding switch is in the off position.		
	b) All conduit termination conduit boxes, Consumer unit, DB's and Adaptable boxes have smooth edges and are properly bushed.		
	c) All fixed metal works close to Electrical installation are bonded to earth continuity conductor.		
	d) All Fuse ways and Circuit breakers for final sub circuits are properly labeled		

TESTS CONT'D

ITEM	TEST DESCRPTION	
3	Carry out the following tests:	
3	7	
	a) Insulation Resistance tests	
	i) Between phases	
	a) R -Y	•••••
	b) R -B	•••••
	c) B-Y ii) Phase to Neutral	•••••
	a) R - N	
	b) R - N	•••••
	c) B - N iii) Phase to Earth	•••••
	a) R - E	•••••
	b) R-E	
	c) B -E	•••••
		•••••
	Minimum thresholds for above and for:	•••••
	i) ELV circuits (SELV & PELV) = 0.25	
	ΜΩ	
	ii) LV Circuits up to $500V = 0.5 M\Omega$ iii)	
	LV Circuits above $500V = 1 M\Omega$	
	b) Earth continuity conductor impedance (0.005 to $2\Omega$ )	
	(0.003 to 232)	
	-\ Fouth foult I con insured on a	•••••
	c) Earth fault Loop impedance	
	(0 - 2000 Ω)	•••••
	d) Earth Electrode resistance	
	(Less than $4\Omega$ )	•••••
	e) Earth Lead resistance	
	(Less than $4\Omega$ )	•••••
	f) The operation of protection MCCBS &	
	MCBS (Tripping under faulty	
	conditions)	
	g) Check the mechanical toggling (make	
	& break) of all the switches to	
	installed accessories.	
L	1	

В

Undergro	ound cabling, Check for:		
i)	Continuity of the phases		
ii)	Factory tests done (avail certification)		
iii)	Proper termination		
iv)	Route markers		
	i) ii)	ii) Factory tests done (avail certification) iii) Proper termination	i) Continuity of the phases  ii) Factory tests done (avail certification)  iii) Proper termination

#### TESTS CONT'D

ITEM	TEST DESCRPTION		OBSERVATIONS/ RESULTS	REMARKS	
5 Installi) iii) iv)		ed load Lighting points (No.) ii) Socket outlets (No.) Motors (Give rating) Other machines (Attach li	st if more)		
	Item	Description	Rating		
6	Туре	of Earthing: TN-C/TN-S/ TN-C	C-S/TT/IT.		
7	7 LV switchboard: The board shall be checked to ascertain the following  i) Rating of the switchboard  ii) Rating of main incomer MCCB				
	iii) Form of construction (1/2B/3B/4)				
	iv) Degree of protection (IP rating)				
	v) Nameplates for identification of all circuits entering/leaving switchgear				
	vi) Proper Electrical & Mechanical operation of functional parts i.e MCCBs, Indicating meters, CTs & VTs .				

В	
	vii) Check cable terminations, type & terminals
	viii) General comments on the appearance of the finished mechanical assembly including welding, full nuts & tightness of bolted parts.
8	Fireman's switch.
	i) Make and manufacturer
	ii) The rating of the switch
	iii) Test for the Electrical and Mechanical operation of the switch
	iv) State the types of loads supported by the maintained board on the switch.
	** see foot note

General comments on the Electrical installation:-
Testing and Commissioning witnessed by:
S.D.P.W REPRESENTATIVE/ PROJECT ENGINEER:-
NameDesignation
Sign
CONTRACTOR'S REPRESENTATIVE:-
NameDesignation
Sign

**If there are other defects noted, list them on a separate sheet and attach.
STATEMENT OF COMPLIANCE
(a) I confirm compliance with all clauses in this tender specification.
(b) I confirm that I have not and will not make any payment to any person which can be perceived as in inducement to enable me win this tender.
Signed
Date



## PROPOSED CONSTRUCTION OF PAVI KWALE CO-OPERATIVE UNION GINNERY AT KINONDO, KWALE COUNTY

#### TENDER SPECIFICATIONS AND BILLS OF QUANTITIES FOR SUPPLY, DELIVERY, INSTALLATION, TESTING AND COMMISIONING OF MECHANICAL INSTALLATION WORKS

#### WP ITEM NO. D116/CO/KWL/2001 - JOB NO. 10826A

#### **VOLUME 3 OF 3**

#### **CLIENT**

## STATE DEPARTMENT FOR CO-OPERATIVES P.O.BOX 30547-00800 NAIROBI

PROJECT MANAGERARCHITECTWORKS SECRETARYCHIEF ARCHITECT

S.D.P.W S.D.P.W

P.O.BOX 30743-00100 P.O.BOX 30743-00100

NAIROBI NAIROBI

<u>QUANTITY SURVEYOR</u> <u>ELECTRICAL ENGINEER</u>

CHIEF QUANTITY SURVEYOR CHIEF ENGINEER (ELECTRICAL)

S.D.P.W S.D.P.W

P.O.BOX 30743-00100 P.O.BOX 30743-00100

NAIROBI NAIROBI

STRUCTURAL ENGINEER	MECHANICAL ENGINEER
CHIEF ENGINEER (STRUCTURAL)	<b>CHIEF ENGINEER (MECHANICAL-B.S)</b>
S.D.P.W	S.D.P.W
P.O.BOX 30743-00100	P.O.BOX 30743-00100
NAIROBI	NAIROBI
ATI	GUST, 2023
AU	5051, 2025



#### REPUBLIC OF KENYA

## MINISTRY OF AGRICULTURE, LIVESTOCK, FISHERIES AND CO-OPERATIVES

#### STATE DEPARTMENT FOR CO-OPERATIVES

#### PROPOSED CONSTRUCTION OF PAVI FARMERS CO-OPERATIVE SOCIETY LTD GINNERY AT KINONDO, KWALE COUNTY (PHASE I)

W.P. ITEM NO. D116 CO/KWL/2001 - JOB NO. 10826A

SPECIFICATIONS AND BILLS OF QUANTITIES FOR SUPPLY, DELIVERY, INSTALLATION, TESTING AND COMMISSIONING OF MECHANICAL INSTALLATION WORKS

#### **CLIENT**

THE PRINCIPAL SECRETARY, STATE DEPARTMENT FOR CO-OPERATIVES, P.O. BOX 30547-00100 NAIROBI

PROJECT MANAGER

WORKS SECRETARY CHIEF ARCHITECT M.O.T.I.H.UD&PW

P.O. BOX 30743 – 00100 P.O. BOX 30743 – 00100

NAIROBI NAIROBI

**QUANTITY SURVEYOR** 

CHIEF QUANTITY SURVEYOR

M.O.T.I.H.UD&PW

P.O. BOX 30743 - 00100

**MECHANICAL ENGINEER** 

CHIEF ENGINEER -MECHANICAL (BS) M.O.T.I.H.UD&PW

ARCHITECT

P.O. BOX 30743-00100

NAIROBI NAIROBI

#### **ELECTRICAL ENGINEER**

#### **STRUCTURAL ENGINEER**

CHIEF ELECTRICAL ENGINEER (BS)

**CHIEF ENGINEER (STRUCTURAL)** 

M.O.T.I.H.UD&PW

M.O.T.I.H.UD&PW P.O. BOX 30743 - 00100

P.O. BOX 30743 - 00100

NAIROBI

NAIROBI.

**OCTOBER, 2022** 

#### **TABLE OF CONTENTS**

ITEM	TITLE	<u>PAGE</u>
1	Definitions	(i)
2	Preliminary & Technical Evaluation Criteria	(i) ME/1 - ME/3
3	General Mechanical Specifications	GM/1 - GM/4
4	Particular Mechanical Specifications	PM/1 - PM/34
5	Bills of Quantities	M-1 -M-12
6	Schedule of Unit Rates	M-13
7	Technical Schedule of Items to be supplied	MT/1 – MT/2
8	Drawing Schedule	MD/1

#### **DEFINITIONS**

The following terms and expressions used in the contract document shall have the following meanings:

The Employer THE PRINCIPAL SECRETARY,

STATE DEPARTMENT FOR CO-OPERATIVES,

P.O. BOX 30547 - 00100

**NAIROBI** 

Project Manager Works Secretary

STATE DEPARTMENT FOR PUBLIC WORKS

P.O. Box 30743 – 00100

Nairobi

**Architect** Chief Architect

STATE DEPARTMENT FOR PUBLIC WORKS

P. O. Box 30743 – 00100 Nairobi

Electrical Engineer Chief Engineer (Electrical)

STATE DEPARTMENT FOR PUBLIC WORKS

P. O. Box 41191 – 00100 Nairobi

**Mechanical Engineer** Chief Engineer (Mechanical – BS)

STATE DEPARTMENT FOR PUBLIC WORKS

P. O. Box 41191 – 00100

Nairobi

**Quantity Surveyor** Chief Quantity Surveyor

STATE DEPARTMENT FOR PUBLIC WORKS

P. O. Box 30743 – 00100

Nairobi

**Structural** 

Engineer

Chief Engineer (Structural)

STATE DEPARTMENT FOR PUBLIC WORKS

P. O. Box 30743 – 00100

Nairobi

**Contractor** The firm appointed to carry out Builders Works

Sub-contractor The firm appointed to carry out Supply, delivery, and

**Installation of Mechanical Installation Works** 

The Site The Site is Located at PAVI FARMER'S CO-OPERATIVE

SOCIETY LTD IN

KINONDO, KWALE COUNTY

## EVALUATION & QUALIFICATION CRITERIA

#### Note.

This criterion shall be used to evaluate the bidders proposed to carry out the specialized works who shall be domestic subcontractors to the main bidder on award of the contract.

#### 1. General Provision

Wherever a Tenderer is required to state a monetary amount, Tenderers should indicate the Kenya Shilling equivalent using the rate of exchange determined as follows:

- a) For construction turnover or financial data required for each Year-Exchange rate prevailing on the last day of the respective calendar year (in which the amounts for that year is to be converted) was originally established. b) Value of single Contract-Exchange rate prevailing on the date of the contract signature.
- c)Exchange rates shall be taken from the publicly available source identified in the ITT. Any error in determining the exchange rates in the Tender may be corrected by the Procuring Entity.

This section contains the criteria that the Employer shall use to evaluate tender and qualify tenderers.

No other factors, methods or criteria shall be used other than specified in this tender document. The Tenderer shall provide all the information requested in the forms included in Section IV, Tendering Forms. The Procuring Entity should use **the Standard Tender Evaluation Report for Goods and Works** for evaluating Tenders.

#### **Evaluation and contract award Criteria**

The Procuring Entity shall use the criteria and methodologies listed in this Section to evaluate tenders and arrive at the Lowest Evaluated Tender. The tender that (i) meets the qualification criteria, (ii) has been determined to be substantially responsive to the Tender Documents, and (iii) is determined to have the Lowest Evaluated Tender price shall be selected for award of contract.

#### 2. Preliminary examination for Determination of Responsiveness

The Procuring Entity will start by examining all tenders to ensure they meet in all respects the eligibility criteria and other requirements in the ITT, and that the tender is complete *in all* aspects in meeting the requirements of "Part 2–Procuring Entity's Services Requirements", including checking

for tenders with unacceptable errors, abnormally low tenders, abnormally high tenders and tenders that are front loaded. The Standard Tender Evaluation Report for Goods and Works for evaluating Tenders provides clear guidelines on how to deal with review of these requirements. Tenders that do not pass the Preliminary Examination will be considered irresponsive and will not be considered further.

#### **TENDER EVALUATION CRITERIA**

After tender opening, the tenders will be evaluated in **2 stages**, namely:

- 1. Preliminary Evaluation;
- 2. Technical Evaluation;

Note: This criterion shall be used to evaluate sub contracts

#### ME/1

#### STAGE 1: PRELIMINARY EVALUATION/MANDATORY REQUIREMENTS

This stage of evaluation shall involve examination of the mandatory requirements as set out in the Tender Advertisement Notice or Letter of Invitation to Tender and any other conditions stated in the bid document.

These conditions shall include the following:

- i) Company Certificate of incorporation/registration
- ii) Current certificate of Registration with National Construction Authority (**NCA 8 and above**) in Fire Suppression Installation Works. iii) Current Annual NCA contractor's Practicing License(s) iv) Valid Tax Compliance Certificate;
- v) Compliance with Technical Specifications, including dully filled Schedule of Unit Rates.

#### Note

On compliance with Technical Specifications, bidders shall supply equipment/items which comply with the technical specifications set out in the bid document. In this regard, the bidders will be required to submit relevant technical brochures/catalogues with the tender document, highlighting (using a mark-pen or highlighter) the Catalogue Number/model of the proposed items. Such brochures/catalogues should indicate comprehensive relevant data of the proposed equipment/items which should include but not limited to the following:

- (i) Standards of manufacture;
- (ii) Performance ratings/characteristics;
- (iii) Material of manufacture;
- (iv) Electrical power ratings; and
- (v) All other requirements as indicated in the technical specifications of the bid.

The bid will then be analyzed, using the information in the technical brochures, to determine compliance with <u>technical specifications</u> for the works/items as indicated in the tender document. Bidders not complying with **any** of the <u>technical specifications</u> shall be adjudged to be technically non-responsive while those meeting all the technical specifications shall be adjudged to be technically responsive.

The tenderer shall also fill in the Technical Schedule as specified in the tender document for Equipment and Items indicating the Country of Origin, Model/Make/Manufacturer and catalogue numbers of the Items/Equipment they propose to supply.

Tenderers who do not satisfy any of the above mandatory requirements shall be considered Non-Responsive and their tenders will not be evaluated further.

#### ME/2

The following table shall be used to determine the bidder's responsiveness to the technical specifications. Tenderers <u>MUST fill the table and provide relevant brochures</u> to check for compliance

#### **Compliance to Technical Specifications (Mechanical Works)**

	TECHNICAL SCHEDULE				
Item	Description	Manufacturer	Country of Origin	Remarks (Catalogue No.etc)	Compliant/NonCompliant
1	GMS pipes & fittings				
2	Gate Valves				
3	Fire sprinkler (nozzle)				

4	Installation Control Valve		
5	Cyclone Ventilator		

Tenders Must attach Brochures/Catalogues as it will form part of evaluation criteria

ME3

# GENERAL MECHANICAL SPECIFICATIONS

#### **GENERAL MECHANICAL SPECIFICATION**

CLAUSE	DESCRIPTION	<u>PAGE</u>
(i)	GENERAL	GM/1
(ii)	QUALITY OF MATERIALS	GM/1
(iii)	REGULATIONS AND STANDARDS	GM/1
(iv)	ELECTRICAL REQUIREMENTS	GM/2
(v)	TRANSPORT AND STORAGE	GM/2
(vi)	SITE SUPERVISION	GM/2
(vii)	INSTALLATION	GM/2
(viii)	TESTING	GM/3- GM/4
(ix)	COLOR CODING	GM/4
(x)	WELDING MECHANICAL SPECIFICATIONS	GM/4 <b>GENERAL</b>

#### 2.01 General

This section specifies the general requirement for plant, equipment and materials forming part of the Subcontract Works and shall apply except where specifically stated elsewhere in the Specification or on the Contract Drawings.

#### 2.02 Quality of Materials

All plant, equipment and materials supplied as part of the Sub-contract Works shall be new and of first-class commercial quality, shall be free from defects and imperfections and where indicated shall be of grades and classifications designated herein.

All products or materials not manufactured by the Sub-contractor shall be products of reputable manufacturers and so far as the provisions of the Specification is concerned shall be as if they had been manufactured by the Sub-contractor.

Materials and apparatus required for the complete installation as called for by the Specification and Contract Drawings shall be supplied by the Sub-contractor unless mention is made otherwise.

Materials and apparatus supplied by others for installation and connection by the Subcontractor shall be carefully examined on receipt. Should any defects be noted, the Sub-contractor shall immediately notify the Engineer.

Defective equipment or that damaged in the course of installation or tests shall be replaced as required to the approval of the Engineer.

#### 2.03 Regulations and Standards

The Sub-contract Works shall comply with the current editions of the following:

- a) The Kenya Government Regulations.
  - The United Kingdom Institution of Electrical Engineers (IEE) Regulations for the Electrical Equipment of Buildings.
  - b) The United Kingdom Chartered Institute of Building Services Engineers (CIBSE) Guides.
  - c) British Standard and Codes of Practice as published by the British Standards Institution (BSI)
  - e) The Local Council By-laws.
  - f) The Electricity Supply Authority By-laws.
  - g) Local Authority By-laws.
  - h) The Kenya Building Code Regulations.
  - i) The Kenya Bureau of Standards

#### **GM/1**

#### 2.04 Electrical Requirements

Plant and equipment supplied under this Sub-contract shall be complete with all necessary motor starters, control boards, and other control apparatus. Where control panels incorporating several starters are supplied, they shall be complete with a main isolator. The supply power up to and including local isolators shall be provided and installed by the Electrical Subcontractor. All other wiring and connections to equipment shall form part of this Sub-contract and be the responsibility of the Sub-contractor.

The Sub-contractor shall supply three copies of all schematic, cabling and wiring diagrams for the Engineer's approval.

The starting current of all electric motors and equipment shall not exceed the maximum permissible starting currents described in the Kenya Power and Lighting Company (KPLC) By-laws.

All electrical plant and equipment supplied by the Sub-contractor shall be rated for the supply voltage and frequency obtained in Kenya, that is 415 Volts, 50Hz, 3-Phase or 240Volts, 50Hz, 1-phase.

Any equipment that is not rated for the above voltages and frequencies shall be rejected by the Engineer.

#### 2.05 Transport and Storage

All plant and equipment shall, during transportation be suitably packed, crated and protected to minimise the possibility of damage and to prevent corrosion or other deterioration.

On arrival at site all plant and equipment shall be examined and any damage to parts and protective priming coats made good before storage or installation.

Adequate measures shall be taken by the Sub-contractor to ensure that plant and equipment do not suffer any deterioration during storage.

Prior to installation all piping and equipment shall be thoroughly cleaned.

If, in the opinion of the Engineer any equipment has deteriorated or been damaged to such an extent that it is not suitable for installation, the Sub-contractor shall replace this equipment at his own cost.

#### 2.06 Site Supervision

The Sub-contractor shall ensure that there is an English-speaking supervisor on the site at all times during normal working hours.

#### 2.07 Installation

Installation of all special plant and equipment shall be carried out by the Subcontractor under adequate supervision from skilled staff provided by the plant and equipment manufacturer or his appointed agent in accordance with the best standards of modern practice and to the relevant regulations and standards described under Clause 2.03 of this Section.

#### GM/2

#### 2.08 **Testing**

#### 2.08.1 General

The Sub-contractor's attention is drawn to Part 'C' Clause 1.38 of the "Preliminaries and General Conditions".

#### 2.08.2 Material Tests

All material for plant and equipment to be installed under this Sub-contract shall be tested, unless otherwise directed, in accordance with the relevant B.S Specification concerned.

For materials where no B.S. Specification exists, tests are to be made in accordance with the best modern commercial methods to the approval of the Engineer, having regard to the particular type of the materials concerned.

The Sub-contractor shall prepare specimens and performance tests and analyses to demonstrate conformance of the various materials with the applicable standards.

If stock material, which has not been specially manufactured for the plant and equipment specified is used, then the Sub-contractor shall submit satisfactory evidence to the Engineer that such materials conform to the requirements stated herein in which case tests of material may be partially or completely waived.

Certified mill test reports of plates, piping and other materials shall be deemed acceptable.

#### 2.08.3 Manufactured Plant and Equipment – Work Tests

The rights of the Engineer relating to the inspection, examination and testing of plant and equipment during manufacture shall be applicable to the Insurance Companies or Inspection Authorities so nominated by the Engineer.

The Sub-contractor shall give two week's notice to the Engineer of the manufacturer's intention to carry out such tests and inspections.

The Engineer or his representative shall be entitled to witness such tests and inspections. The cost of such tests and inspections shall be borne by the Subcontractor.

Six copies of all test and inspection certificates and performance graphs shall be submitted to the Engineer for his approval as soon as possible after the completion of such tests and inspections.

Plant and equipment which is shipped before the relevant test certificate has been approved by the Engineer shall be shipped at the Sub-contractor's own risk and should the test and inspection certificates not be approved; new tests may be ordered by the Engineer at the Sub-contractor's expense.

#### **GM/3**

#### 2.08.4 Pressure Testing

All pipe work installations shall be pressure tested in accordance with the requirements of the various sections of this Specification. The installations may be tested in sections to suit the progress of the works but all tests must be carried out before the work is buried or concealed behind building finishes. All tests must be witnessed by the Engineer or his representative and the Sub-contractor shall give 48 hours' notice to the Engineer of his intention to carry out such tests.

Any pipe work that is buried or concealed before witnessed pressure tests have been carried out shall be exposed at the expense of the Sub-contractor and the specified tests shall then be applied.

The Sub-contractor shall prepare test certificates for signature by the Engineer and shall keep a progressive and up-to-date record of the section of the work that has been tested.

#### 2.09 Colour Coding

Unless stated otherwise in the Particular Specification all pipe work shall be color coded in accordance with the latest edition of B.S 1710 and to the approval of the Engineer or Architect.

#### 2.10 Welding

#### 2.10.1 Preparation

Joints to be made by welding shall be accurately cut to size with edges sheared, flame cut or machined to suit the required type of joint. The prepared surface shall be free from all visible defects such as lamination, surface imperfection due to shearing or flame cutting operation, etc., and shall be free from rust scale, grease and other foreign matter.

#### 2.10.2 Method

All welding shall be carried out by the electric arc processing using covered electrodes in accordance with B.S. 639.

Gas welding may be employed in certain circumstances provided that prior approval is obtained from the Engineer.

#### 2.10.3 Welding Code and Construction

All welded joints shall be carried out in accordance with the following Specifications:

#### a) Pipe Welding

All pipe welds shall be carried out in accordance with the requirements of B.S.806.

#### b) General Welding

All welding of mild steel components other than pipework shall comply with the general requirements of B.S. 1856.

#### 2.10.4 Welders Qualifications

Any welder employed on this Sub-contractor shall have passed the trade tests as laid down by the Government of Kenya.

The Engineer may require to see the appropriate to see the appropriate certificate obtained by any welder and should it be proved that the welder does not have the necessary qualifications the Engineer may instruct the Sub- contractor to replace him by a qualified welder.

GM/4

# PARTICULAR MECHANICAL SPECIFICATIONS

#### **DESCRIPTION OF SITE**

The contractor is deemed to have visited the site and if unable to locate it or its details apply to the Principal Secretary, State Department for Public Works, Ngong Road, Nairobi.

No claims will be allowed for the traveling or other expenses, which may be incurred by the subcontractor's works. However, the sub-contractor may allow that he may have to, during contract time, do part of the works and therefore three visits may be catered for.

#### **PM/1**

### 1. PARTICULAR SPECIFICATIONS FOR FIRE PROTECTION INSTALLATIONS

#### 1.1: GENERAL

The particular specification details the requirements for the supply and installation and commissioning of a fire protection system which includes **fire sprinklers** and **hose-reel installations**. The Subcontractor shall include for all appurtenances and appliances not necessarily called for in this specification or shown on the contract drawings but which are necessary for the completion and satisfactory functioning of the works.

If in the opinion of the Sub-contractor there is a difference between the requirements of the Specifications and the Contract Drawings, he shall clarify these differences with the Engineer before tendering.

#### 1.2: SCOPE OF WORKS

The Sub-contractor shall supply, deliver, erect, test and commission all the fire sprinklers and hose-reel installations called for in these Specifications and as shown on the Contract Drawings.

#### 1.3: PIPE WORK

The pipe work for the fire protection installations shall be galvanised wrought steel tubing heavy grade Class C to B.S 1387: 1967 with pipe threads to B.S 21. The pipe work and all associated fittings shall be in approved colour for fire fittings.

#### 1.4: PIPE FITTINGS

The pipe fittings shall be wrought steel pipe fittings, welded or seamless fittings conforming to B.S.

1740 or malleable iron fittings to B.S 143.

All changes in direction will be with standard bends or long radius fittings. No elbows will be provided.

#### 1.5: NON-RETURN VALVES

The non-return valves up to and including 80mm diameter shall be to B.S. 5153: 1974. The valves shall be of cast iron construction with gunmetal seat and bronze hinge pin.

#### 1.6: GATE VALVES

The gate valves up to and including 80mm diameter shall be non-rising stem and wedge disc to B.S 5154: 1974 with screwed threads to B.S. 21 tapes thread.

#### 1.7: SLEEVES

Where pipe work passes through walls, floors or ceilings, a sleeve shall be provided one diameter larger than the diameter of the pipe, the space between them to be packed with mineral wool, to the Engineer's approval.

#### 1.8: EARTHING

The fire protection installations shall be electrically earthed by a direct earth connection. The installation of the earthing shall be carried out by the Electrical Subcontractor.

#### PM/2

#### 1.9: FINISH PAINTING

Upon completion of testing and commissioning the fire protection installations, the pipework shall be primed and finish painted with 2 No. coats of paints to the Engineer's requirements/NFPA guidelines.

#### 1.10: TESTING AND COMMISSIONING

The fire protection installations shall be flushed out before testing to ensure that no builder's debris has entered the system. The installation is to be then tested to one and half times the working pressure of the installation to the approval of the Engineer. Simulated fault conditions of the pumping equipment are to be carried out before acceptance of the System by the Engineer.

#### 1.11: INSTRUCTION PERIOD

The Sub-contractor shall allow in his contract sum for instructing of the use of the equipment to the Client's maintenance staff. The period of instruction may be within the contract period but may also be required after the contract period has expired.

The period of time required shall be stipulated by the Client but will not exceed two days in which time the Client's staff shall be instructed on the operation and maintenance of the equipment.

#### **PM/3**

### 2. PARTICULAR SPECIFICATIONS FOR MECHANICAL VENTILATION INSTALLATIONS

#### 1.1: GENERAL

The particular specification details the requirements for the supply and installation and commissioning of a mechanical ventilation system which includes **cyclone ventilators**. The Subcontractor shall include for all appurtenances and appliances not necessarily called for in this specification or shown on the contract drawings but which are necessary for the completion and satisfactory functioning of the works.

If in the opinion of the Sub-contractor there is a difference between the requirements of the Specifications and the Contract Drawings, he shall clarify these differences with the Engineer before tendering.

#### 1.2: SCOPE OF WORKS

The Sub-contractor shall supply, deliver, erect, test and commission all the cyclone ventilator installations called for in these Specifications and as shown on the Contract Drawings.

#### 1.3: CYCLONE VENTILATOR SPECIFICATIONS

#### **PM/4**

### BILLS OF QUANTITIES AND SCHEDULE OF UNIT RATES

## BILLS OF QUANTITIES AND SCHEDULE OF UNIT RATES CONTENTS

CLAUSE No.	<u>PAGE</u>	
1.01 GENERAL NOTES TO TENDERERS	(i)	
1.02 STATEMENT OF COMPLIANCE	(ii)	
2.01 BILLS OF QUANTITIES	M1 t M11	0
2.02 SUMMARY PAGE	M12	
3.01 SCHEDULE OF UNIT	M13	

1.01: SPECIAL NOTES

- 1. The Bills of Quantities form part of the contract documents and are to be read in conjunction with the contract drawings and general specifications of materials and works.
- 2. The prices quoted shall be deemed to include for all obligations under the sub-contract including but not limited to supply of materials, labour, delivery to site, storage on site, installation, testing, commissioning and all taxes (including 16% VAT).

In accordance with Government policy, **3% Withholding Tax shall be deducted** from all payments made to the Tenderer, and the same shall be forwarded to the **Kenya Revenue Authority (KRA)**.

- 3. All prices omitted from any item, section or part of the Bills of Quantities shall be deemed to have been included to another item, section or part there of.
- 4. The brief descriptions of the items given in the Bills of Quantities are for the purpose of establishing a standard to which the sub-contractor shall adhere. Otherwise alternative brands of **equal** quality will be accepted.

Should the sub-contractor install any material not specified here in before receiving written approval from the Project Manager, the sub-contractor shall remove the material in question and, at his own cost, install the proper material.

5. The grand total of prices in the price summary page must be carried forward to the **Form of Tender for the tender to be deemed valid**.

Tenderers must enclose, together with their submitted tenders, detailed manufacturer's Brochures detailing Technical Literature and specifications on all the equipment they intend to offer.

#### **1.02: STATEMENT OF COMPLIANCE**

- 1. I confirm compliance of all clauses of the General Conditions, General Specifications and Particular Specifications in this tender.
- 2. I confirm I have not made and will not make any payment to any person, which can be perceived as an inducement to win this tender.

Signed:	for and on behalf of the	Tenderer
Date:		
Date:		
Official Rubber Stamp:		

(ii) 2.01: BILLS OF QUANTITIES

A) PRICING OF PRELIMINARIES ITEMS.

Prices will be inserted against item of preliminaries in the sub-contractor's Bills of Quantities and specification. These Bills are designated as Bill 1 in this Section. Where the sub-contractor fails to insert his price in any item he shall be deemed to have made adequate provision for this on various items in the Bills of Quantities. The preliminaries form part of this contract and together with other Bills of Quantities covers for the costs involved in complying with all the requirements for the proper execution of the whole of the works in the contract.

The Bills of Quantities are divided generally into three sections:-

#### a. Preliminaries - Bill 1

Sub-contractor's preliminaries are as per those described in section C – subcontractor preliminaries and conditions of contractor. The sub-contractor shall study the conditions and make provision to cover their cost in this Bill. The number of preliminary items to be priced by the Tenderer has been limited to tangible items such as site office, temporary works and others. However, the Tenderer is free to include and price any other items he deems necessary taking into consideration conditions he is likely to encounter on site.

#### b.Installation Items - Other Bills

- The brief description of the items in these Bills of Quantities should in no way modify or supersede the detailed descriptions in the contract Drawings, conditions of contract and specifications.
- The unit of measurements and observations are as per those described in clause 3.05 of the section

#### c. Summary

The summary contains tabulation of the separate parts of the Bills of Quantities carried forward with provisional sum, contingencies and any prime cost sums included. The sub-contract shall insert his totals and enter his grand total tender sum in the space provided below the summary.

This grand total tender sum shall be entered in the Form of Tender provided elsewhere in this document

ITEM	DESCRIPTION	QTY	UNIT	RATE (KSHS)	AMOUN (KSHS
1.0	PRELIMINARIES				
1	Discrepancies clause 1.02	1	Item		
2	Conditions of sub-contract Agreement clause 1.03	1	Item		
3	Payments clause1.04	1	Item		
4	Site location clause 1.06	1	Item		
5	Scope of Contract Works clause 1.08	1	Item		
6	Extent of the Contractor's Duties clause 1.09	1	Item		
7	Firm price contract clause 1.12	1	Item		
8	Variation clause 1.13	1	Item		
9	Prime cost and provisional sum clause 1.14	1	Item		
10	Bond clause 1.15	1	Item		
11	Government Legislation and Regulations clause 1.16	1	Item		
12	Import Duty and Value Added Tax clause 1.17	1	Item		
13	Insurance company Fees clause 1.18	1	Item		
14	Provision of services by the Main contractor clause 1.19	1	Item		
15	Samples & Materials Generally clause 1.21	1	Item		
16	Supplies clause 1.20	1	Item		
17	Bills of Quantities clause 1.23	1	Item		
18	Contractor's Office in Kenya clause 1.24	1	Item		
19	Builder's Work clause 1.25	1	Item		
20	Setting to work and Regulating system clause 1.29	1	Item		
21	Identification of plant components clause 1.30	1	Item		
22	Working Drawings clause 1.32	1	Item		
23	Record Drawings (As Installed) and Instructions clause 1.33	1	Item		
24	Maintenance Manual clause 1.34	1	Item		
25	Hand over clause 1.35	1	Item		
26	Painting clause 1.36	1	Item		

Extended Preliminaries Clause 1.66(see appendix on page C- 24)  Supervision by Engineer and Site Meetings Clause 1.67  Allow for profit and Attendance for the above	1	Item Item	150,000.00	150,000.
page C- 24) Supervision by Engineer and Site Meetings Clause	-	Item	150,000.00	150,000.
` · · ·	1			
Mobilization and Demobilization Clause 1.65	1	Item		
Patent Rights clause 1.64	1	Item		
Temporary Works clause 1.63	1	Item		
Local and other Authorities notices and fees clause 1.60	1	Item		
Attendance Upon Tradesmen, etc. (Insert percentage only) clause 1.58		%		
Initial Maintenance clause 1.42	1	Item		
Storage of Materials clause 1.41	1	Item		
Testing and Inspection – Installation clause 1.39	1	Item		
Testing and Inspection – manufactured plant clause 1.38	1	Item		
	Testing and Inspection – Installation clause 1.39  Storage of Materials clause 1.41  Initial Maintenance clause 1.42  Attendance Upon Tradesmen, etc. (Insert percentage only) clause 1.58  Local and other Authorities notices and fees clause 1.60  Temporary Works clause 1.63  Patent Rights clause 1.64	Testing and Inspection – Installation clause 1.39 1  Storage of Materials clause 1.41 1  Initial Maintenance clause 1.42 1  Attendance Upon Tradesmen, etc. (Insert percentage only) clause 1.58  Local and other Authorities notices and fees clause 1.60  Temporary Works clause 1.63 1  Patent Rights clause 1.64 1	Testing and Inspection – Installation clause 1.39 1 Item  Storage of Materials clause 1.41 1 Item  Initial Maintenance clause 1.42 1 Item  Attendance Upon Tradesmen, etc. (Insert percentage only) clause 1.58  Local and other Authorities notices and fees clause 1.60  Temporary Works clause 1.63 1 Item  Patent Rights clause 1.64 1 Item	Testing and Inspection – Installation clause 1.39 1 Item  Storage of Materials clause 1.41 1 Item  Initial Maintenance clause 1.42 1 Item  Attendance Upon Tradesmen, etc. (Insert percentage only) clause 1.58  Local and other Authorities notices and fees clause 1.60  Temporary Works clause 1.63 1 Item  Patent Rights clause 1.64 1 Item

ITEM	DESCRIPTION	QTY	UNIT	RATE (KSHS)	AMOUNT (KSHS)
	Sub-Total for Preliminaries b/f from Previous Page				
39	Contractor Obligation and Employers	1	Item		
40	Obligation clause 1.69(see appendix page C- 24)	1	Item		
41	Any other preliminaries;				
	i) Continuous Professional Development Courses and registration fees at the Kenya School of Government (KSG),Institute of Engineers of Kenya(IEK) and Engineer's Board of Kenya (EBK)	1	Item	100,000.00	100,000
	Allow for profit and Attendance for item (i) above		%		
	ii)	1	Item		
	Allow for profit and Attendance for item (ii) above		%		
	Total for Preliminaries Carried to Summary Page		70		

ITEM	DESCRIPTION	QTY	UNIT	RATE (KSHS)	AMOUN'
	FIRE PROTECTION SERVICES				
2.10	Fire Sprinkler System for Bale Store				
	Supply, deliver and install the following sprinkler system as described below and shown on the drawings.  All pipework and fittings in this installation to be black				
	steel, class C heavy grade to BS 1387 and fittings to BS 143 to conform to ASTM/ANSI/ASME. Threaded joints shall only be done for pipes of diameter 50mm and smaller. Tenderers must allow in their prices for jointings, couplings, supports, plugging and clamping,				
	reducers, tees, nipples, mortices, pipe sleeves through structural members, etc for proper functioning of the system according to NFPA 13 - 2022 Edition.				
	Associated Pipework Install Galvanised mild steel (GMS) piping and fittings with screwed & socketed joint to heavy grade class "C" to BS. 1387:1967 with pipe threads to B.S. 21. The pipework and all associated fittings shall be in approved colour for fire fittings				
Α	GMS Pipework				
	i) 25mm dia. seamless black steel class C pipe Schedule 40	100	LM		
	ii) 50mm ditto	40	LM		
В	Bends/Elbow				
	i) 25mm diameter bend/elbow	20	No.		
	ii) 50mm ditto	5	No.		
С	Tee				
	i) 25mm diameter tee	20	No.		
	ii) 50mm ditto	20	No.		
D	Reducer Bush				
	i) 25x15mm diameter reducing bush	20	No.		
	ii) 50x25mm diameter reducing bush	20	No.		
Е	Plug				
	50mm dia, plug	3	No.		

	Sprinkler Heads (Nozzles)				
F	Supply and install 15mm diameter automatic sprinkler head, pendant convectional pattern with universal deflector and red bulb for 68oC (degrees Celsius) operating temperature as manufactured by Firekil International or equal and approved. The sprinkler heads shall be corrosive resistant type/ Duraspeed solder type.	28	No.		
G	Ditto but sprinkler heads as spare to be handed over to the client after completion of the entire installations, together with a set of sprinkler spanners, all fixed in a cabinet.	5	No.		
	Sub-total c/f to the next page			•	

ITEM	DESCRIPTION	QTY	UNIT	RATE (KSHS)	AMOUN' (KSHS
	Sub-total b/f from the previous page	-			
Α	200mm diameter manifold to connect pump outlets to 50mm diameter pipe to control valve.	1	No.		
	General Ancillary Items for Pipework				
В	Mount the sprinkler pipe-work to building fabric. Pipework supports and anchoring shall be designed and constructed to NFPA 13 - 2022 Edition. Allow for pipe sleeves through structural walls, beams and columns as per the specifications.	1	Item		
С	Paint the sprinkler pipe-work installation with a coat of red oxide primer, undercoat and two gloss coats to NFPA colour code specification.	1	Item		
	Installation Control Valve Station				
D	50mm diameter Installation Control Valve Station comprising swing check sprinkler alarm valve flanged (PN16) fitted with a butterfly isolation valve, 50mm drain valve, 50mm test valve, air release valve, alarm motor stop valve, alarm motor & gong, retard chamber, manual by-pass valve, strainers and all necessary trim, common key padlocks, pressure gauges and pressure switches to enable the valve to operate, etc, for complete installation to NFPA 13 2002 Edition guidelines. Control valve station must be rated for operation pressures up to 12.5 bar and shall be		No.		

	manufactured by "Angus Fire" or an approved equivalent.			
E	50mm diameter anti-vortex plate (6mm thick) made from brass material.	1	No.	
	Hom brass material.			
F	50mm diameter approved gate valve and its associated unions to BS 5154 PN16 for series B rating with wheel head and joints to steel tubing as manufactured by 'Pegler' or an approved equivalent. The gate valve to have tamper proof fitting (Lockable).	3	No.	
G	25mm diameter high pressure gate valve	3	No.	 
	Sub total off to the next page			
	Sub-total c/f to the next page			

ITEM	DESCRIPTION	QTY	UNIT	RATE (KSHS)	AMOUN (KSHS
	Sub-total b/f from the previous page				
ι Δ	Allow for 200mm diameter strainer for pipe outlet from the water storage tank.	1	Item		
	Working and Record (As-installed) Drawings				

	Prepare and submit <b>three sets</b> of working and record				
	(as-installed) plan and isometric layout drawings to				
	easily readable scale, A1 or				
	A0 paper size format as follows; i) general arrangement drawings of all				
	equipment, plant etc. ii) routes - types and sizes				
	and arrangement of all pipework iii) wiring				
В	(electrical & control) details iv) any other details	1	Item		
	as per specifications Drawings are to be submitted in soft copy (AutoCAD				
	2018 format) & hard copy to the client, the Architect				
	and the Engineer. The soft copies to be stored in a				
	flash disk. Allow for preparation & submitting draft and three final copies of operation, instruction and				
	maintenance manuals to Engineer's approval.				
	Allow for setting to work, testing and commissioning				
С	and labelling of the entire fire sprinkler system to NFPA guidelines and to the satisfaction of the Engineer.	1	Item		
	List any other items necessary for complete installation				
D	of the entire fire sprinkler system;				
	i)				
	ii)				
	iii)				
	iv)				
	v)				
	Sub-Total for Bale Store Sprinklers C/F to C	ollec	tion F	Page	
	<u> </u>				1

ITEM	DESCRIPTION	QTY	UNIT	RATE (KSHS)	AMOUN' (KSHS
2.20	Fire Sprinkler System for Ginning House				

	Supply, deliver and install the following sprinkler system as described below and shown on the drawings.  All pipework and fittings in this installation to be black steel, class C heavy grade to BS 1387 and fittings to BS 143 to conform to ASTM/ANSI/ASME. Threaded joints shall only be done for pipes of diameter 50mm and smaller. Tenderers must allow in their prices for jointings, couplings, supports, plugging and clamping, reducers, tees, nipples, mortices, pipe sleeves through			
	structural members, etc for proper functioning of the system according to NFPA 13 - 2022 Edition.  Associated Pipework Install Galvanised mild steel (GMS) piping and fittings with screwed & socketed joint to heavy grade class "C" to BS. 1387:1967 with pipe threads to B.S. 21. The pipework and all associated fittings shall be in approved colour for fire fittings			
	GMS Pipework			
A	i) 25mm dia. seamless black steel class C pipe	110	LM	
	ii) 100mm dia. seamless black steel class C pipe Schedule 40	70	LM	
В	Bends/Elbow			
	i) 25mm diameter bend/elbow	40	No.	
	ii) 100mm diameter bend	10	No.	
С	Tee			
	i) 25mm diameter tee	10	No.	
	ii) 25x15x25mm unequal tee	15	No.	
	iii) 100mm equal diameter tee	30	No.	
D	Reducer Bush			
	25x15mm diameter reducing bush	20	No.	
	100x25mm diameter reducing bush	30	No.	
Е	Plug			
	100mm dia, plug	3	No.	

F	Supply and install 15mm diameter automatic sprinkler head, pendant convectional pattern with universal deflector and red bulb for 68oC (degrees Celsius) operating temperature as manufactured by Firekil International or equal and approved. The sprinkler heads shall be corrosive resistant type/ Duraspeed solder type.	38	No.	
G	Ditto but sprinkler heads as spare to be handed over to the client after completion of the entire installations, together with a set of sprinkler spanners, all fixed in a cabinet.	5	No.	
	Sub-total c/f to the next page			

ITEM	DESCRIPTION	QTY	UNIT	RATE (KSHS)	AMOUN (KSHS
	Sub-total b/f from the previous page		1		
А	Supply and install 15mm diameter automatic sprinkler head, sidewall sprinkler pattern with universal deflector and red bulb for 68oC (degrees Celsius) operating temperature as manufactured by Firekil International or equal and approved. The sprinkler heads shall be corrosive resistant type and suitable for fixing in basement parkings.	8	No.		
В	Ditto but sprinkler heads as spare to be handed over to the client after completion of the entire installations, together with a set of sprinkler spanners, all fixed in a cabinet.	3	No.		
С	200mm diameter manifold to connect pump outlets to 150mm diameter pipe to control valve.	1	No.		
	General Ancillary Items for Pipework				
D	Mount the sprinkler pipe-work to building fabric. Pipework supports and anchoring shall be designed and constructed to NFPA 13 - 2022 Edition. Allow for pipe sleeves through structural walls, beams and columns as per the specifications.	1	Item		
Е	Paint the sprinkler pipe-work installation with a coat of red oxide primer, undercoat and two gloss coats to NFPA colour code specification.	1	Item		
	Installation Control Valve Station				

F	100mm diameter Installation Control Valve Station comprising swing check sprinkler alarm valve flanged (PN16) fitted with a butterfly isolation valve, 50mm drain valve, 50mm test valve, air release valve, alarm motor stop valve, alarm motor & gong, retard chamber, manual by-pass valve, strainers and all necessary trim, common key padlocks, pressure gauges and pressure switches to enable the valve to operate, etc, for complete installation to NFPA 13 2022 Edition guidelines. Control valve station must be rated for operation pressures up to 12.5 bar and shall be manufactured by "Angus Fire" or an approved equivalent.		No.		
G	100mm diameter anti-vortex plate (6mm thick) made from brass material.	1	No.		
Н	100mm diameter approved sluice valve and its associated unions to BS 5154 PN16 for series B rating with wheel head and joints to steel tubing as manufactured by 'Pegler' or an approved equivalent. The gate valve to have tamper proof fitting (Lockable).	2	No.		
I	Ditto 200mm diameter high pressure sluice valve	1	No.		
J	25mm diameter high pressure gate valve	4	No.		
	Sub-total c/f to the next page			1	

ITEM	DESCRIPTION	QTY	UNIT	RATE (KSHS)	AMOUN (KSHS
	Sub-total b/f from the previous page				
	HP Spectre X360 -14t - ea000 Convertible PC with the following features:				

M9

	A	Windows 10 Pro 64 Intel core i7-1165G7 (upto 4.7GHz,12MB L3 cachhe, 4 cores) + Intel Iris Xe Graphics + 16GB (onboard) 15.6" diagonal, WUXGA+ (1920 x 1280),Touch, IPS, edge-to-edge glass, micro-edge, 1000 nits with integrated privacy screen 1 TB Intel® SSD + 32 GB Intel® Optane™ memory Microsoft® Office 2019 Home and Business 4-cell, 66 Wh Li-ion polymer battery complete with power cable Full-size island-style backlit keyboard HP TrueVision HD IR Camera with integrated dual array digital microphone Intel® Wi-Fi 6 AX 201 (2x2) and Bluetooth® 5 combo (Supporting Gigabit file transfer speeds) HP Rechargeable MPP2.0 Tilt Pen	2	No	
•	В	Allow for 200mm diameter strainer for pipe outlet from the water storage tank.	1	Item	
		Working and Record (As-installed) Drawings			
	С	Prepare and submit <b>three sets</b> of working and record (as-installed) plan and isometric layout drawings to easily readable scale, A1 or A0 paper size format as follows; i) general arrangement drawings of all equipment, plant etc. ii) routes - types and sizes and arrangement of all pipework iii) wiring (electrical & control) details iv) any other details as per specifications  Drawings are to be submitted in soft copy (AutoCAD 2018 format) & hard copy to the client, the Architect and the Engineer. The soft copies to be stored in a flash disk. Allow for preparation & submitting draft and three final copies of operation, instruction and maintenance manuals to Engineer's approval.	1	Item	
-	D E	Allow for setting to work, testing and commissioning and labelling of the entire fire sprinkler system to NFPA guidelines and to the satisfaction of the Engineer.  List any other items necessary for complete installation of the entire fire sprinkler system;	1	Item	
		i) ii) iii)			

Sub-Total for Ginning House Sprinklers C/F to Collection Page					0.00

#### **COLLECTION PAGE FOR FIRE PROTECTION SERVICES**

DESCRIPTION	AMOUNT (KSHS)
l carried forward from Bale Store Sprinklers	
I carried forward from Ginning House Sprinklers	
al for FIRE PROTECTION SERVICES C/F to nmary Page	

ITEM	DESCRIPTION	QTY	UNIT	RATE (KSHS)	AMOUN' (KSHS
3.00	VENTILATION SERVICES				
	CYCLONE VENTILATORS				
	Supply, deliver, install and test the following cyclone ventilators in positions indicated on the contract drawings or as shall be instructed by the Structural & Mechanical Engineers.				
Α	Cyclone Ventilators: Bale Store				
	Cyclone Stainless Steel Roof Ventilator of overall height 580mm, dome dimensions 365 x 700mm (H x W), throat height 215 x 600mm (H x W), complete with the top & bottom plates, Soaker Flange & security frames. To be as 'SuperEco SS' or equal & approved.	16	No.		
В	Cyclone Ventilators: Ginning House				
	Cyclone Stainless Steel Roof Ventilator of overall height 580mm, dome dimensions 365 x 700mm (H x W), throat height 215 x 600mm (H x W), complete with the top & bottom plates, Soaker Flange & security frames. To be as 'SuperEco SS' or equal & approved.	16	No.		
С	Allow for setting to work, testing and commissioning of the ventilation system to the satisfaction of the Engineer.	1	Item		
D	List any other items necessary for complete installation of the entire ventilation system;				
	i)				
	ii)				
	iii)				
	iv)				

Total for Ventilation Services C/F to Summary Page				
v)				

ITEM	DESCRIPTION	QTY	UNIT	RATE (KSHS)	AMOUN (KSHS
4.00	STATIONERY				
Α	Printing Cartridge/Toner				
	i) 1 No. <b>Black</b> Print cartridge code <b>CF259A/59A</b> for HP laserjet Pro M404 printer	2	No.		
	ii) 1 No. <b>Black</b> Print cartridge code <b>CF505A</b> for HP laserjet P2055 printer	2	No.		
	iii) 1 No. Black Print cartridgefor HP laserjet P2015 printer	2	No.		
	v) 1 No. <b>Toner</b> code <b>Tk-8735K</b> for Kyocera Taskalfa 8353ci printer	1	No.		
В	Printing Paper				
	i) A4 Printing Paper (white)	25	ream		
	iii) A4 Letterhead Printing Paper (Cream) as 'Conqueror'	10	ream		
С	Multi-plug extension cable (solatek) with surge protection and four ports.	1	No		
D	Kaspersky Antivirus (1 year, 3 user)	3	No		
	Universal Power Supply (UPS)				
E	UPS with automatic voltage regulation, wall mount holes, audible alarms, UPS power conditions, LED indicators,input power 230V.To be as "APC Easy UPS BV 800VA,AVR, Universal outlet"	1	No.		
	Total for Stationery c/f to Summary Page				

### **SUMMARY PAGE FOR MECHANICAL WORKS**

ITEM	DESCRIPTION	AMOUN (KSI
1	Preliminaries	
2	Fire Protection Services	
3	Ventilation Services	
4	Stationery	
	TOTAL	
	TOTAL FOR MECHNICAL WORKS C/F TO GRAND SUMMARY OF	
	MAIN WORKS	
	in words (Kenya Shillings)	
Tenderei Stamp:	's name and	
Date:	Signature:	
PIN NO. (Provide		
Witness:	Address:	
Date:	Signature:	

## **SCHEDULE OF UNIT RATES**

ITEM	DESCRIPTION	RATE
1	25mm diameter 30 m long swinging type fire hose reel complete with delivery valve, mild steel feed pipe, isolation valve guide, electro-galvanized surface mounted hose reel cabinet in approved colour and all other accessories as "GERMANIA" or equal and approved.	
2	Surface mounted fire hose cabinet manufactured from electro galvanised steel sheet with folded edges and curled hose plate edges and painted with electro static powder coating, 180oC baked. The cabinet size shall be capable of housing hosereel and 3No. portable extinguishers as described in the next page and should conform to BS EN 671-1. To be as Germania or equal and approved.	
3	65 mm diameter, gunmetal gate pattern landing valve with flanged inlet and female instantaneous outlet fitted with plug secured by short chains complete with 65 mm diameter, 20 metres long canvas hose, branch pipe and nozzle.	
4	25mm Air Release Valve	
5	Install a two way Fire Department Connection (Fire Brigade Inlet Breeching Valve) complete with drain valve, check valve, chain & caps for inlets and drain valve. All to be housed in a lockable standard cabinet with 6mm wired glass and identification sign.	
6	65 mm diameter, canvas hose, 30 metres long designed for a bursting pressure of 34bar complete with instantenous coupling.	
7	Twyfords E100 Premium Round close coupled washdown WC suite in white vitreous china with horizontal outlet, E100 Premium round cistern, pan & fittings 4/6 litre BSIO push button complete with quick release family seat and cover, plastic hinges & self closing mechanism, P trap outlet connector, fixing screws and all oher accessories necessary for correct use of the suite	

# TECHNICAL SCHEDULE OF ITEMS TO BE SUPPLIED

**CONTENTS** 

	CLAUSE No.	<u>PAGE</u>	
1.	GENERAL NOTES TO THE TENDERER		MT/1
2.	TECHNICAL SCHEDULE		MT/2

#### **TECHNICAL SCHEDULE**

#### 1. General Notes to the Tenderer

- 1.1 The tenderer shall submit technical schedules for all materials and equipment upon which he has based his tender sum.
- 1.2 The tenderer shall also submit separate comprehensive descriptive and performance details for all plant apparatus and fittings described in the technical schedules. Manufacturer's literature shall be accepted. Failure to comply with this may have his tender disqualified.
- 1.3 Completion of the technical schedule shall not relieve the Contractor from complying with the requirements of the specifications except as may be approved by the Engineer.

#### MT/1

#### **TECHNICAL SCHEDULE**

The tenderer must complete in full the technical schedule. Apart from the information required in the technical schedule, the tenderer **MUST SUBMIT** comprehensive

manufacturer's technical brochures and performance details for all items listed in this schedule (fill forms attached).

TECHNICAL SCHEDULE					
Item	Description	Manufacturer	Country of Origin	Remarks (Catalogue No.etc)	
1	GMS pipes & fittings				
2	Gate Valves				
3	Fire sprinkler (nozzle)				
4	Installation Control Valve				
5	Cyclone Ventilator				

Tenders Must attach Brochures/Catalogues as it will form part of evaluation criteria

# **DRAWING SCHEDULE**

# **DRAWING SCHEDULE:**

As shal	l be <sub>l</sub>	provided	l durir	ng proj	ject	impl	lement	ation.	